

Birla Central Library

PILANI (Jaipur State)

Class No :- 677.28

Book No :- H 76 H

Accession No :- 7370

THE ARTISTIC CRAFTS SERIES
OF TECHNICAL HANDBOOKS
EDITED BY W. R. LETHABY

HAND-LOOM WEAVING



Domestic Loom

From a Lyonnese Woodcut, 1510

*"A winter garment now demands your care,
To guard your body from th' inclement air ;
Soft be the inward vest, the outward strong,
And large to wrap you warm, down reaching
long :*

*Thinly ply your warp, when you the loom prepare,
And close to weave the woof no labour spare.
The rigour of the day a man defies
Thus clothed, nor sees his hairs like bristles rise."*

"The matron cheerful plies the loom at home."

Hesiod "Works and Days"

HAND-LOOM WEAVING,
PLAIN & ORNAMENTAL,
BY LUTHER HOOPER : WITH LINE
DRAWINGS BY THE AUTHOR &
NOEL ROOKE: ALSO SEVERAL
ILLUSTRATIONS FROM ANCIENT
AND MODERN TEXTILES



LONDON
SIR ISAAC PITMAN & SONS, LTD.
PITMAN HOUSE, PARKER ST., KINGSWAY, W.C.2
BATH MELBOURNE

1936

PREFATORY NOTE TO THE 1920 REPRINT

Prefatory Note

It was unfortunate that the first edition of "Hand-loom Weaving" became exhausted at a time when the difficulty of producing such books was almost insurmountable, especially as its success and the increasing demand for it called for an immediate reprint. Happily the lengthy period of delay has come to an end, and the present volume, which is an exact replica of the first edition, except for a page or two of necessary addenda, is now ready for the use of students and others interested in the fascinating textile arts.

The favourable opinions of "Hand-loom Weaving" so generally communicated to the author have been highly gratifying, and have more than compensated for the care and labour bestowed on the preparation of the work. These communications are hereby gratefully acknowledged.

LUTHER HOOPER.

EDITOR'S PREFACE

IN issuing this volume of a series of Handbooks on the Artistic Crafts, it will be well to state what are our general aims.

Editor's
Preface

In the first place, we wish to provide trustworthy text-books of workshop practice, from the points of view of experts who have critically examined the methods current in the shops, and putting aside vain survivals, are prepared to say what is good workmanship, and to set up a standard of quality in the crafts which are more especially associated with design. Secondly, in doing this, we hope to treat design itself as an essential part of good workmanship. During the last century most of the arts, save painting and sculpture of an academic kind, were little considered, and there was a tendency to look on "design" as a mere matter of *appearance*. Such "ornamentation" as there was was usually obtained by following in a mechanical way a drawing provided by an artist who often knew little of the technical processes involved in production. With the critical attention given to the crafts by Ruskin

**Editor's
Preface**

and Morris, it came to be seen that it was impossible to detach design from craft in this way, and that, in the widest sense, true design is an inseparable element of good quality, involving as it does the selection of good and suitable material, contrivance for special purpose, expert workmanship, proper finish and so on, far more than mere ornament, and indeed, that ornamentation itself was rather an exuberance of fine workmanship than a matter of merely abstract lines. Workmanship when separated by too wide a gulf from fresh thought—that is, from design—inevitably decays, and, on the other hand, ornamentation, divorced from workmanship, is necessarily unreal, and quickly falls into affectation. Proper ornamentation may be defined as a language addressed to the eye; it is pleasant thought expressed in the speech of the tool.

In the third place, we would have this series put artistic craftsmanship before people as furnishing reasonable occupations for those who would gain a livelihood. Although within the bounds of academic art, the competition, of its kind, is so acute that only a very few per cent. can fairly hope to succeed as painters and sculptors; yet, as artistic craftsmen, there is every probability that nearly every one who would pass through a sufficient period of apprenticeship to workmanship and design would reach a measure of success.

In the blending of handwork and thought in such arts as we propose to deal with, happy careers may be found as far removed from the dreary routine of hack labour, as from the terrible uncertainty of academic art. It is desirable in every way that men of good education should be brought back into the productive crafts: there are more than enough of us "in the City," and it is probable that more consideration will be given in this century than in the last to Design and Workmanship.



This volume on Weaving, the seventh of our series, is an interesting account of a very ancient and a very remarkable art. With weaving from early days has been associated the making of patterns which repeat a given unit, and the commerce in such fabrics has been the chief means of disseminating patterns over the world. Considering the utility, the universality, and the wonderful nature of the art at its simplest and the splendid triumphs of its maturity, weaving must have a strong claim for being the most extraordinary of man's inventions.

W. R. LETHABY.



ARMS OF THE WEAVERS' COMPANY
LONDON 1700

AUTHOR'S PREFACE

NOTWITHSTANDING the competition of its formidable rival the power-loom, the hand-loom still survives, and seems likely to continue in use for the weaving of the best webs, in several branches of textile manufacture.

Author's
Preface

In various districts of Great Britain, as well as in France, Germany, Italy, and other European countries, hand-loom weaving continues to be, though much decayed, an important industry. In the East—in India, China, and Japan—the hand-loom weavers outnumber by several millions the workers employed in attending to the textile machinery of Europe and America.

The fact that hand-loom weaving has so long survived gives hope, that, now that there is a growing demand for the best in all departments of workmanship, the future may see an extensive revival of this beautiful and ingenious art.

There is more hope for such a revival since numerous handicraft societies and guilds, as well as many independent art workers, have been led to

**Author's
Preface**

study and practise weaving, and have met with much encouragement, both as regards the quality of the work they have been able to produce, and its appreciation by the public.

It is a pity that the introduction of machine spinning and weaving should have had the effect of almost entirely superseding the domestic loom and its auxiliary the spinning-wheel. Spinning and weaving are ideal domestic occupations, especially in the country home. Since they ceased to be universally practised, no home industry at all approaching them in usefulness or interest has taken their place. It is true that some branches of the art, such as the weaving of fine silk into elaborate damasks or brocades, require special training and constant application in the worker. This has always been so ; but the weaving of linen, cotton, woollen, and the coarser silk threads, into materials of strength and beauty for domestic use, can quite well be carried on intermittently together with other household occupations.

There can be no doubt of the superiority of well-made hand-woven webs, whether they be of the finest silk or of the coarsest wool. This is plainly shown if the best hand-made and the best machine-made productions be compared.

Hand-loom weaving, too, is superior to machine-weaving if judged by the effect it is likely to have

on the worker. The hand-weaver is employed in a pleasant, ingenious occupation which exercises all his faculties, while the attendant on a power-loom is engaged in a monotonous toil, in which no quality but intense watchfulness is required.

The object of the present volume is to inform the student of hand-loom weaving of the best methods of preparing warps, fitting up looms, and making or selecting the various appliances necessary for the work, as well as inventing, planning, and weaving plain and ornamental webs. The assistance of the domestic and the artistic weaver has been particularly borne in mind in the preparation of the book.

I hope that this volume will also prove of use to all who are interested in textiles artistically, commercially, or in any other way. The principles of weaving, traced out from their origins, to their greatest perfection in the eighteenth century, are identical with those of the most highly developed modern inventions—inventions which have succeeded in accelerating the speed of weaving at more or less cost to its artistic perfection.

For assistance in the preparation of the book my thanks are due to the authorities of the Victoria and Albert Museum, the National Art Library, and to the authorities of the British Museum, for facilities of research, and for permission to photograph.

**Author's
Preface**

examples of choice textiles, &c., in their various collections ; to Miss Charlotte Brock and Mr. Noel Rooke for valuable assistance in preparing the illustrations, and to Mr. W. H. Abbott, M.A., and other friends for much helpful advice and many practical suggestions.

LUTHER HOOPER

CONTENTS

PREFATORY NOTE	PAGE	
EDITOR'S PREFACE	IV	Contents
AUTHOR'S PREFACE	V	
	ix	

PART I

PLAIN WEAVING

CHAPTER I

THE RUDIMENTS OF SPINNING AND WEAVING

The Comparative Importance of the Weaver's Art—
Scope of Hand-loom Weaving—Weaving Uni-
versal—The Construction of Plain Cloth—The
Warp—The Weft—Relative Size of Warp and
Weft—Preparation of Threads for Weaving—Flax
and its Prehistoric use—Retting and Scutching of
Flax—Preparation of Cotton, Wool, and Silk—
Carding, its Purpose and Method—Fine Spinning
by Machinery—Ancient Spinning with Distaff and
Spindle—The Distaff—The Spindle

i

CHAPTER II

THE INDISPENSABLE APPLIANCES FOR SIMPLE WEAVING

The Origin of the Loom—Looms in Ancient Art and
Literature—Egyptian and Greek Looms—The
Essential Part of the Loom—The Cross in the

Contents

	PAGE
Warp—The Simplest Practical Loom—Demonstration of the Cross—Special Need for the Cross in Long Warps of many Threads—Preparation of the Warp—Ancient Warping—A Simple Method of Warping for Domestic Looms	18

CHAPTER III

THE WARPING BOARD

The Warping Board—The Necessity for Strength in all Weaving Appliances—The Warping Board in Use—Securing the Crosses in the Warp—Warping Several Threads at once—The Reel- or Bobbin-carrier, and its Use in connection with the Warping Board—The Portee Cross—Taking off the Warp—The Hand-stick	28
--	----

CHAPTER IV

THE WARPING MILL

The Warping Mill necessary for Long, Full Warps—Description of the Warping Mill for Silk-weaving—The Bobbin Frame—The Heck-block—Demonstration of spreading a Warp—Regulating the Length of Warps—The Heck—The Gatherer—The Count and Length of Warps; how calculated—Threading the Heck—Beginning a Warp—Taking the Cross—The Ratchet and Wheel of the Heck-block—Mending Threads	42
--	----

CHAPTER V

TURNING ON, OR BEAMING

Turning on, or Beaming—The Raddle, or Vateau—Selection of a Raddle for a particular Warp—The	
--	--

	PAGE	Contents
Cane Roller and Cane Sticks—The Raddle Stand for Small Warps—To separate the Portees—Distributing the Portees in the Raddle—Turning on in the Loom—Position of the Cane Roller in the Loom—Means of turning the Roller—Assistance required in turning on—Method of keeping the Warp Hard on the Roller	60	

CHAPTER VI

THE BEAMING DRUM

The Essential Part of Beaming Machinery—The Drum and its Fittings—Friction Brakes—Ropes of the Drum—Space necessary for Beaming—Importance of Accuracy of Detail in Weaving Operations—Turning-on Posts—Appliance for Beaming in Confined Space—Winding the Warp on the Drum—Beaming with the Drum	73
--	----

CHAPTER VII

THE HAND-LOOM FOR AUTOMATIC WEAVING

Opening or shedding the Warp for Wefting—Shedding the Warp without Appliances—Simplicity of Egyptian and Greek Weaving—The Headle-rod—Ancient Horizontal Looms and Automatic Sheds—Indian and Chinese Looms—The Old English Hand-loom—The Loom Frame—The Rollers—The Ratchet and Wheel—Friction Brake for Cane Roller—Comparison of Indian and English Looms—Automatic Method of opening the Shed—The Long Comb or Reed—The Batten—Position of the Harness and Batten—Preparations for entering the Warp in Harness and Reed—Gating the Loom	81
--	----

Contents

CHAPTER VIII

THE ACCESSORY APPLIANCES OF THE LOOM

	PAGE
The Hand-shuttle—Superiority of Hand-shuttle Weaving—The Fly-shuttle—The Batten for the Fly-shuttle—The Raceboard—The Shuttle-boxes—The Pickers—The Picking Stick—The Action of of the Fly-shuttle—Advantages of the Fly-shuttle—The Temple—The Skein Reels—The Doubler—The Quill-winder—Other Tools—Method of Weaving with Hand-battens—Method of Weaving with Box-battens	III

PART II

SIMPLE PATTERN-WEAVING

CHAPTER IX

TAPESTRY-WEAVING

A Definition of Pattern-weaving—Ancient Textile Decoration—The Origin of Tapestry-weaving—Tapestry a Variety of Plain Weaving—The Effect of tight and loose Wefting—Tapestry-weaving necessarily an Artistic Handicraft—Tapestry akin to Embroidery	131
---	-----

CHAPTER X

THE SIMPLEST WARP AND WEFT EFFECTS OF PATTERN

Further Definition of Pattern-weaving—Patterns possible on the Loom with only Two Headles—The Striped Webs of India—Ancient Use of Striped Cotton Hangings—Patterns resulting from striping the Warp—East African Woven Design—Various	
--	--

Simple Warp Patterns—Simple Weft Effects—
Tartan Patterns—Inlaying or Brocading—Primitive
Indian Brocading—Usual Method of Brocading—
Binders or Ties—Brocading on Weaving Board—
Extra Headle for Brocading—Long and Short Eyes
of Headles—Cashmere Shawl Weaving—Origin of
Brocading

PAGE

Contents

139

CHAPTER XI

SINGLE-HARNESS PATTERNS

Ruled Paper and its Uses—Sketches of Entering and
Tie-up—Designs possible on a Loom with few
Headles—The Position of Cloth in Weaving—
Tying up the Loom—Plan of a Tie-up—Simple
Twills—The Broken Twill, its Importance—Origin
and Peculiarity of Satin-weaving—The Four-headle
Twill—Method of drawing Designs for Simple
Looms—Simple Pattern with Tabby Ground
throughout, its Advantages

160

CHAPTER XII

THE SATINS AND DOUBLE CLOTH

Construction and Utility of Satin Tie—Meaning of
the Term *Satin*—Peculiar Quality of the Satin
Tie—Various Satins and the Number of Headles
required for weaving them—Reasons for weaving
Webs Face Downwards—Exceptions—The Selvages
of Satin and other Webs—Separate Selvages and
their Fitting up—When Separate Selvages are
necessary—Contrast of Colours in Satin Webs and
its Limits—Double Cloth, its Advantages—Pre-
paring and entering the Warp for Double Cloth—
Weaving Double Cloth

179

Contents

CHAPTER XIII

SHEDDING MOTIONS

	PAGE
The Simplest Shedding Motion—Two Typical Shedding Motions—Differences between the Two Kinds of Shedding Motions—Choice of Shedding Motion left to Weaver—Suitable Design for Shedding Motion No. 2	191

CHAPTER XIV

DOUBLE-HARNESS PATTERN-WEAVING

Diaper-weaving—Example—Patterns in Double Cloth—Indian Example—Use of the Figure Harness—Use of the Tabby Harness—Importance of the Two-harness Method of Weaving—The Weaving of Small Damask Patterns with Two Harnesses—Details of Weaving Figured Damask—Analysis of the Effect of the Two Harnesses—Shed-making for Damask Patterns—All Modern Weaving of Pattern based on Two-harness Principles—Weaving from Two Separate Warps—Velvet-weaving and its Methods—Arrangement of the Loom for Velvet-weaving—Actual Process of Velvet-weaving—Principal Tool for Velvet-weaving—Terry Velvet—Superiority of Hand-loom Velvet—Small Designs in Velvet—Tobine Weaving	199
--	-----

CHAPTER XV

AUTOMATIC MACHINES FOR SHEDDING MOTIONS

Automatic Shedding Motions and their Use—Disadvantages of the Jacquard Machine for Home Weaving—Comparison of it with Simpler Machines	xviii
--	-------

—The Jack-in-the-box—Its Inventor—Character of Old Hand-loom Weavers—Tie-up and Working of the Jack-in-the-box—The Drawboy Machine, its Details and Use—Examples of Pattern-weaving with Drawboy	PAGE 229	Contents
--	-------------	----------

PART III

COMPLEX PATTERN-WEAVING

CHAPTER XVI

THE DRAW-LOOM AND THREAD MONTURE

Ancient Origin of the Draw-loom—Its Importance in Weaving—Description of Draw-loom—Building the Monture—The Two Kinds of Repeating Patterns—The Comber-board—The Pulley-box—The Tail Cords—The Simple and Guide Cords—The Term <i>Cords</i> in reference to Design—Rigidity of Lateral Repeats on a Loom—Freedom of Vertical Repeats—The Drawboy—The Drawboy's Fork—The Most Perfect Loom—The Thread Monture—Various Uses of the Thread Monture—Examples of Silk-weaving on Thread Monture	251
--	-----

CHAPTER XVII

THE SHAFT MONTURE

Invention of the Split or Shaft Harness—The Comber-board for Shaft Harness—Building a Shaft Harness—Description of Various Parts of the Harness—The Shaft Harness in Use—Note on regulating the Length of Designs—Draughting Designs—Examples of Shaft-harness Weaving	276
--	-----

Contents

CHAPTER XVIII

BROCATELLE AND TISSUE WEAVING

	PAGE
The Technique of Brocatelle Webs—Weaving Brocates — Draughting for Tissue weaving—Two Methods of mounting Binders—Old Spitalfields Tissue—Broché Tissues—General Utility of Shaft Harness—Shaft Harness for Coarse Materials—Tissues of Wool, Linen, and Cotton on Shaft Harness—Examples of Modern Wool Tissues—Old Method of Tissue weaving without Split Shaft Harness	285

CHAPTER XIX

THE COMPOUND MONTURE

Advantages of dividing the Monture—Description of the Compound Monture—Examples of Compound Monture Weaving—Old English Brocade—Eighteenth-century Striped Brocade—French Late Seventeenth-century Brocade	306
--	-----

CHAPTER XX

FIGURED-VELVET WEAVING

File and Terry Figured Velvet—The Draught—The Monture—The Preparation of the Loom—The Bobbin Frame—Italian and Spanish Velvets	320
CONCLUDING NOTE	322
GLOSSARY	325
INDEX	331

LIST OF PLATES

PLATE		FACING PAGE
I.	East African Weaving, illustrating Primitive Work <i>British Museum, London</i>	1
II.	Ancient Egyptian Weaving, B.C. 2000 and later. The heavy comb shown was used for beating the woof together <i>British Museum, London</i>	7
III.	Illustration of Warp and Weft intersected	10
IV.	Fragments of Linen Cloth, woven by the Pre-historic Lake-dwellers of Switzerland <i>British Museum, London</i>	16
V.	Figure of a Spinster. Vase Painting of Ancient Greece, B.C. 500 <i>British Museum, London</i>	17
VI.	Spindles, Whorls, and Loom Weights, Ancient Greece <i>British Museum, London</i>	32
VII.	Tapestry Ornaments. Fragment of a Robe of Amenhetep II., found in the Tomb of Thothes IV. Amenhetep, whose Ka name is woven in the design, reigned in Egypt, B.C. 1500 <i>Cairo Museum</i>	129
	FRONTISPIECE TO PART II.	
VIII.	Copy (in progress) of a Portion of the East African Web, illustrated by Plate I. <i>By the Author</i>	144

PLATE	FACING PAGE
IX. Piece of Eighteenth-century Silk-weaving, illustrating <i>Tobine Stripes</i> <i>Victoria and Albert Museum, South Kensington</i>	248
X. Fragment of Seventeenth-century French Brocade, a most perfect specimen of the Weaver's art <i>Author's Collection</i>	249
FRONTISPICE TO PART III.	
XI. Example of French Silk-weaving, time of Louis XIII. Size of design, 30" x 21" <i>Victoria and Albert Museum, South Kensington</i>	273
XII. Copy, by the Author, of Eighteenth-century Fine French Silk. A portion of the design only is shown. The part photographed is the full size of the original	288
XIII. Copy, by the Author, of Sixteenth-century Italian Brocatelle. A portion of the design only is shown, about half the actual size of the original	289
XIV. Spitalfields Tissue in Green and Gold Silk. Date about 1900 <i>The Author's Collection</i> <i>This is shown as an example of skilful weaving, not of fine design</i>	291
XV. Wool Hanging designed, draughted, and arranged for weaving by the Author for St. Christopher's Church, Haslemere. The colours are scarlet, blue, green, and white	302
XVI. Portion of Hanging of woven wool and coarse silk. Designed, draughted, and arranged for weaving by the Author	304
XVII. Brocade, probably Old English. The lower portion of the photograph shows the method of brocading with small shuttles at the back <i>Author's Collection</i>	311
XVIII. Figured Velvet. The ornament is composed of cut and terry pile. This specimen is beautifully designed and perfectly woven <i>Victoria and Albert Museum, South Kensington</i>	314

PART I
PLAIN WEAVING




Plate I.—East African Weaving, illustrating
Primitive Work.

See page 3.

British Museum, London.

PART I

PLAIN WEAVING

CHAPTER I

THE RUDIMENTS OF SPINNING AND WEAVING

The Comparative Importance of the Weaver's Art—Scope of Hand-loom Weaving—Weaving Universal—The Construction of Plain Cloth—The Warp—The Weft—Relative Size of Warp and Weft—Preparation of Threads for Weaving—Flax and its Use Prehistoric—Retting and Skutching of Flax—Preparation of Cotton, Wool, and Silk—Carding, its Purpose and Method—Fine Spinning by Machinery—Ancient Spinning with Distaff and Spindle—The Distaff—The Spindle.

It may be confidently affirmed that the art of weaving occupies a place of importance and usefulness to mankind second only to that of agriculture. We shall reach this conclusion whether we take into consideration the number of persons engaged in the various branches of the art, the universal practice of weaving in ancient and modern times, or the necessity and value of the productions of the weaver's craft and industry to society in general.

The Scope
and Value of
the Weaver's
Art

The Scope and Value of the Weaver's Art If necessary it could be proved by statistics that at least one-fifth of the working world is occupied either with weaving and its allied trades, or in the distribution of its finished materials. It would be found also that a similar proportion of the general expenditure is for woven goods of one kind or another.

It is not only, however, from an economic point of view that the art of weaving is of such interest and importance, but also on account of the vast amount of invention and ingenuity, both of a mechanical and an artistic kind, that it has been the means of calling forth. These qualities have been shown during the course of its development from the elementary and laborious attempts of primitive tribes to the elaborately finished and swiftly wrought, though complicated webs woven on the modern power-loom. It is this aspect of the subject—viz., the development of textile art from its earliest beginnings—that the present volume is intended to set forth. A clear account of the principles and practice of the art of weaving, and the possibilities and limitations of the loom and its accessories, cannot fail to be of interest and value to the antiquary and to the collector of ancient textiles, as well as to the designer, the weaver, the distributor, and the purchaser of the various kinds of modern woven fabrics.

Possibilities of Hand-loom Weaving It will not be necessary, nor, indeed, would it be possible within the compass of this handbook, to follow the subject of weaving beyond the point when it ceased to be a handicraft, owing to the introduction of the Jacquard machine and the application of steam-power to the loom, which

events took place at the end of the eighteenth century. These changes in the construction and mechanism of the loom did not alter the principles of weaving in the least, nor add any new effects of combinations of threads to those previously in use. The inventions only affected the exactness and speed of the weaving, the motive power by means of which the loom was driven, and rendered easy a frequent change of pattern. No real advance in weaving technique has taken place for a hundred years, as nothing more perfect is possible in the weaver's art than the sumptuous webs of silk, of exquisite texture, which were deliberately woven by hand on the perfected draw-loom of Europe during the seventeenth and eighteenth centuries.

Possibilities
of Hand-
loom
Weaving

The first principles and practice of the art of weaving, wherever they are found, are universally similar. Primitive peoples of to-day follow the same methods and use the same appliances as those of ancient times. And as it is on these that all later textile developments are based, it will be necessary in the first place to define them clearly. A visit to the ethnographical department of any of our museums, and an examination of their contents, will prove that there is scarcely a savage tribe, however primitive, which has not some more or less proficient acquaintance with the art of making thread and of utilising it in the weaving of cloth (see plate I). Also, the specimens of ancient handicraft, such as those shown in plate II, which remain to us, as well as other less direct evidence, will show decidedly that the people of antiquity were familiar with the arts of spinning

Universality
of Weaving

Universality of Weaving and weaving, which they practised with a great deal of skill and carried to a high pitch of perfection. Indeed, so universal and so ancient are the occupations of making thread and weaving webs that they appear to be instincts as natural to the human species as to the caterpillar and the spider.

The Construction of Plain Cloth If we look carefully at a piece of plain cloth we find it to consist of a number of longitudinal threads placed side by side, and intersected, or interlaced, by a continuous single thread. This thread passes alternately before and behind the longitudinal ones, and has been introduced between them from edge to edge, by some means and in such a manner as to bind them together and hold them in position. When thus united the threads are woven into a flat, orderly, and uniform-surfaced material, of more or less durability, according to the strength of the threads of which it is composed and the closeness and evenness with which the crossing thread has been pressed down and beaten together. By means of plate III the arrangement of the longitudinal threads and the continuous thread crossing and intersecting them should be made quite clear. The longitudinal threads of a woven material are always called the *warp*, because, in order to allow of their being intersected conveniently by the continuous crossing thread, they have to be *warped*—that is, tightly strained in their position on some kind of frame prepared for the purpose. The longitudinal threads are known as the *warp* and by no other name, but the continuous crossing thread has several technical names, the most usual being

The Warp

The Weft *weft*, *woof*, or *shoot*—sometimes spelt *shute*.

In the magnified piece of plain cloth (plate III) the warp threads are seen at once to be much finer than the weft thread. This is always the case, except in the most elementary attempts at weaving. And the threads differ not only in size, but in the manner in which they are prepared for use. The warp threads need to be hard, having thin strands strongly twisted together. The weft thread is only slightly twisted ; this makes it soft and yielding, and enables the weaver to press it well down and to beat both warp and weft together into firm, good material. The selection of properly proportioned threads is of the highest importance in weaving, for the good appearance of the finished work depends almost entirely upon it, as also does its durability.

The Relative
Size of Warp
and Weft

The simple methods and appliances for making thread and weaving adopted by different ancient peoples and by primitive tribes of to-day are remarkably similar in kind. But the raw materials used and the manner of preparing them differ considerably, and depend, of course, on the natural products with which the particular people happen to be familiar, and the inventive skill which they possess. The most obvious and simple of all raw materials for weaving were the long grasses and rushes, or other plants, with which the weaver was acquainted, which could be readily split into filaments or used entire. But the rudest people readily become aware that many animal and vegetable substances are capable of being drawn out and twisted together into a continuous thread, of more or less firmness and strength, and they accordingly soon invent for themselves some simple appliances for performing this operation.

Various
Threads and
their
Preparation
for Weaving

Flax and its
Preparation
Prehistoric

Previous to the introduction of cotton from India and the marvellous development of the cotton industry in this country during the last century, the most important of all the various kinds of thread for weaving purposes was obtained from the stems of the family of plants known as the *Linum* family, of which the flax has always been the chief member. Animal wool and silk—the only natural continuous thread—have been chiefly used for ornamental fabrics, but flaxen or linen thread has always been the most used and the most useful for ordinary purposes. The earliest specimens of knitted and woven thread at present known are fragments that were found amongst the remains of the lake-dwellings in Switzerland, and which are attributed ; by the most reliable authorities, to the age of stone. These venerable relics are therefore prehistoric. They consist of small bundles of flax fibre, both raw and twisted into threads of various thickness. Some are made into ropes and nets and others knitted or woven into pieces of cloth (see plate iv). In Egypt, in Greece and Rome, and, with one or two exceptions, in all the more or less civilised countries of the ancient world, flax was used and preferred above all other fibres for weaving purposes. It is remarkable that the cultivation and preparation of flax, even at the present day, is almost identical with that in use in ancient Egypt four or five thousand years ago. Probably the reason why cotton has, within the last century, almost superseded the use of linen, is because it is better adapted for preparation and weaving by machinery and takes more kindly to all sorts of abominable adulteration, so that it can be more cheaply put upon the market.



Plate II.—Ancient Egyptian Weaving, 2,000 B.C. and later. The heavy comb shown was used for beating the wool together.

See page 3.

British Museum, London

The valuable portions of the flax plant are the dark brown seeds, usually called *linseed*, and the inner fibres of the stems, which by a severe course of treatment become linen thread. After the flax has been pulled up by the roots the seeds are first shaken out. The plants are then made up into small bundles and immersed in water until they begin to ferment. As soon as the fermentation has begun they are taken out of the water and allowed to dry in the open air. This process is called *retting*, and when it is complete the leaves and outside membrane of the stem are easily removed. The roots and small stems are next cut away, and the main stems are then ready for the next operation, called *skutching*. The purpose of the skutching process is to thoroughly clear away all remains of the outer membrane and the short, useless veins of the leaves, and to straighten out the inner fibres and lay them all in

Flax.

Flax and its Preparation



FIG. 1
Flax Plant

Flax and its Preparation one direction ready for twisting into thread. Sharp toothed combs of various sizes are used for this



FIG. 2.—Stripping Hemp in Burgundy.

skutching, coarse ones at first and finer ones afterwards. The fibres are finally made up into convenient bundles. By this process the filaments of

the flax are thoroughly cleaned and separated, and converted into a fine, silky kind of tow. This, in brief, is the manner in which the best flax is prepared for the linen thread of to-day, and there is evidence to show that it was in just such a manner that the flax was prepared for the thread of the state robe of "fine linen" given by Pharaoh to Joseph in ancient Egypt as a mark of his royal favour.

Flax and its
Preparation

The down of the cotton plant and the fleece of the sheep need much less preparation than the fibre of the flax. The former only have to be cleaned and the fibre cleared by the process of *carding*, which will presently be explained, and the cotton or wool is ready to be operated upon by the *spinster* who makes it into thread.

The
Preparation
of Cotton
and Wool

Silk is produced ready spun by the silkworm in a continuous double thread, and only requires to be unwound from the cocoon, as the case is called which the caterpillar twists and winds curiously around itself when ready to change into the chrysalis form. When unwound the cocoon is found to consist of a continuous double thread of silk about one thousand yards in length, but of such exceeding fineness that it takes from ten to twelve hundred cocoons to weigh one pound. So fine, indeed, is the natural filament that twelve strands have to be twisted together in order to make the finest thread of silk that it is practically possible to use for weaving. The twisting and cleaning of these threads of silk is technically called *silk-throwing*, and is a most delicate and elaborate process.

Silk Thread
produced
by the Silk-
worm
ready spun

The operation of carding by hand requires the use of a pair of implements called *cards* (fig. 3A).

Carding

Carding

FIG. 3.




FIG. 3A.—Pair of Cards.




Plate III.—Illustration of Warp and Weft intersected.

See page 5.

They are made of hard wood, and each has one of its flat surfaces covered with tough leather, into which a large number of points of thin steel wire have been very strongly and evenly fixed. A small quantity of clean cotton down or fleecy wool is spread as evenly as possible on the steel points of one card. This card is then held by the handle, with the points upward, in the left hand of the operator, who sits to the work and rests the implement flat upon her knee. The other card is then taken in the right hand, and its points pressed firmly down upon the fibre to be carded. The right-hand card is then drawn smartly over the left-hand one in the direction shown in fig. 3, which movement tears the fibres apart and straightens them out. When this action has been repeated a few times the straightened fibres will be found lightly attached to one edge of the lower card. They can then be transferred to the smooth back of the other card, and with a few deft taps of the back edge of the one from which they were taken, may be made to assume the curled shape shown at the foot of fig. 3A. When it has been worked into this neatly curled form the carding is ready to be drawn out and twisted into thread.

Carding

Spinning, as its name denotes, is the process by which the short filaments that have been separated and combed into order by the carder or skutcher, are drawn out and joined by being twisted or spun together into a continuous thread, or *yarn*. This yarn can be spun to an astonishing degree of fineness. The finest ever known to be made was spun by machinery and shown at the great Exhibition

Spinning

Spinning of 1851. It was a cotton yarn, and a single pound of it, it was said, would measure one thousand and twenty-six miles in length. This yarn was only made for exhibition, and was of no practical use. The finest cotton yarn used in weaving is spun by machinery, and *runs*, as it is called, three hundred miles to the pound weight. Needless to say, the ancient method of spinning by hand could never produce a thousand miles of thread from a single pound of cotton, but the hand-spinners of India spin, for use in the Dacca muslin industry, one pound of cotton fibre into a length of thread which measures two hundred miles. The Eastern spinners can also spin wool or flax into yarn of a hundred miles to the pound weight. These figures have been approached if not quite reached by good spinsters of Europe.


Spinning
with Distaff
and Spindle

The figure of a spinster (plate v) is copied from a painting on a Greek vase preserved in the British Museum. It gives a fairly good general idea of the method of spinning by the primitive means, viz., by the use of the *distaff and spindle*. It is not wise, however, to put much faith in the details of ancient pictures of this kind, as we shall have occasion to notice particularly when we come to consider the representations of ancient looms. Artists and poets, in ancient times, seem to have been content if they succeeded in conveying a general impression of a figure or scene they intended to represent, without much regard to accuracy of detail. In this case the graceful figure is holding up a stick, the distaff, on which a tightly wound ball of thread is fixed; and at the end of the thread, which passes through the right hand of the figure,

a spindle is turning. All that we can learn from this figure is that the distaff and spindle were used in ancient Greece for the purpose of making thread, but neither the details of the process of spinning are explained nor is the position or action of the figure suitable for the work. When only the distaff and spindle are used for spinning, the distaff is usually fixed under the spinster's left arm, so that the prepared flax, loosely wound upon its end, may project in front of her. By this method of fixing the distaff the hands of the spinster are both left free, the one to twist the thread and the other to keep the spindle duly rotating.

The *distaff* (fig. 4) is simply a round stick of wood about fifteen or eighteen inches in length, at one end of which the flax, or other raw material prepared for spinning, is loosely wound in such a way that

Spinning
with Distaff
and Spindle



The Distaff

FIG. 4
The Distaff


The Distaff



FIG. 5.—Spinning with Distaff and Spindle.

the fibres can be readily drawn out and twisted together by the spinster. The distaff is sometimes, although not generally, used for cotton and wool—these are for the most part spun from the cardings, which are joined on as required ; but the distaff is always used for the spinning of flax. When the distaff is fitted up, or the cardings ready to the spinster's hand, she deftly draws out a few filaments, sufficient, in her judgment, for the thickness of the thread required, and gradually twists them into an even thread without detaching them from the distaff or carding. When a sufficient length of thread is thus twisted it is attached to the spindle, which is then made to revolve, and as it spins it assists in evenly twisting the gradually drawn out thread. As the length of thread increases, the twisted yarn is wound upon the spindle from time to time, until it is conveniently full ; then the thread is cut, and a fresh spindle attached in place of the full one (fig. 5).

The spindle (fig. 6) is simply a slender metal or hardwood rod, from six to ten inches in length, having at one end, or in the centre, a round weight, and at the other end a hook, or notch, for the purpose of holding it in a vertical position



The Distaff

The length of thread indicated by the break at A is about half a yard.

The Spindle

Fig. 6.—A Spindle.

The Spindle



FIG. 7.—Spinning with Wheel.



Plate IV.—Fragments of Linen Cloth, woven by the Pre-historic Lake-dwellers of Switzerland.

See page 6.

British Museum, London.



Plate V.—Figure of a Spinster. Vase Painting of Ancient
Greece, 500 B.C.

See page 12.

British Museum, London

when the thread is attached to it. Spindles are of various weights and dimensions, according to the size of the yarn for the spinning of which they are used. Plate VI shows ancient spindles preserved in the British Museum. The Spindle

This method of spinning with these simple appliances, the distaff and spindle, seems to have been universal. It is still used by primitive peoples, and the best, strongest, and most durable thread is even now produced by its means. The method also illustrates perfectly the essential principles of the making of all thread. The use of machinery for spinning, whether it be only the simple, picturesque, mediæval spinning wheel (see fig. 7), or the elaborate machinery of the cotton-spinning industry of the nineteenth century, did not alter the principles of the process in the least. These only enabled the work to be carried out with increased speed and with greater exactness of result.

CHAPTER II

THE INDISPENSABLE APPLIANCES FOR SIMPLE WEAVING

The Origin of the Loom—Looms in Ancient Art and Literature—Egyptian and Greek Looms—The Essential Part of the Loom—The Cross in the Warp—The Simplest Practical Loom—Demonstration of the Cross—Special Need for the Cross in Long Warps of many Threads—Preparation of the Warp—Ancient Warping—A Simple Method of Warping for Domestic Looms.

Origin of the Loom

THE weaving of mats and baskets from natural grasses and rushes can, of course, be manipulated without the use of any special appliance for holding or stretching the materials whilst in working. But as soon as pliant thread has to be woven, and any considerable length of web is required, it becomes necessary to devise some kind of frame to hold and stretch the warp threads upon, so that the weft may be readily interlaced with them. The more or less elaborate frame constructed for this purpose, with the properly arranged warp mounted on it, together with the various contrivances added from time to time by the weaver's ingenuity, has by universal consent been called a *loom*.

The representations of looms in ancient sculp-

tures, paintings and drawings, are exceedingly scarce, and what few there are, are for the most part so incomplete, not to say incorrect, in detail, that it is difficult for the most expert weaver to see how they could have been used effectively. Textile art seems to have been a more attractive and interesting subject to the ancient poets than to the artists, as their allusions to the loom, the needle and the various operations of weaving and needlework are frequent and interesting, and prove beyond doubt that the weaver's and embroiderer's occupations were held in very high estimation and were very extensively practised in the ancient world. These literary allusions to the loom and to textile art will be considered in a subsequent chapter, but a reference to the available pictorial representations is necessary at this point.

The most ancient illustrations of looms and weaving are to be found amongst the wall-paintings in a tomb at Beni Hasan, in Egypt. Fig. 8 represents a warp apparently stretched on the ground, and a figure in an impossible attitude weaving what may be supposed to be a mat. Fig. 9 shows an upright frame having a few threads fixed to it, at which two women are working. One of the women may be presumed to be introducing the weft between the warp threads, and the other beating it together. A later Egyptian painting represents a loom of more elaborate construction (fig. 10). This painting is at Thebes, and shows a weaver very actively at work at an upright frame, on which he is evidently weaving cloth by means of a stick having a hook at its end. No threads, however, in this instance are shown, either of warp or weft. These are all the instances

The Loom
in Ancient
Art and
Literature

Egyptian
Looms

Egyptian Looms

at present discovered of representations of Egyptian looms, except that there is a kind of hieroglyphic on a sarcophagus of an early period which is supposed to stand as a sign for a loom, or weaving. The scarcity of these pictorial records is remarkable when we consider that Egypt was the seat of a great




FIG. 8.—Egyptian Loom.

linen-weaving industry, which not only supplied the large domestic market with woven materials, but was famous throughout the ancient world for the manufacture of "fine linen," and exported great quantities of it to contemporary nations with whom the Egyptians traded.

Although in ancient Greece and Rome weaving was a common domestic occupation universally practised, as we gather from many classic literary allusions, drawings or other representations of looms seem to be even more rare than are those of Egypt. It appears that only in two Greek vase-paintings is there anything of the kind to be found. One of these (fig. 11) represents the loom of Penelope, and the other that of Circe (fig. 12). They are

Greek Looms

both upright looms, and differ from those of Egypt in that the warp strings are stretched by means of a weight being hung on each separate string, instead of the threads being tightly stretched all together on the frame, as were those of Egypt.

Greek Looms




FIG. 9.—Egyptian Loom.

There are a few other ancient drawings extant, purporting to be of Roman looms, but these are absolutely unreliable, as they are from Byzantine and Eastern manuscripts of later periods, and only show the kind of weaving appliances in use at the time when, and in the places where the drawings were made. In all these ancient pictures of looms the artists have shown the stretched threads of the warp, and suggest the insertion of the weft thread. We can also gather that, owing to the

What may
be learned
from Ancient
Pictures of
Looms

different methods of stretching the warp peculiar to Egypt and Greece, the Egyptians beat the weft together down from *above*, whilst the Greeks beat




FIG. 10.—Egyptian Loom.

theirs up from *below*. This is an important difference, and was noticed by the Greek historian Herodotus when he visited Egypt. Beyond these meagre details we can learn nothing definitely from the ancient pictures. We may conjecture and

argue, as learned authors and antiquarians are constantly doing, as to the methods by which the ancient weavers obtained the fine results which they certainly did, but the pictures are no help in the matter to anything beyond conjecture. It is

What may
be learned
from Ancient
Pictures of
Looms



FIG. 11.—Greek Loom.

remarkable that all the artists have neglected to observe and show one simple but universal and indispensable contrivance used in weaving, the ONE thing we know must have been there, and without which no loom, however simple or complicated, could be set to work or kept in order by the weaver.

By means of fig. 13 the nature and value of this simple but essential part of the loom can be readily explained. The figure represents a board, which may

The Essen-
tial Part of
a Loom

The Essen-
tial Part of
a Loom

be of any convenient size ; for the present purpose we will say it is four inches wide by sixteen inches long. The construction is shown at no. 1. At the ends A, a and b, B a piece of beading, having a rounded edge, is fixed. The beadings are four and a half inches long, so that when fixed on the ends of the board they project slightly beyond its edges. No. 2, is a section of the board, showing the position of the rounded edges of the beadings. This



FIG. 12.—Greek Loom.

The
Simplest
Loom

Practical
Demonstra-
tion of the
Cross in the
Warp

board, when fitted up with a warp, is perhaps the simplest possible form of loom. But notwithstanding its simplicity many beautiful and ingenious narrow webs suitable for braiding and other trimmings may be made on it, as will be shown in a subsequent chapter. At no. 3, the board has a string wound upon it lengthwise. In this case it is wound so as to make a warp of nine strings, but these may be of any number possible to the width of the board. Before the string is wound on to the board a loop is made at its end, which is caught on to the projecting end of the beading at A, no. 2. The string being looped on to the beading, the winding proceeds, and when the desired number of strings is complete the string is carried down the back and tied to the other

projecting end of the beading B. At no. 4, the strings on the board are shown intersected by the two rods C, in such a way that alternate strings go over and under each rod. In the space between the rods, the alternate strings cross each other in regular succession. This cross is clearly shown in the diagram between

Practical
Demonstra-
tion of the
Cross in the
Warp




FIG. 13.—Cross in the Warp.

the points marked C, D. It will now be understood that whilst the rods C, are kept in their position in the warp, it is impossible for the threads to get out of place or to get hopelessly entangled, as they otherwise would certainly do. This cross in the warp, sometimes called the *lease*, is really the one indispensable part of the loom. It is no doubt prehistoric, and is universally used in weaving. All other parts and appliances of the loom may vary,

**The Cross
in the Warp** and be of either the most complicated and elaborate or of the rudest possible description, but this simple yet perfect contrivance for keeping the warped threads in order cannot be dispensed with, and is never likely to be superseded.

**Special Need
of Cross in
Long Warps
of many
Threads** The difficulty of keeping the warp from getting entangled when only a few threads are used in it, and when the finished work is not required to be longer than the loom itself, is not so very apparent. But when in place of the fixed bars, or other limits between which the warp is stretched, rollers are used, and it is desired to make several yards of material, and, added to this, the warp is to consist of a great number of fine threads, the difficulty, it is clear, will be considerably increased, and, but for the contrivance of the crossing of the alternate threads of the warp, as described above, would be found to be insurmountable. This would especially be the case with warps many yards in length, consisting as they often do of several hundreds of threads of fine linen, cotton, or wool, or, it may be, of several thousands of threads of fine silk.

**Preparation
of the
Warp** A length of warp much longer than the loom itself cannot, of course, be prepared upon it, as a short one may readily be. This being the case, some contrivance has to be resorted to in order to build up a series of threads of exactly the required number, and of the length determined upon; and not only this, but to keep the threads as nearly as possible at the same tension, so that when transferred to the loom and stretched between its front and back rollers they shall give the weaver as little trouble as possible with loose and uneven threads. This process of preparing the threads for the loom

is, obviously, called *warping*, and is a very important one, requiring great exactness and care in the doing—as, indeed, may be said of all the operations connected with weaving, from beginning to end.

Preparation
of the
Warp

The ancient method of warping, a method that is still practised in India, where weaving as a simple domestic art still survives, is as follows. A row of sticks in pairs, fixed upright in the ground, is set out, of the required length. The warper, holding two reels of thread, in such a way that they will readily unwind, ties the thread to the first pair of sticks, and then passes along the line from end to end, backwards and forwards, crossing the threads at each pair of sticks, in order to keep the tension even. When he has the required number of threads piled upon the sticks, he inserts a cord in the place of the last pair but one, at both ends of the row, tying it up securely so that it cannot slip out of the cross. Finally he binds the warp firmly together at both ends, looses it from the sticks, and winds it upon a hand-stick, or rolls it into a ball convenient for carrying it to the loom and turning it on to the rollers.

Ancient
Warping

A more compact and convenient, though similar, method of warping to the ancient one, is by means of a board fitted up with a number of pegs, in place of the row of sticks planted in the ground. As this is a very easy and effective way of warping a moderate number of threads, such as would be required for a domestic loom, and at the same time perfectly illustrates the principles of warping, which it is necessary for the student of weaving to understand clearly and definitely once for all, it will be well in the next chapter to carefully describe it and demonstrate its use.

A Simple
Method of
Warping

CHAPTER III

THE WARPING BOARD

The Warping Board—The Necessity for Strength in all Weaving Appliances—The Warping Board in Use—Securing the Crosses in the Warp—Warping Several Threads at Once—The Reel- or Bobbin-carrier, and its Use in connection with the Warping Board—The Portee Cross—Taking off the Warp—The Hand-stick.

The
Warping
Board

THE board with its arrangement of pegs for warping is shown in fig. 14, nos. 1, 2, and 3. It may be of any convenient size, according to the place where it is fitted up, but it should not be less than six feet long by one foot broad, and it must hang firmly on a wall at such a height from the ground that the operator can reach to any part of it without difficulty. On a board of the size indicated a warp of ten yards in length, and of any reasonable number of threads, can quite easily be warped. A longer length may be warped either by increasing the length of the board or by increasing its width and adding to the number of pegs with which it is furnished. One peg added below each of the pegs 2, 3, and 4, will add four yards to the length possible to be warped on the board. The pegs, indicated by the letters and

numerals, must not be less than six inches long, and not more than nine inches in projection from the surface of the board. The pegs must be made of The Warping Board






FIG. 14.—Warping Board.

hard wood, not less than one inch in diameter, as they have to bear a great strain when some hundreds of threads are stretched upon them, and they must be well made, be perfectly smooth and have nicely rounded ends. The board itself must also

The
Warping
Board

Necessity
for Strength
in all
Weaving
Appliances

The Board
in Use

be strong and smoothly finished, and must not be less than one inch in thickness if six feet in length, and an inch and a half, if longer. It may be remarked here—and it cannot be with too much emphasis—that, EVERY APPLIANCE CONNECTED WITH THE LOOM REQUIRES TO BE MUCH STRONGER THAN WOULD AT FIRST APPEAR NECESSARY. THE WEIGHT OF THE REPEATED BEATING OF THE WEFT TOGETHER, AND THE MULTIPLIED STRAIN OF THE MANY THREADS OF WARP, ARE MUCH GREATER THAN WOULD BE SUPPOSED. The pegs marked A and E, and filled in solid black, must be movable, but all the others should be firmly fixed in the board. The space between the pegs A and B must not be less than one foot, and the space between B and C six inches. The space between pegs D and E should also be one foot.

The board being ready and fixed in its place on a wall, we may now proceed to use it. We will suppose that we require quite a small warp, of say twenty threads, ten yards long. We take a reel of thread and, placing it on a short rod of thick wire, in order that it may turn freely, we begin operations by tying one end of the thread to the movable peg A (no. 2, fig. 14). Now, holding the wire with the reel on it in our left hand, with our right hand we guide the thread *under* peg B and *over* peg C. Then, following the dotted line shown, we carefully guide the thread outside pegs 1, 2, and 3 back to peg 4, then to pegs 5, 6, and 7 in succession until it reaches peg D, which it goes *under*. The thread must now be carried *over* and *under* peg E, and thus begin its return. Before returning, however, it will be well to compare the

thread on the board with the dotted line of the drawing, in order to make sure that we have exactly followed in its course. Having ascertained that all is well, we may now carry the thread *over* D on to peg 7, and so back in the same course till we again reach peg 1. Having carried the thread over peg 1, it must be taken *below* C over B and arrive *below* A; this will complete one course. We have now warped two threads, and the warping board should be as represented at no. 3, with the threads crossed between pegs B and C, and D and E. Taking into consideration the size of the board, it is clear that we have warped two threads of a length of ten yards between the two crosses. The second thread being carried round and over peg A, goes *under* B, following exactly the course of the first thread, and duly arrives at E; then, following the second thread back, it reaches A, goes under and over the peg, and four threads, out of the twenty required, are warped. By the time ten forward and ten backward journeys are made our sample warp of twenty threads will be finished, and may be removed from the board as soon as the crosses we have taken so much trouble to make are secured. This important matter of securing the crosses is easily done, but if forgotten, and the warp be removed from the board, it will be irretrievably spoiled, especially if it consists of a great number of fine threads. Not only the labour, but the thread itself will be wasted. Fig. 15 will make clear the method of operation. The letters A, B, C, D, and E, are the pegs of the warping board. The thick lines are the threads of a warp, which may be of any number, large or small.

The Board
in Use

Securing the
Crosses

Securing the Crosses in the Warp




FIG. 15.—Method of securing the Crosses in Warps.

Between C and B, and D and E, are the two important crossing places of the alternate threads. The thin lines represent two pieces of strong, pliable cord, each about two yards long, which have been inserted from the front in the openings of the warp made by the pegs C and E. These cords have then been passed between the first thread and the board, and brought through from the back in the openings made by the pegs B and D. The ends of the cords have been firmly tied together, and by their means the cross is perfectly secured, whatever may happen to the warp. It will be noticed that there is another cross in the warp between pegs B and A, but this is not so important. It is useful, however, to pass a short cord through the loop at peg A and tie the threads all together. If our small warp of twenty threads were now taken off the board and the cords which secure the crosses stretched out, the two ends of the warp would be represented by fig. 16.




Plate VI.—Spindles, Whorls, and Loom Weights, Ancient Greece.

See page 13.

British Museum, London.




FIG. 16.—The Warp displayed.

To warp
several
Threads at
once.

It would be a very tedious proceeding to warp a great number of threads, one at a time, and it was only suggested as advisable to do so in order that the principle of warping might be made clear. Eight threads can quite easily be warped together, so that when the warper has carried them once from the peg A to peg E and back again, sixteen




FIG. 17.—Bobbin-carrier.

The
Bobbin-
carrier.

threads will be placed in order. To effect this saving of time and labour we must use a *reel- or bobbin-carrier* (fig. 17). The bobbin-carrier is an oblong frame, in which there is room for eight bobbins to stand and turn, when they are fitted up with wires for the purpose. A convenient handle for holding the frame is firmly fixed to it at the bottom. The top of the frame is pierced with eight holes, and in the bottom, corresponding holes are drilled about half through the thickness of the wood, so as to fix the eight wires and not allow them to fall through. The wires are passed through the top

edge of the frame, through the bobbins, and are then caught and fixed by the holes in the bottom edge. As the frame is held upright, the weight of the bobbins standing in the frame will be found to give the tension to the thread which is required for warping. When placing the reels in the carrier care must be taken so to fix them that the threads all unwind on

The
Bobbin-
carrier




FIG. 18.—Two Positions of Bobbin-carrier.

the same side, and cause all the reels to revolve in the same direction.

Having got the bobbins properly set up, the ends of the threads must be gathered together and tied in a convenient way for fixing on to peg A of the warping board (fig. 14). The threads being fixed to the peg A, no. 1, fig. 18, and the carrier held in the left hand of the warper, in an upright position, it must be taken past the pegs B and C and held there a little above their level, so that the threads are well separated and taut. Then with the first finger and thumb of the right

The
Bobbin-
carrier

hand the warper must pick out and draw downwards the second, fourth, sixth, and eighth threads, as numbered in no. 1, fig. 18, and place them *below* peg B in the same position as the first thread in the warp of ten was placed. This will leave threads 1, 3, 5 and 7, above the peg. Again tightening the threads by a slight further movement of the carrier, taking care that they do not slip off peg B, the first, third, fifth, and seventh threads must be picked out and pulled downwards so as to place them *below* peg C, leaving threads 2, 4, 6, and 8 above it. It will now be found that we have a crossing of alternate threads between pegs B and C. After making quite sure that the crossing is correct, the eight threads must be grasped by the right hand of the warper and carried steadily round the seven pegs in exactly the same course as the single thread was carried when guided by the dotted line, no. 2, fig. 14. After having traversed the seven pegs the carrier arrives at the peg D. It is not necessary to take a cross of single threads here, as at B, C, but altogether, the eight threads must be taken *below* peg D, *over* and *under* peg E, then *over* peg D, and so back again the whole round to peg 1. When arriving at peg 1 the carrier must be transferred to the right hand, without twisting the threads, so as to leave the left hand free to manipulate the return cross between pegs C and B. The position of the carrier and threads is now represented at no. 2, fig. 18, and the threads marked 1, 3, 5, and 7 must be pulled down and placed *below* peg C, leaving threads 2, 4, 6, and 8 above it. Again with a slight movement, the threads must be tightened, and

threads 2, 4, 6, and 8 placed below peg B, leaving threads 1, 3, 5, and 7 above it. The crosses are now complete, and it only remains to take the group of eight threads *below* and *over* peg A in order to finish the first PORTEE, as such a collection of threads warped in one round is called. The use of the portee cross (no. 3, fig. 14) will be explained later on. Before beginning the second round it will be well to examine the threads between pegs C and B in order to make sure that the sixteen threads are all "in the cross" in proper succession, as they will certainly be found to be if the above directions have been accurately followed. After a little careful practice it will be found that, the portee of eight threads can be warped in the same time as that taken for warping one thread. As soon as a few portees have been warped it will be found difficult to remember how many threads are gathered together on the pegs, so it becomes necessary to use some contrivance for readily counting them, in order that we may know exactly when the warp is finished. This account can be quite easily kept if half a yard of narrow tape or coloured cord be attached to the top edge of the warping board above the portee cross (no. 3, fig. 14). The tape has to be turned back until five portees have been made; then it must be allowed to hang over the front until five more have been built up, and so on, forward or backward, after every fifth portee. By this means the number of portees can at any time be counted. Thus, five portees of sixteen threads contain eighty threads, and these multiplied by the number of fives warped will give the total number of threads reached. The warp, of any required number of portees, being

The
Bobbin-
carrier

The Portee
Cross

Keeping
Account of
the Number
of Threads
warped

Taking off
the Warp

finished and the crosses secured, as directed at p. 32, it may be taken off the board and wound on to a stick, for convenience in transferring it to the loom. For reasons which will afterwards be explained, it is necessary in winding on to a handstick, to begin at the beginning of the warp, peg A, fig. 14; this will leave the portee cross




FIG. 19.—Taking off the Warp.

outside when the warp is all wound on to the stick. The handstick should be a short round stick, smoothly finished and with rounded ends, in size about an inch and a half in diameter by eighteen inches long. This being ready, the warp must be firmly held by the left hand of the warper at the point shown in fig. 19. The peg A is then to be removed and the loop of warp taken in the right hand, the fingers being thrust through it. The loop being securely held, the left hand is free to remove the warp from pegs C and B and from peg 1. The cross having been previously secured, the loop between A and B may be made of a

convenient length for the next operation, which a careful study of figs. 21 and 21A will make quite clear, so that it needs no verbal description. It may be remarked that the loop shown in this figure is a most useful one, and is much used in the fitting up of looms; it should therefore be well mastered once for all. The loop having been formed, the handstick must be inserted and the loop tightened as indicated in the bottom compartment

Taking off
the Warp




FIG. 20.—Handstick and Warp off Pegs A, B, C, and 1, 2 of Warping Board.

of fig. 21A. The warp looped on to the handstick ready for winding off the pegs is shown at fig. 20. It may be found advisable to enlist the help of an assistant in taking off the warp, especially to hold it at the pegs and prevent its coming off too freely. The warp may now be gradually and firmly wound upon the stick, care being taken to start the winding in the direction of the arrow, bottom compartment, fig. 21A. If wound in this direction the warp will not slip round the stick or come loose. When the portee cross is reached the warp may be taken off the pegs D and E, carried away and kept quite safely till the loom is ready to receive it.

**Forming the
Loop**




FIG. 21.—Making the Weaver's most useful Loop.

Forming the
Loop




FIG. 21A.

CHAPTER IV

THE WARPING MILL

The Warping Mill necessary for Long, Full Warps—Description of the Warping Mill for Silk-weaving—The Bobbin Frame—The Heck-block—Demonstration of spreading a Warp—Regulating the Length of Warps—The Heck—The Gatherer—The Count and Length of Warps; how calculated—Threading the Heck—Beginning a Warp—Taking the Cross—The Ratchet and Wheel of the Heck-block—Mending Threads.

The War-
ing Mill
necessary for
Long Full
Warps

ALTHOUGH the warping board described in the last chapter is very useful for small warps of moderate length, such as would be used in a domestic loom, it would not be convenient for very long warps, or accurate enough for warping several thousands of fine silk threads. For such warps as these a warping mill is necessary, on which, if need be, as many as twenty thousand threads can be made into a warp of a hundred yards in length.

Description
of the Warp-
ing Mill for
Silk-weaving

The warping mill now to be described is of the kind used in conjunction with the silk-weaving draw-loom of the seventeenth, eighteenth, and part of the nineteenth centuries. It is perfectly adapted to its purpose, and, like the draw-loom itself, was the result of centuries of gradual development.

The warping mill, fig. 22, is made entirely of hard,

tough wood, perfectly smooth and strongly fitted together. Its chief feature is a large skeleton reel, AAAA, generally five yards in circumference, though sometimes seven and a half yards, and about two yards long. The reel has an axle, B, which has a long iron pin at each end, shown plainly at no. 2. A strong frame, consisting of two uprights, C, C, and two cross-pieces, D, D, is very firmly fixed up, and in the centre of the bottom cross-piece there is a socket to receive the iron pin, E, of the axle when the reel is set on end in its place, as in the diagram. The reel is kept in an upright position by the pin F, which passes through the upper cross-piece and terminates about ten inches above it. This arrangement allows the skeleton reel to turn freely on its axle. A grooved wheel, G, is strongly screwed to the end of the axle where the pin E enters it, and another wheel, H, also grooved, is attached to a handle which can be turned by the warper, who sits on the seat I. The seat I is movable, and may be placed in any convenient position, being kept there by heavy weights, J. The grooved wheels G and H are connected by a continuous cord, as indicated in the ground-plan, no. 3. It is now obvious that the warping reel may be turned at any required speed, and in either direction, by means of the handle K.

The front upright of the frame, C, is divided into two for the greater part of its length, and a solid block of wood, L, is fitted to it, so that it can slide up and down the frame opposite to any part of the reel. Fig. 23, which is an enlargement of the sliding block, will explain this mechanism. Between the uprights a pulley, M, is attached




FIG. 22.—The Warping Mill.

to the top of the block. At the top of the frame (fig. 22, no. 1) is another pulley, N, and a strong

The
Warping
Mill




FIG. 23.—The Heck-block.

staple, O. The axle-pin F, no. 2, terminates in a small cylinder, P, which fits over it and is fixed

**The
Warping
Mill**

so that it will revolve with the reel. A hole is made in the cylinder near one end, a strong, smooth cord being passed through it, and a knot tied to prevent its slipping out. This cord is next passed over the pulley N, down to the pulley M in the block, then up again to the staple O, and tied there.

**The Bobbin
Frame**

The side elevation of a frame made to hold a large number of bobbins of silk or other thread, is shown at QQ, no. 1, fig. 22. A front view of the frame is given in fig. 24. The wires on which the reels are placed are fitted into holes drilled half through the sides of the uprights of the frame. On one side a groove of the same depth as the hole is cut, of the shape indicated at RR, so that the wire can be removed by lifting it at one end and drawing it backwards. This is necessary for changing the bobbins as they become empty. The position of the frame, in regard to the warping mill, is clearly shown in the drawing. S, fig. 22, is a strong staple screwed to the mill frame, from which a cord passes to a similar staple fixed in the centre of the bobbin frame, fig. 24, S. This cord keeps the frame from falling backwards, and at the same time allows it to be readily adjusted. The frame stands freely on the ground, inclining backwards, and the weight of the bobbins of silk, added to that of the frame itself, gives just sufficient tension to the threads when in process of warping. Before going into further details, the action of the warping mill, in so far as it has been described, must now be noticed.

**The
Heck-block**

In the block L, figs. 22 and 23, centres the whole mechanism of the warping mill. On it the

appliance for *taking the cross* is fastened. It is also the means of spreading the warp truly and Heck-block




FIG. 24.—Bobbin Frame.

evenly upon the large reel of the mill. The apparatus for taking the cross will require careful

Demonstration of
spreading a
Warp

explanation of further details, but everything for spreading and regulating the warp has been described and is ready for demonstration. For this purpose a single reel of stout thread must be placed on the reel frame, fig. 24, at about the centre, T (see also no. 1, fig. 22). The dotted line passing from the reel at T, fig. 22, indicates the course of the thread. At the point in the block marked U (no. 4) a temporary screw-eye is fixed. Through this the thread is passed, and tied to one of the staves of the mill reel at V. By the turning of the handle K the mill reel will be made to revolve, winding the thread upon itself. The thread will not be wound horizontally, but rather diagonally, and will gradually rise on the reel, until it will be found, on the completion of one revolution, that the second round of thread will begin a little space above the starting point of the first, V. This is owing to the cord on which the block is suspended by the pulley M (fig. 22, no. 4) having been shortened by being wound upon the cylinder, P, at the top of the axle. The shortening of the cord has gradually raised the block L, and if the cord and cylinder are properly adjusted the block will have risen an equal distance at each revolution. Consequently the thread will be exactly distributed over the mill. Now, if the thread be fixed at the top of the reel and the handle turned backwards, the reel will revolve in the opposite direction, the cord unwind from the cylinder, the heavy block descend, and the second thread will follow exactly the same course as the first until it reaches the bottom. In the same manner, if a hundred bobbins were placed in the frame and all the threads drawn through the eye in the block and

tied together to the mill reel they would be laid and spread as easily and evenly as the single thread.

Again, any length of warp desired, from two yards to a hundred, can be measured and determined at the beginning, by the revolutions of the mill reel. For instance, we will suppose the block, carrying the warp, is wound to the top of the mill. This is always its position on starting. Let the warp be tied to one of the pegs on the top of the reel at X, no. 1, and the handle K turned so that the block descends. The mill being five yards round, at the end of one revolution there must be five yards of warp on it. It follows that we have only to count the convolutions on the vertical line from the starting point and multiply them by five to ascertain the length wound upon the mill reel. For instance, if twenty-five yards of warp are required, five revolutions of the reel must be completed in each direction. In order to make different lengths of warp at will, there must be provided some means of holding the threads at the beginning and end of the length required. The first and last of the pegs, five in number, shown in fig. 22, no. 1, at Y, W, and X, answer this purpose. The three pegs at the top of the mill, Y and X, are fixed in that position, as the warp always begins at the same place. The board in which pegs W are inserted, is movable, and is so made that it can be fixed by a wedge at any height on the reel between any two of the staves. The threads are first looped on to peg Y, and the mill caused to revolve in the direction of the arrow Z. When a place on the mill is reached where it is wished to terminate the warp, the peg board W is moved to the spot, the

Demonstration of spreading a Warp

Determining the Length of a Warp

Determining the Length of a Warp threads are looped round the right-hand peg, and the motion of the reel reversed. As the block continues to fall and rise between the top of the mill and peg W, the threads of the warp will all be laid of an equal length.

Use of the Fixed and Movable Pegs

The spaces between the rounds of thread formed by each revolution can be regulated by altering the size of the cylinder P, no. 1, fig. 22. An increase in the size of the cylinder causes the block to rise quicker. This lays the thread in a steeper diagonal and increases the space between each round. A smaller cylinder, of course, has the reverse effect. The pegs X, no. 1, fig. 22, correspond with the pegs B and C in the diagram or the warping board, fig. 14, and the pegs W with the pegs D and E of that appliance. The former are for use in building the cross of alternate threads at the beginning of a warp, and the latter for making and preserving the portee cross at its end.

The Heck

The next detail of the warping mill to be described is the important fitting which gives the name to the block L, fig. 23, by means of which the cross in the warp is made quite easily, however many threads are used. Fig. 25 is a representation of the HECK, which is the name given to this useful appliance. There are variously constructed hecks in use, but they are all made on the same principle. The drawing shows one of the simplest both to make and keep in repair. It consists of a strong, hardwood frame of an oblong shape, having an attachment, at the bottom, pierced with a hole, by means of which it is firmly fastened with a thumb-screw to the heck-block, as at N, fig. 23. On

the inside, at both ends, the heck frame is grooved (B, fig. 25), and two smaller frames are fitted into the grooves loosely enough to be easily moved up and down in them separately or together. Tied

The Heck




FIG. 25.—The Heck.

at regular intervals on the two small frames, are a number of loops of fine, strong thread, as in no. 2, which shows one frame detached. The loops are for the purpose of holding a row of eyes in the centre of the frame. These may be either smaller loops of string, as in no. 4, or smooth glass beads, or *mails*, as they are called in weaving (no. 3). These can be obtained perforated with three holes, one large for

The Heck the thread to pass through and two smaller ones for attaching them to the loops (no. 3). For the sake of clearness, only seven loops are shown on the frame in the illustration. Any number, however, may be used, but each frame must have at least half as many loops as there are reels of thread on the bobbin-carrier. Thus, if eighty bobbins are to be used in making a warp there must be forty eyes on each frame. The position of the eyes and loops on the second frame is shown by the dotted lines in no. 2.

The Gatherer The next appendage to the heck-block to be described is placed at the back of it, opposite the centre of the heck frame. It is shown screwed to the block in fig. 26, no. 1, A. No. 2 is an enlargement of it. It will be seen to consist of a block of wood (it should be boxwood), very smoothly finished, about five inches by three inches, and an inch and a half thick. Projecting from the top edge are two strong steel points, about three inches long, and two inches apart. Upon these points two round, hollow, boxwood pegs are made to fit. In the drawing one of these, B, is represented in its place on the point, but the other is shown separately at C. The pegs are not fixed on the points, but are fitted so that they will easily revolve on them. The reason for these pegs being loose, is to prevent friction when a large number of threads gathered together is passing quickly between them, from the reel frame, through the heck, to be spread upon the revolving mill.

The Regulator of the Heck-block In the centre of the heck-block shown in fig. 23 at O a ratchet and wheel will be observed. This is to enable the warper to regulate to a greater nicety the spreading of the warp on the mill reel.

The section, no. 2, will explain its construction. The pulley M is attached to the axle of the ratchet wheel by a piece of strong catgut, which on the Heck-block




FIG. 26.—The Gatherer.

wheel being turned ever so slightly winds the cord on to the axle and brings the pulley nearer to the block. This has the effect of raising the block a little, and prevents the accumulating threads of the

The Regulator of the Heck-block warp from piling up in one place on the mill, as they would otherwise do.

The Count and Length of Warp complete, and it only remains to demonstrate its use in the preparation of a large warp of fine silk, say of twenty thousand threads fifty yards long.

Calculations
necessary in
Warping

In warping, the first thing to determine is the number of bobbins of silk to be used, and to arrange them on the bobbin frame, fig. 24. The frame must be fixed in the position shown at QQ, fig. 22, no. 1, and all the other fittings of the mill must be in working order. Fifty bobbins will be a convenient number, as twenty thousand divides equally by fifty. This number of bobbins will make each portee consist of one hundred threads (see pp. 34-37). It must next be calculated how many portees of one hundred threads each, will make up the number required for the whole warp.

$$20,000 \div 100 = 200.$$

Two hundred portees, then, will be needed. In order to build this number up on the warping mill the heck-block must be caused to travel down and up the mill frame two hundred times, a cross being taken at the beginning and the end of each journey.

Order of
Bobbins on
the Frame

The bobbins of silk must next be arranged on the frame, which is shown to be capable of holding a hundred, so that the fifty we propose to use will just fill the upper half of it. It must also be noted that the reels are counted in rows, beginning at the top of the left-hand row. This order must be maintained in threading them through the

heck. When placing the bobbins on the wires care must also be taken that they will all unwind in the same direction (see p. 35).

The bobbins being ready on the frame the warper must stand between it and the mill with the right hand to the bobbin frame. The end of silk hanging from the first reel must be taken and threaded through the first eye of the heck, which will be seen by reference to fig. 25, no. 1, to be on the front frame of that appliance. The thread must be drawn well through the eye, taken between the revolving boxwood pegs, and left hanging there. In like manner the second thread must be passed through the second eye of the heck, which will be found on the back frame. The silk from the third bobbin must then go through the third eye, which is on the front frame, and this order of alternate threading must continue until all the threads pass in regular order from the frame through the heck, and hang all together between the boxwood pegs.

The heck-block, which has been standing at any convenient height for threading the silk, must now be worked gently up to the level of the pegs at the top edge of the mill, and all the loose ends of silk, hanging from the heck, being tied together, must be looped on to the peg Y, fig. 22, no. 1. On the mill being now moved a few inches in the direction of the arrow Z all the threads will be tightened, and the heck must be examined in order to see that they all pass in regular alternation through the eyes of its front and back frames. Any error in the threading will be at once detected if the frames are lifted in succession so as to raise

Order of
Bobbins on
the Frame

Position of
Warper
when
threading
the Heck

Position of
the Heck-
block at
Beginning
of a Warp

Position of
the Heck-
block at
Beginning
of a Warp

first one half and then the other of the fifty threads. This being found correct, the collection of threads which passes between the frame and the heck must also be examined. They should come off the bobbins in five distinct vertical rows, so that the warper may be able to see at any moment that the reels are all revolving properly, and detect at once threads that require mending or any other attention.

Taking the
Cross

It will next be necessary to remove the silk from between the revolving pegs of the heck-block, gently turn the mill by hand until the peg Y stands about two feet to the left of the heck, and then all will be ready for the important operation of *taking the cross* which is done in the following manner. Care being taken to keep the threads all taut, the *front* frame of the heck must be first raised. This will lift half of the threads and make an opening through which a short glass rod or the finger and thumb of the warper's left hand must be passed. The opening thus made can then easily be moved along the threads and transferred to the first peg X, which is nearest to Y. By another slight movement of the mill the silk must again be tightened, the *back* frame of the heck raised, and the rod inserted in the opening, which is then to be transferred in like manner to the second peg X. The cross should now be complete and perfect, and as soon as it is seen to be so the silk must be replaced between the revolving pegs of the heck, and the warping may proceed. The length of warp is next to be arranged for and spread as described at p. 48. The fifty yards will need ten revolutions of the mill to spread, and these are to be made by turning the handle K, no. 1, fig. 22. Great care must be exercised

in order to turn the mill steadily and firmly and keep an unrelaxed tension on the threads of silk. When the ten revolutions are complete the movable board holding the pegs W must be wedged between the staves of the mill just below the termination of the tenth round of the warp. Here, as previously explained (p. 37), only the portee cross is required. Accordingly the fifty threads, taken all together, will pass above the first peg W, below the last one, then round it, and under the first, which completes the portee cross. The revolution of the mill must now be reversed, the silk being wound upwards in the same course until the heck-block again reaches the pegs at the top, and the mill is stopped gently for taking the return cross. This time, as the first opening has to be transferred to the second peg, the *back* heck frame must be the first raised for the insertion of the glass rod. When this has been done the front frame will be lifted, the opening transferred to the first peg X, and when the warp has been looped round peg Y the first portee will be finished, and a hundred and ninety-nine others will have to be done in exactly the same manner. An excellent way of keeping account of the portees as they are warped is shown at fig. 27. A stroke is made for every portee completed until nine are reached, and at the tenth one the nine are crossed out.

On arriving at peg Y, fig. 22, after the last portee has been warped the half-portee must be divided and the threads cut from the heck and tied in such a manner as to loop over the peg.

As the warping proceeds it will be found necessary to make use of the ratchet and wheel

The Ratchet
and Wheel
of the Heck-
block

marked O in fig. 23. Without the help of this extra means of regulating the length of the cord by which the block is suspended the threads would be piled up in one place in an unmanageable heap, and when stretched out in the loom would be of various lengths and cause great inconvenience to the weaver. After a few portees have been laid on the mill, therefore, the cogged wheel has to be turned so that the ratchet may catch the next tooth. This will




FIG. 27.—Method of Counting Portees.

obviously raise the block a little and cause the next round of warp to be laid a trifle higher on the mill. As this movement of the ratchet wheel is repeated from time to time the warp will gradually fill in the space between the rounds and lie flat in a spiral band on the mill. This filling of the space needs to be done judiciously, and must never be carried so far as to merge one round into the next. Warps of a high count naturally require greater space between the rounds. This is regulated, as has been described (see p. 50), by the size of the cylinder P, fig. 22, no. 1.

Mending
Threads

However great the care taken by the warper may be, it is impossible to prevent threads occasionally breaking. These must be most carefully watched, and if possible detected before the broken thread has passed away through the heck. To find and mend threads

between the bobbin frame and the heck is an easy matter if done in the right way. The warper must reach down from the top between the vertical row of threads in which the broken one should be and the row nearer to him, bring both ends up, seeing that they come direct from the bobbin on the frame and from the heck, and tie them together. If this has been rightly done the thread will find its proper place as soon as the mill begins to revolve again. Should the thread have passed the heck it is more difficult to find and mend. In this case the end must be brought from the bobbin and threaded through the vacant eye in the heck. If the end to be joined has disappeared, as will be most likely the case, the half-portee must be unwound with the greatest care and searched for the missing end. As the silk is unwound from the mill the warper temporarily winds it upon his hand until the missing thread is discovered. When found, it is tied to the loose end from the reel, and the half-portee replaced gently and accurately in its proper position as the mill is turned by hand, until the heck is again reached, and the warping proceeds. This is rather a difficult and tiresome process, and needs to be avoided as much as possible by watchful care. Immediately on the warp being finished the crosses must be secured in the manner described at p. 32, the greatest care being taken that the cords pass clearly through the openings kept by the pegs.

There are, of course, numberless points with regard to warping which only experience will teach, but enough has been advanced to explain the method itself and to indicate the uses of the various parts of the warping mill.

CHAPTER V

TURNING ON, OR BEAMING

Turning on, or Beaming—The Raddle, or Vateau—Selection of a Raddle for a particular Warp—The Cane Roller and Cane Sticks—The Raddle Stand for Small Warps—To separate the Portees—Distributing the Portees in the Raddle—Turning on in the Loom—Position of the Cane Roller in the Loom—Means of turning the Roller—Assistance required in turning on—Method of keeping the Warp hard on the Roller.

Turning
on, or
Beaming

In order that the warp may be stretched in the loom ready for the weaver to make into cloth, it has to be attached to a roller and spread out and wound evenly and tightly upon it. This roller fits into the back or top of the loom frame, and when spread out upon it the warp has to be a little wider than the web is intended to measure when finished. This process is called *turning on* or *beaming*—beaming because beam is the old name for the roller of a loom. When we read in history or poetry of a “weaver’s beam” we may know that the roller is the part of the loom referred to.

In Chapter III. the use of the warping board was demonstrated, and a finished warp, with the crosses properly secured, was described as left wound

upon a hand-stick, with the portee cross exposed, and ready for beaming (p. 39).

Turning
on, or
Beaming

For the demonstration of turning on we will suppose that the width of material to be woven is twenty-two inches, that the warp contains nine hundred and sixty threads, and that this number is made up of sixty portees having sixteen threads in each.

We have first to spread the warp out evenly to a width of a little more than twenty-two inches. This must be done by means of an appliance called a *raddle*, or *vateau* (fig. 28, nos. 1 and 2). The raddle is simply a comb with a movable cap to cover the ends of the teeth (no. 1). The frame is made of wood, but the teeth are of hard brass wire. The cap has holes in it, near the ends, through which the sides of the frame pass in order to fix it on, as shown at no. 2. Metal pins or small wedges passing through the projecting ends secure the cap in its place. The cap also is deeply grooved above the range of teeth, and when fixed on the comb effectually separates all the divisions of the raddle. The teeth of the raddle are accurately spaced and marked, so many to the inch. A warper has to be provided with a set of raddles, so as to be able to deal conveniently with warps made up of different numbers of portees and various thicknesses of yarn.

The Raddle,
or Vateau

In order to determine the proper raddle required for a warp, the number of portees it contains must be divided by the number of inches it is to occupy on the roller. Thus, the warp with which we are dealing contains sixty portees, and as it is to make cloth twenty-two inches wide, it should be

Selection of
the Raddle
for a Warp

Selection of
the Raddle
for a Warp




FIG. 28.—The Raddle.

spread out to at least twenty-four inches in the raddle.

$$60 \div 24 = 2\frac{1}{2}.$$

Selection of
the Raddle
for a Warp

We find then that every inch of the raddle must have two portees and a half distributed on it. A raddle having five spaces to an inch will accordingly suit our purpose, and in every space we




FIG. 29.—The Cane Roller.

must place half a portee. This can be quite readily done, as each portee is divided into two at the cross.

Fig. 29 represents the back or top roller of a loom such as the warp is to be spread and wound upon. It is called the *cane* roller, to distinguish it from the *breast* roller, in front of the loom, on which the woven cloth is wound. It has a groove ploughed in it from end to end deep enough for two smooth, wood or metal sticks to be placed easily one above the other in it. One of these rods we shall require to use at once in spreading the warp.

The Cane
Roller and
Cane Sticks

The Cane
Roller and
Cane Sticks

The warp is shown on the hand-stick in fig. 30. Into the opening at A the cane stick must be inserted, and through the opening B, another cord, a little longer than the cane stick, has




FIG. 30.—Portee Cross in Use.

Raddle
Stands

to be passed and tied securely to the ends of the stick. As soon as this is done the first cord may be cut away. The portee cross will now be safely kept by means of the cane stick and the cord as at no. 2. Two little supports for the raddle will now be required in order to fix it in an upright position on a table, as shown in fig. 31. Fig. 32 shows the warp in the proper position for distribution in the raddle. A




FIG. 31
Raddle Stands




FIG. 32.—Warp ready for distributing in Raddle.

Raddle
Stands

Raddle
Stands heavy weight of some kind, B, is placed on the warp three or four feet from the raddle, and the portee cross, secured by the cane stick and cord, is on the opposite side. A piece of card folded as at A and placed on top of the teeth of the raddle, makes a handy rest for the warp while the portees are being picked out and placed in order. It will now be found that on taking the cane stick in hand and gently pulling the warp tight the portees can readily be separated and entered in regular succession along it. By this means the warper is enabled to distribute the portees at will in the raddle spaces.

To separate
the Portees

Distributing
the Portees
in the
Raddle The raddle will probably be more than twenty-four inches long, but that is quite immaterial. We must first find the central space and count off twelve inches to the right of it, marking it as the starting place of the distribution. The folded card may be moved to within a few inches of the mark, with the warp resting upon it. The first portee must now be separated from the bulk of the warp and divided, the first half of it, which will come out of the cross naturally, being placed in the first space, and the second half in the second space. The second portee, in like manner, will fill the third and fourth spaces, and so each portee will follow in succession, until all are distributed. It will be found necessary, during the distribution, to keep the cane stick as much below the level of the raddle as possible. If this be not done, the distributed portees are apt to escape from their appointed spaces, and the work of distribution has all to be done again. As soon as the whole warp is in the raddle the cap must be fixed securely in its place, and then all will be safe and ready for the actual turning on.

Such a warp as the one we are dealing with, made on the warping board, is just suitable for a domestic loom, so we will suppose it has to be turned on, in the loom, with the roller, on which the warp has been wound, fixed in its place. This can readily be done, but an important silk warp, such as the one described as made on the warping mill, requires the use of a special turning-on machine, with facilities for very heavy weighting and a means of keeping a steady and even tension on the multitude of fine silk threads.

Turning
on in the
Loom

This is not the place to explain the method of fixing the roller to the loom, that will be done when the whole construction of the loom itself is treated of. We must therefore, for our present purpose, imagine it bracketed to the loom-posts as shown in fig. 33, in which A, A are the back posts of the loom, B the cane roller, and C the groove in the roller into which the cane sticks fit. Two assistants will now be required, one to turn the roller and the other to hold on to the hand-stick, on which the warp is at present wound. Before we can actually begin the turning on, however, some means of turning the roller must be devised.

The Position
of the Cane
Roller in
the Loom

Into the roller at the place marked D, fig. 33, a very strong, short screw or nail must be driven, deep enough to take firm hold but at the same time to leave the head about an inch out of the wood. About six feet of strong cord will also be wanted ; this must be tied together at the ends so as to form a long loop. One end of the loop must be caught on to the screw-head, and the double cord wound round the roller two or three times, crossing itself


Means of
turning the
Roller

Means of
turning the
Roller

as it winds. It must be wound in the direction shown at fig. 33A, leaving the loop E for the insertion

of the stick as at F, fig. 33B. By means of this stick and cord, the assistant will be enabled to turn the roller, hand over hand, and wind the warp upon it quite easily, although a good deal of strength be exerted at the other end in order to pull the warp tight on the roller.

The actual process of turning on will be readily explained with the assistance of figs. 34 and 35. At fig. 34, no. 1, the warp is shown with the raddle, GG, and the cane stick, HH, in their proper places in the warp. One assistant, we will suppose, is holding the hand-stick, with the bulk of the warp upon it, at some little distance off



Turning on

FIG. 33.—Loom Posts
with Roller.

in the direction of the arrow. The other assistant is holding the raddle, GG, and the cane stick, HH, in the relative position, with regard to the loom-posts, shown in the drawing. The warper must now

stand behind the loom-posts, and, reaching between them, take from the assistant the cane stick, HH, to which the warp is attached by the portee loops. This he must slip into the groove in the cane roll. To fix the cane stick in the groove, another stick must be passed underneath the roller and the warp, into the groove, as shown at no. 2, fig. 34. The

Turning on




FIG. 33A.




FIG. 33B.

Loop and Stick for turning Roller.

raddle must now be brought close to the roller by being slipped along the warp, and the roller itself must be turned once round. This will fix the warp securely in its place, and at the same time spread it evenly upon the roller. When placing the cane stick in the groove care must be taken to leave equal spaces, or whatever proportion of space may be necessary for the working of the loom, at each end of the roller.

The warper and the assistant holding the raddle will now have to change places, but before doing so the roller must be fixed so that it will not turn

Assistance
required

back although the tension be kept on it. This may be done at any time, by placing the turning stick, F, in the position shown in fig. 35. This drawing (fig. 35) represents the stage of the operation now arrived at. The warper must take the raddle in hand and see that all the portees are in their proper




FIG. 34.—Warp ready for fixing in Cane Roller.

places, and that the raddle can be moved easily and without obstruction along the threads. All being in order, the turning on may now proceed. The warper must guide the warp, as it is turned on, by means of the raddle, gently shifting it about so as to lay the threads on the roller as evenly as possible round by round. All the time of turning he must look out for broken or tangled threads, being careful to place any that have to be mended in the portee to which they belong. If all goes well and the warp is turned on easily, it will prove that the warping has been properly done. All this time, from the first turning of the roller,

the assistant holding the hand-stick with the warp upon it must have been pulling with all his force and steadiness against the turning. If, indeed, the warp is of any considerable size, the services of two or three people are necessary in order to give sufficient tension to it. When a few turns have

Assistance
required




FIG. 35.—Warp ready for turning on.

been given, it may be well to place a sheet of very thick paper or tough card underneath the warp, between it and the roller. This being wound on, will prevent any threads sinking in and giving future trouble, as they would otherwise be apt to do. A long warp may require several of these protecting cards to be wound in with it, but the need for them will depend very much upon the weight and evenness of the tension kept during the turning on. If the warp on the roll begins to feel soft and flabby, it may be known that a card is required. As soon as the important cross is exposed on the hand-stick, the warper must call a halt, leave the

For keeping
the Warp
Hard on the
Roller

Placing
Rods in
the Cross

raddle, and spread the crossing threads out on the securing cords. This will not be found difficult to do if the weight be kept well on. When the cross is spread out clearly, two smoothly polished, round, wooden rods, pointed at one end, about an inch thick and six inches longer than the width of the warp, must be put into it, in the openings made by the securing cords, and left there together with them. When the rods are safely in place, the turning must proceed and continue as before, until the rods are close up to the raddle. As soon as they are in this position the cap must be taken off the raddle and the raddle itself removed, its work being done. One or two more turns will wind the cross and the rods on to the roller. The hand-stick may then be detached from the warp, and the turning on, or beaming, will be completed, the warp being quite ready to be entered in the loom.

CHAPTER VI

THE BEAMING DRUM

The Essential Part of Beaming Machinery—The Drum and its Fittings—Friction Brakes—Ropes of the Drum—Space necessary for Beaming—Importance of Accuracy of Detail in Weaving Operations—Turning-on Posts—Appliance for Beaming in Confined Space—Winding the Warp on the Drum—Beaming with the Drum.

THE beaming of such a warp as that described in Chapter IV. necessitates the use of some mechanical appliance in order to give to the threads a great and unintermittent tension during the whole operation. This want is met by the essential part of any turning machinery, the beaming drum.

This drum is a strongly, solidly made, large reel, with an iron axle, on to which the warp to be beamed has to be wound instead of being turned on directly from the hand-stick, as was done in the case of the small warp described in the last chapter. The drum, furnished with all its fittings and fixed in position, is represented by figs. 36, 36A, and 36B. It should be in size at least two feet in diameter and two feet six inches to three feet in length. It must be perfectly smooth and well joined, so that there may be no danger of the finest

The
Essential
Part of
Beaming
Machinery

The
Beaming
Drum and its
Fittings

The
Beaming
Drum and
its Fittings

silk thread being caught or broken on any part of it. The two stands on which it revolves must be firmly bolted to the floor of the workshop, as the strain they have to bear is very heavy and continuous, and they must be carefully adjusted in order that the




FIG. 36.—The Beaming Drum.

The Friction
Brakes

revolutions of the drum may be level and true. The drum itself must be provided with two friction brakes (figs. 36A and 36B, B, B). Each of these brakes consists of a strap of tough leather, about two inches in width, and long enough to reach from the ground at the back of the drum—where they are fixed by strong staples (C, C, fig. 36A)—to the bar DD at the front (fig. 36B). It is by means of these straps that the tension is given to the warp as it is being turned on.

Weights are hung on the bar, and the tension given to the warp can be regulated to a nicety by their means.

The Friction Brakes

The drum must also be furnished with two well-made ropes capable of bearing a heavy strain, and long enough to reach from the drum, after going once round it, to the frame on which the roller

Ropes of the Drum




FIG. 36A.—The Drum : Back View.

for turning on is fixed. These ropes must be permanently fastened, at one end, to the drum, as near as possible to the straps of the friction brakes, but not so near as to interfere with them when working. The ropes are wound on to the drum, care being taken to avoid crossing them, as shown at E, E, figs. 36A and 36B. The free ends of the ropes must be looped in order that a thick, round stick, almost as long as the width of space between the straps, may rest in them (F, fig. 36B). To

Ropes of the Drum this stick one end of the warp to be turned on is attached as shown at fig. 36.

Length of Space The next necessity for good beaming is a long workshop, in which a clear space of thirty or forty feet is available. Where such a space can be had, the drum, fitted up in the manner described, is the




FIG. 36B.—The Drum : Front View.

only apparatus that is required, with the exception of two posts, answering to the back posts of the loom, on which the cane roller is placed for beaming the warp, as described on p. 68 and shown in fig. 33. The posts specially made for turning on must be fitted up exactly opposite to the drum, and as far from it as convenient. They must be adjustable—that is to say, whatever width apart they may have to be in order to accommodate different lengths of rollers, the centre of the space between them must be exactly opposite to the

centre of the drum. ALL THESE MATTERS OF DETAIL ARE OF THE UTMOST IMPORTANCE IN WEAVING. IN THIS CASE, FOR INSTANCE, A LITTLE INACCURACY IN ADJUSTING THE POSTS WILL CAUSE THE DISTANCE OF THE DRUM FROM THE ROLLER TO BE GREATER ON ONE EDGE OF THE WARP THAN THE OTHER. THIS DIFFERENCE WOULD BE MULTIPLIED SEVERAL TIMES IF THE WARP WERE A VERY LONG ONE. IN CONSEQUENCE OF THIS, WHEN IT WAS IN THE LOOM THE WEAVER WOULD DISCOVER THAT ONE SIDE OF HIS WARP WAS LOOSER THAN THE OTHER, AND HE WOULD HAVE TO WASTE A GOOD DEAL OF TIME IN CONTRIVANCES FOR REMEDYING THE DEFECT. The posts may be made adjustable in the manner

Necessity for
Accuracy of
Detail in
Weaving




FIG. 37.—Turning-on
Post fitted

Turning-on
Posts

indicated by fig. 37. A strong cross-beam about eight feet long, a section of which is shown at A, must be fixed to the roof of the workshop, as far from the drum as possible and exactly parallel with it. As stated above, the space between the beam and the drum should be at least thirty feet. At the same time the beam must not be less than four feet from the wall indicated in the diagram by the line B, for in this space the assistant stands to turn the roller. A permanent mark should be made on the beam A exactly opposite the centre of the drum,

Turning-on Posts and a line may be painted on the floor also marking the centre of the space from the drum to the beam. This line and mark will make the nice adjustment of the posts, when they are fixed up, quite easy. The two posts need to be very strong, and should be about six inches wide by three inches thick. Their length will, of course, depend on the height of the workshop, as they must reach from the roof to the floor. It will be seen from the diagram that the posts do not stand quite upright, but lean against the beam in the direction of the drum, so that although when not in use they can easily be removed, when the tension is on the warp they are firmly fixed in their places. In order to make the posts stand firm when the weight is not on, their ends are accurately cut to the angles of the beam and roof and of the floor, so that when in position a tap with a mallet at the place marked C, fig. 37, will at once fix them. It will also be seen that the roller simply rests upon brackets fitted to the posts at a convenient height for the turner-on to work at.

Beaming in a Smaller Space If a space of thirty feet is not available for the beaming it is possible to do it in a much smaller one by means of rollers fitted in a frame. The frame with rollers is fixed to the wall, or placed opposite the turning-on posts, as far away from them as possible. The drum, with its front facing the rollers, stands between them and the posts, as near the latter as convenience will allow. This arrangement of the beaming machinery is shown at fig. 38. The warp in this case unwinds from the drum A, passes under the roller B, over C, and then, turning back, escapes the top of the drum and is turned on at the opposite posts. The simpler arrangement without rollers

is better for several reasons, the principal one being that when the silk goes direct from the drum to the cane roller there is much less friction and strain on it.

Beaming in
a Smaller
Space

The process of beaming when the drum is used is exactly the same as that described in the last chapter, except for the management of the drum itself, which takes the place of the assistant who holds the hand-stick and pulls, in order to give the




FIG. 38.—Beaming in a Smaller Space.

necessary tension to the threads. It will only be needful, therefore, to give instructions for the management of the drum and refer to the previous explanation for the rest.

In taking the warp off the warping mill on to the hand-stick, when a beaming drum is to be used, the *portee cross* end of the warp must be looped first to the hand-stick, so that when it is all wound on the *porrey cross* (see fig. 14) will be left outside. This is the reverse of the former direction (p. 38), and is necessary because the warp has to be rewound on to the drum. When this has been done the warp will be found in the same position on the drum as regards the crosses, as it was in the former case upon the hand-stick. In order to wind the warp on to the

Winding the drum, the stick C, fig. 36, must be detached from the ropes E, E and placed in the opening made by peg Y, fig. 22, no. 1. The stick must then be reattached to the ropes, and the drum turned so as to wind the warp tightly and evenly upon it. Of course while this is being done the weight must be taken off the bar of the friction brakes ; the straps themselves may even have to be removed. As soon as the warp is all wound on the drum, the friction brake must be replaced and a light weight put on the bar. The warper must then take in hand the portee end of the warp and carry it over to the cane roller posts, where the raddle is for the present fixed, in a convenient manner, in the place that the cane roll will eventually occupy. He will then proceed to insert the cane stick in the warp, distribute the portees in the raddle, and fix the cap on. Then the roller will take the place of the raddle and the cane stick be dropped into its groove. One turn given to the roller will fix the cane stick, and the necessary weight being put on the drum, the beaming may proceed.

Beaming with the Drum

When the warp is all off the drum, and the stick, to which it is looped, is in the position shown at fig. 36, the weight must again be taken off the brakes, in order to allow of the spreading and straightening out of the cross and the cords securing it. When this is done and the two rods inserted as directed at p. 72, the weight must be again put on and the beaming can be completed, the tension being kept even by means of the unwinding ropes.

The directions for finishing off the beaming, which are the same in large or small warps, are also given at p. 72.

CHAPTER VII

THE HAND-LOOM FOR AUTOMATIC WEAVING

Opening or shedding the Warp for Wefting—
Shedding the Warp without Appliances—Simplicity
of Egyptian and Greek Weaving—The Headle-rod—
Ancient Horizontal Looms and Automatic Sheds—
Indian and Chinese Looms—The Old English Hand-
loom—The Loom Frame—The Rollers—The
Ratchet and Wheel—Friction Brake for Cane
Roller—Comparison of Indian and English Looms
—Automatic Method of opening the Shed—The
Long Comb or Reed—The Batten—Position of
the Harness and Batten—Preparations for entering
the Warp in Harness and Reed—Gating the Loom.

THE warp, its special characteristics and the manner of preparing it, have been carefully and minutely explained; this will therefore need no further consideration. The method of opening the warp for the intersection of the weft thread next claims attention, for in this consists the whole art and mystery of weaving. Thus briefly stated, weaving may appear to be a very simple matter, but it will be found, as the subject is developed, that the warp may be intersected by the weft in an infinite variety of ways, and that the contrivances for doing this are numerous, and many of them most elaborate.

Opening or
shedding
the Warp

Opening or shedding the Warp So much is this the case that, instead of being altogether a simple art, weaving, in its highest perfection, is perhaps the most complicated of all the arts of life.

In order to explain the method of opening the warp for inserting the weft, it will be necessary to turn back to fig. 13, no. 1. In this drawing, as was intimated at p. 24, is represented the simplest possible form of loom. The method of weaving plain cloth is all that must concern us at present, the weaving of patterns being left for later consideration. The tools required are as simple as the loom itself, being only the spindle, with the weft wound upon it as it was spun (see pp. 14 and 15), and a flat stick to be used for keeping the openings wide and clear for the passing of the weft, and for beating the weft itself together.

To secure the Cross-
rods The loom for the demonstration of weaving being prepared as directed at p. 25, the cross-rods must first be secured in their place at the top of the loom. This may be done by attaching loops of string to the projecting ends of the beading, and twisting it round the two rods as shown in the end view of the rods, fig. 39. The flat rod E must next be placed in the opening made by the lower cross-rod, brought a little way down and turned edgeways, as shown in the section of the loom, fig. 39A. This flat rod is usually called the *shed-stick* because it is used for widening the shed, shed being the technical name for any opening made for the passing of the weft. Through the opening F, fig. 39A, the spindle, G, with the weft upon it, must now be passed, after sufficient thread has been unwound to reach across the warp, and leave the end of it projecting at H. All the warp threads at the

Opening or shedding the Warp without Appliances

back of the shed will now be covered by the weft, whilst those in front are still exposed. The latter must now be covered by the return of the spindle and weft. For this purpose a different opening or shed must be made as shown at I, fig. 39B. This is effected by pressing back the front threads with the top joint of the forefinger of the left hand, and hooking each back string on to it in succession. To do this quickly requires a good deal of practice; it is well, therefore, to begin by raising and passing the weft through only a very few threads at a time. For example, let the warp consist of seventeen threads, nine being in front. Beginning at the first thread on the left-hand side, and pressing it back, the back thread

can easily be caught on to the finger, which must next press in the same manner the second front thread and catch up the second back one. Next the third front and the third back, and lastly the fourth front and the fourth back threads must be taken up. It will now be found that four

Opening or
shedding
the Warp
without
Appliances




FIG. 39.—Primitive Loom and Shed-sticks.

Opening or
shedding
the Warp
without
Appliances

of the back threads nearest the left-hand side of the loom are on the finger, and if the shed-stick be placed flat in its original position, E, fig. 39,




FIG. 39A.

FIG. 39B.

they can easily be raised sufficiently high for the weft spindle to be passed through the opening. When this is done and the shed-stick again placed edge-ways, the remaining four back threads have to be raised in the same manner, and the weft passed through. After the weft has been drawn straight, the shed-stick being again in a flat position, its edge may be brought down smartly upon the whole weft in order to beat it together. The two shoots of weft will now appear as drawn between H and J, fig. 39, and the shed-stick being returned to its position at F, fig. 39A, the opening for the third shoot will be ready. The

fourth opening is made by picking up, in the same way as the second, and so shoot by shoot the weaving may be regularly continued. After a little practice the picking up of the back threads for every second shoot will become quite easy, and may be very quickly done. It will also be found that if the cross-roads are of a good size the shed-stick may be dispensed with. The weft, too, may be wound in convenient balls or skeins, small enough to pass

through the opening, so that the only tool actually requisite for this simple weaving is a heavy fork or comb to press the weft and beat it together from time to time (see plate II).

The above may be taken as typical of all primitive weaving, both ancient and modern. There is no evidence to show that the "fine linen" of Egypt or the famous textiles of Greece and Rome were woven in a less simple manner. Frames of various sizes for stretching the warp upon were certainly used, and the warps often consisted of a great number of fine threads. Rollers also were added to the loom, enabling the weaver to make long lengths of cloth, but the actual methods of weaving appear to have been as stated.

There is, in use amongst some primitive tribes of to-day, a contrivance for bringing forward the back threads of the warp all together or in sections, instead of picking them up separately on the fingers as above described. This is sometimes called a headle-rod. It is a rather obvious improvement, and, where the threads are very fine and numerous, would save a great deal of time. It may have been used in ancient Egypt and Greece, but there is no evidence to prove it. This appliance is a strong rod, a little longer than the warp is wide. It is suspended in front of the loom a little below the cross-rods. Each back thread of the warp is enclosed by a loop which passes between the front threads and is fastened to the rod (fig. 40). When this appliance is fitted to a loom the first opening is made by means of the shed-stick as already described. The second opening is made by the weaver giving the headle-rod a vigorous pull forward, and into the

Opening or
Shedding
the Warp
without
Appliances
Egyptian
and Greek
Weaving
Simple in
Method

The Headle-
rod

The Headle-rod opening thus made the flat shed-stick is carefully thrust. When quite through the warp it is turned edgeways, and effectually clears the opening for the passing of the weft.

Horizontal Looms and Automatic Sheds It is impossible to say how early in the history of weaving two most important steps in its




FIG. 40.—Headle Rod.

development were made. These steps were (1) placing the warp horizontally ; (2) arranging an automatic motion by which both the necessary openings or sheds can be made with equal speed and certainty. There is little doubt that it was in China that these improvements were first made. From that country they spread to India and the East generally. There are in existence very ancient

representations of Chinese and Indian horizontal looms with such automatic arrangements. Moreover, the fine silk webs of China and India, so much valued in ancient Greece and Rome, could hardly have been made in the simple manner described above.

Horizontal
Looms and
Automatic
Sheds




FIG. 41.—Indian Loom.

Fig. 41 is a drawing of an Indian loom made for the weaving of fine muslin. Such looms as this have without doubt been commonly used in India from a time long anterior to the Christian era. The framework is of bamboo, and the warp is stretched between bamboo rollers. There are many details lacking, as we have seen is usual in these ancient drawings, but the automatic motion for opening the

Indian and
Chinese
Looms

Indian and Chinese Looms shed, just referred to, is quite clearly shown. Altogether in its general arrangement the Indian loom bears a close resemblance to the hand-loom of old English pattern (fig. 42) and the domestic loom in the old French woodcut of the frontispiece. The stuffs carefully made by hand on such looms as fig. 42 cannot be equalled either in appearance or durability by the productions of the power-loom, notwithstanding all its claims to perfection of mechanism.

Old English Hand-loom A careful study of this old English loom in all its parts will now be both useful and interesting.

The hand-loom, like the warping mill, was the result of the experience of many generations of craftsmen. Simple as it may appear, it is perfectly adapted for use either in the weaving of the finest silk, or of the coarsest linen, woollen, or cotton materials. The parts already described will be at once recognised—viz., the back or cane roller, the warp with its cross or lease, and the cross-sticks protecting it; but the new features, the loom frame and its other fittings, now claim attention.

The Loom Frame Strength and rigidity are the chief qualities requisite in the loom frame, in order to enable it to withstand the continual heavy beating down of the weft, on which the making of good cloth so largely depends. The four posts must be made of sound wood, and be about six inches wide by three inches thick and not less than six feet in height. The posts must be joined together in pairs by being mortised into the long side-pieces of wood D, D, which should measure in length not less than eight feet. The cross-pieces, E, E, need not be mortised, but may be simply fixed in their places by screws, in




FIG. 42.—Old English Loom.

The Loom Frame

the way shown in the drawing. The length of the cross-pieces will depend on that of the rollers, and the length of these depends on the width of the web to be made. For a twenty-three-inch warp the rollers should be thirty-six inches long. There is no necessity for cross-pieces to join the posts together at the bottom. These would, in fact, be rather in the way of the weaver, who should be able to get conveniently to any part of the warp. In order to fix the frame solidly in its place and prevent the posts from shifting, four little blocks can be nailed to the floor at the foot of each post, as shown in the plan F, fig. 42. In erecting the loom frame care must be taken to fix it exactly square (see Note 1 at end of chapter), so that the front and back rollers are perfectly parallel to one another. Stays also should be fixed between the top-pieces, from the ends marked with a cross, and the nearest solid beam or wall above or behind the weaver, who sits to work facing the front roller. Constructed in this manner, of well-seasoned wood, the loom frame will be found to resist any amount of strain it may have to bear.

The Rollers

The back, or cane roller, A, has already been described (p. 63), and the front or breast roller, B, is exactly like it, having a groove in which two cane-sticks are put, in order to fix the warp.

The Ratchet and Wheel

The breast roller has in addition a ratchet and wheel attachment (C, fig. 42), which allows it to be turned only in the direction indicated by the arrow. The back roller is not so rigidly fixed, but is weighted by a friction brake at each end, the arrangement of which fig. 43, nos. 1 and 2, will readily explain. A is the roller, with the rope

wound three times round it at each end. B is a box suspended between the two ropes, into which any amount of weight, that may be required, can be put. C is a small weight just heavy enough to prevent the rope slipping too freely when the box is heavily weighted and set in the position shown. The warp being placed in the loom, is first sufficiently unwound for its end to reach to the front roller, where it is fixed, in the same manner as in the cane roller, by two rods. It will now be obvious that the warp will be stretched in proportion to the amount of weight put into the box suspended from the back roller.

Method of
weighting
the Cane
Roller




FIG. 43.—Cane Roller and Weighting.

Tapestry looms and some other simple looms for coarse weaving are made with a ratchet and wheel on the back roller, instead of the friction weight. This arrangement would not do for the weaving of fine threads, especially if they be silk, as the tension obtained by two ratchet wheels is rigid, instead of being elastic. When the friction brake is used, no matter how heavy the box may be made, the weight will give slightly at every blow of the beating down. This kindly giving prevents the breaking of the slender threads. The friction brake

Advantages
of the
Friction
Brake on the
Cane Roller

Advantages
of the
Friction
Brake on the
Cane Roller
Comparison
of the
Indian and
English
Looms

also admits of a nice adjustment of the tension to the requirements of the weaving, and has also many minor advantages unnecessary to mention here.

If the Indian loom, fig. 41, be compared with the English one, fig. 42, it will be at once noticed that they are both alike in two most important particulars. Both have the warp arranged in a horizontal position, and the contrivance used for making the opening or shed in the warp is the same in each.

The horizontal position of the warp in the loom was no doubt originally adopted because, in the first place, it enables the weaver to throw the weft swiftly through the opening by means of a shuttle, instead of slowly passing the ball or spindle across the warp ; and, in the second place, because it is easier to arrange for the automatic opening of the alternate sheds. In fact, if the interlacements of the warp and weft required are at all complicated, it would be practically impossible to arrange mechanically for the necessary succession of openings on an upright loom.

Method of
opening
the Shed

In fig. 41 and at letter G, fig. 42, the simplest possible automatic arrangement for opening the sheds is represented. It consists of four laths of wood, H, H, H, H, fig. 42, joined together in pairs by threads passing from those above the warp to those below it. Each pair of laths thus joined together is called a *headle*, or *heddle*. The threads joining the laths together are not simply single ones, but are made up in the same manner, although on a larger scale, as the loops of the part of the warping mill called the *heck*, shown at fig. 25, nos. 3 and 4. These compound loops are known as *leashes*, and any number of

them mounted on the two laths is called a *headle*.* The front headle of the English loom will be seen to have ten leashes, and the back one nine, thus allowing all the threads of the warp to pass through the eye of a leash. The first, third, fifth and all the odd-numbered warp threads pass through the eyes of the front headle, and the second, fourth, sixth, eighth and all the even-numbered threads occupy the eyes of the back headle. Only nineteen threads are represented in the drawing of the warp, for the sake of clearness, but it might, of course, consist of any number in reason, and the effect would be the same. It will now be seen that if the headles are raised successively, by some means, the alternate threads of the warp will be raised with them, and the necessary sheds opened for weaving.

There are various devices in use for the purpose of governing the headles in order to make the shed. These will be described later on, but the opening made by means of the arrangement of cords, pulleys, and treadles shown in figs. 41 and 42, as well as in the French loom of the frontispiece, is most simple and effective. By its use the pulling down of one headle causes the other to rise, so that while one half of the warp is rising the other is falling, and the clear opening required is consequently made in half the time it would otherwise take. Fig. 44, in which a longitudinal section of the loom is given, will explain the action of this contrivance. A and B are the rollers of the loom, C, C are the cross-sticks, and D is one of the two pulleys suspended from the centre cross-piece at the top of

Method of
opening
the Shed

* Sometimes the loop itself is called a *heudle* or *hook*, and the collection of them a *leaf* or *lam*.

Method of
opening
the Shed

the loom frame, just above the ends of the two headles. A cord passes from the front headle over the pulley, and is tied to the top lath of the back headle. The cord is made just long enough to allow the whole warp, when the headles are at rest,




FIG. 44.—Section of Opened Warp.

to lie flat, as shown in fig. 42 and represented by the dotted line in fig. 44. At E are the treadles of the loom, tied separately to each of the lower laths of the headles.

The opening F shown in fig. 44 is obtained by pressing down the right-hand treadle and allowing the left-hand one to rise. The falling treadle draws down the front headle with all the threads of warp carried by it, and at the same time, by means of the pulley D, draws up the back headle

with all its threads, the result being a clear open shed as depicted. In like manner the second shed is made by releasing the right-hand treadle and pressing down the left.

Method of
opening
the Shed

It is impossible to say at what period the important improvement in the apparatus of the loom was made, which consists in lengthening the short, heavy, independent comb, by which the weft had hitherto been beaten together, and attaching it to the loom itself, enclosed in a heavy swinging frame. It may be that at first the long comb was only fixed in the loom, near the front roller, in order to keep the warp threads from gathering together in places, as they are so apt to do. It is still used, for this purpose only, in looms built for the making of tapestry. When the long comb is fixed in this manner the short comb has to be used as well for beating down the weft. It led, however, to a great advance in the weaving process, when the idea occurred of hanging the long comb loose in the loom, in order that it might be used, not only for keeping the warp threads evenly distributed, but also for beating the weft together.

Origin of
the Long
Comb

By the adoption of the long swinging comb, needless to say, much time is saved. But more important than this, the blow of the comb is by this means evenly distributed across the whole width of the warp, and is so equalised that even the most delicate threads of silk or cotton, composing the warp, are not unduly strained, although a surprising amount of force may be used, after each shoot of weft, to beat the cloth together.

Advantage
of the Long
Comb

The name given to the long comb by weavers is the *reed*, because the divisions were originally made

Signification of fine strips of cane or reed, most carefully prepared and fixed between four half-round laths, in the
Reed




FIG 45.—Method of Reed-making.

manner shown at fig. 45. A, A, no. 1, are the ends of four half-round laths, shown also in the section no. 2, bound together in pairs by a fine waxed cord, one end of which appears loose at B.

In order to make the reed, the laths had to be fixed in pairs about four inches apart, and, starting at one end, a rather thick strip of cane—shown at C, no. 1, and B, no. 2, fig. 45—was placed between the laths and bound in with the cord as there represented. This thick strip of cane was for the protection of the finer strips which followed after about a quarter of an inch of the binding cord had been wound about the laths. The fine strips were put in, one to each round of cord, the spaces between them being regulated by the thickness of the cord itself. The whole length of reed being thus built up, the end was finished off in the same way as the beginning. The bound laths were finally steeped in melted resin in order to fix everything securely.

Method of
making the
Reed

The spaces in the completed reed between the strips of cane were called *dents*, and for fine silk-weaving there were often as many as a hundred and twenty to the inch. Often several threads of fine silk were passed, or *entered*, as it is called, in each dent of the reed. These combs still retain the name of *reeds*, although, since the middle of the eighteenth century, metal has taken the place of cane for the strips. The best metal reeds are still made by hand in the same way as the old cane ones, but they are now for the most part made by machinery.

The heavy swinging frame in which the reed is fixed is called the *batten*, and the method of hanging it is clearly shown in the drawing of the old English loom (fig. 42). Fig. 46 represents a batten for use with a hand-shuttle. It is constructed as follows. A is a heavy block of hard wood called the *race-block*, having a groove cut in the top, at the back edge, the same length as the

The Batten




FIG. 46.—Hand-batten.

reed, and of the shape shown in the section at B. It also has a piece of polished beading along the top front edge. This is for the shuttle to run on (letter C in section) as it is thrown through the shed of warp, which is so regulated that the threads held down by the treadle press upon the beading and allow the shuttle to pass over them. D, D are called the swords of the batten, and are mortised into the race-block. E is a grooved cap, also shown in the section ; it is movable, and its use is to fix the reed in its place.* F is the rocker by means of which the batten is hung in the loom as shown in fig. 42. When the batten is attached to the rocker by a double cord, as indicated in the side view G, its height can be nicely regulated by means of the peg at the back, which shortens, or lengthens the cord, by twisting, or untwisting it.

The Batten

In order to complete the description of the old English loom, it only remains to point out that the cross-piece, from which the headles are suspended, is movable, and may be fixed at any distance from the front of the loom necessary for the regulation of the shed. The nearer to the reed the headles are hung, the clearer and wider the opening in the warp will be.

Position of
the Headles

The position of the batten can be regulated by moving the rocker backward or forward in the brackets on which it rests (fig. 42, I). When the right place for it has been determined it is fixed there by means of small screws being partially driven into the bracket at the front and back of the rocker pins.

Position of
the Batten

All the essential parts of the loom for plain weaving are now described, and it is next necessary to explain the method of entering the threads of the warp in the *harness*, as a collection of two or more headles is called, and the reed. Entering has to be

To enter the
Warp in the
Harness and
Reed

* See Addenda, page 340.

To enter the Warp in the Harness and Reed done with great care and accuracy, as one mistake will throw out the whole succession of remaining threads. It is also very difficult to rectify mistakes when the entering is finished. In some cases the whole of the warp, beyond the faulty place, has to be drawn out and re-entered.

Fixing the Cross-rods for Entering Fig. 47 shows a warp in the loom prepared for entering. At p. 72 the turner-on is described as finishing his work by winding the cross-rods with the warp on to the cane roller. If not turned on in the loom itself, the roller, with the warp on it, was brought to the loom and placed on the brackets of the back loom-posts. Two strong, side cords, A, C, C, C, were then firmly attached to the front posts of the loom, and, being carried over the ends of the back roller, were rather heavily weighted. The warp was then gently unwound, and the ends of the cross-rods were allowed to rest on the side cords at A. The unwinding was continued until the rods rested at B. The side cords were then twisted once round the ends of the rods, as shown in the drawing, and by this means they were securely fixed at that point, but at the same time could be readily moved backward or forward on the side cord weights being lifted. The warp can now be regulated so that the loops hanging below B will reach to the front of the loom.

Fixing the Headles for Entering The headles had next to be specially fixed for entering, and for this the short pieces of wood D were provided. These were tied, as indicated in the drawing, to the top of the loom frame and to temporary staples driven into the floor. The ends of the top shafts of the harness rest upon the upper pieces of wood, and the bottom shafts are tightly held down




FIG. 47
Loom prepared for Entering

Fixing the Headles for Entering by the lower pieces, which are attached by slip-loops to the staples in order to regulate them. By this means the leashes of the headles are rendered quite taut and the eyes can be readily selected in due succession by the enterer. To make them still more secure, which is necessary in the case of a rich, full harness of many headles, little blocks of wood may be placed between the ends of the shafts and the latter may be bound together with cords.

Entering Hooks Nos. 2 and 3 are the hooks necessary for entering. No. 2 must be slender enough to pass easily through the eyes of the leashes, and the flat hook No. 3 must be thin enough to go through the fine dents of the reed.

Note about Entering It may be noted here that entering only needs to be done when the loom, or at any rate the harness, is new. After a length of cloth has been woven, sufficient of the old warp is left in the loom, with the cross-rods in it, to allow of a new one being tied on to it thread by thread. When the threads are all joined the old piece of warp is drawn forward, and of course the new threads follow the old ones through the headle-eyes.

Method of entering the Harness These preparations all being made, the entering can proceed. The enterer's assistant sits in the space D, between the warp and the harness. Beginning at one edge, he takes up a small bunch of the looped threads, and first cuts off the looped end; he gives it two or three sharp, firm pulls, which clear the cross between the rods and make it quite easy to select and separate the first thread. When this is done the thread is held ready to be hitched on to the enterer's hook as soon as it is pushed through the first eye in the harness.

The enterer himself sits in the loom in front of the harness, with the slender hook, no. 2, ready for use. He selects the first eye in the front or back headle and pushes the hook through it.* The assistant places the first thread on the hook, which, as it is drawn back, takes the thread with it. The enterer holds the thread in his left hand and repeats the operation with the hook, only selecting the first eye on the next headle, and draws through the second thread, which his assistant has picked out at the cross and placed on the hook. However many headles there may be in the harness, the first hook in each is filled before the first headle is returned to for the beginning of the second course. The keeping of this regular course all through the harness is of the utmost importance. As the entering proceeds, the entered threads are loosely tied together in small bunches, in order to prevent their slipping back again through the eyes.

Method of
entering the
Harness

Another pair of slings, marked E in the drawing, is placed in front of the harness. To these the reed is tied as shown at No. 4. The assistant now sits in front of the harness, and the enterer stands over him. The enterer thrusts the reed-hook No. 3 down through the first dent of the reed. The assistant holds the first bunch of threads in one hand, after having untied the knot. He traces out the thread coming through the first eye in the harness and places it upon the hook, which is then drawn up and treated in the same manner as when drawn through the harness. The first thread in each headle is taken in succession, and then the second,

Entering
the Reed

* In England usually the back headle is first ; on the Continent it is the front.

Gating the Loom and so on to the end. When the reed is all entered and the bunches of threads safely knotted, the loom will be all ready for the weaver to *gate*, as the adjustment of the parts of the loom for actual weaving is called.

The gating of the loom is always done by the person who is to weave the material upon it, as every weaver has his, or her own ideas as to the best way of adjusting the various parts for the work. It will therefore only be possible on this point to state the principal matters that have to be attended to. In the first place, cords must be attached to the top laths of the headles, preferably the back one, and passed over the pulleys of the centre cross-piece, in order to meet and be joined to short strings coming from the other headle. It is necessary that these, and, in fact, all the cords of a loom, should be so tied as to be easily adjusted to a nicety as regards length; the manner of doing this is, once for all, explained in Note 2 at the end of this chapter. When the headles have been securely connected by the cord, the slings at D, fig. 47, must be removed as well as those on which the reed is resting. The reed itself may, for the moment, be allowed to hang loosely from the harness, suspended by the knotted warp. The space in front of the headles being thus cleared, the batten must next be hung on its rocker in the position and manner shown at fig. 42. The cap of the batten, E, fig. 46, being removed, the reed can be fitted into the groove at the back of the race-block. This groove must be deep enough for the round edge of the reed to be completely buried, so that the silk or other threads of the warp may press on the smooth shuttle-race, and not

fray against the lower edge of the reed as the batten is moved backward and forward. The top edge of the reed is next to be caught in the groove of the reed-cap and the latter screwed by wing-nuts to the swords of the batten. The harness must then be brought to its proper place, by moving forward the cross-piece from which it hangs. The nearer it can be allowed to be to the reed the better, so long as it does not interfere with the swing of the batten. The greater the space between the batten and the harness, the larger the opening has to be made in order to be effective in front of the reed where the weft has to be shot. A large opening has the disadvantage of increasing the strain on the warp threads. The harness and the treadles will now be ready to be connected. A long cord must be tied, at both ends, to the bottom laths of each headle, as in fig. 42, and from the separate treadles, exactly underneath these cords, a double cord must be brought up, and joined to them by the adjustable slip-knot described in Note 2. It now only remains to arrange the friction brake on the cane roller as in figs. 42 and 43, to remove the side-cords and weights, A, C, C, C, fig. 47, to gently clear and separate the warp threads and move the rods as far back as possible, in order to finish the preparation, or *gating*, of the loom for actual weaving. (See end.)

NOTE 1, p. 90.—It is very important that the loom-posts should be set up exactly square, in order that the two rollers may be parallel to one another. Before they are permanently fixed they may be tested by a diagonal measurement being taken from the back left-hand post to the front right-hand one. If the distance between the back right-hand post and the front left-hand one

Notes

Notes proves to be the same as that between the two others, the loom will be found perfectly square. The posts should be tested with a plumb-line for uprightness, and the rollers and all horizontal parts with a spirit-level.

NOTE 2.—In order to nicely adjust the length of the various cords for tying up the loom, a very simple slip-knot is used. A reference to figs. 21 and 21A, pp. 40 and 41, will be of use in describing it, as the first loop of the slip-knot is there illustrated. It is usual to *tie up* with double cords, as these always terminate either in a loop or two ends, both of which are necessary for the adjustable slip-knot. The cords to be thus joined are shown at A, fig. 48. The loop for the slip-knot is made at the end of the looped cord in the manner shown at figs. 21 and 21A. Through the loop thus made the two ends of the cord are passed as at B, fig. 48, and tied together in a single knot, after the loop has been drawn close round them, as at C. By pulling the two ends of the single knot the latter is drawn close to the loop, and it will be found, that, whatever weight is hung on the cords at D, the knot will not give way in the least. If, however, the ends of the cord are pulled up, it can be shortened at will, and if the knot is loosened the cord may be adjusted with great accuracy.

NOTE 3.—A large number of cords of exactly the same length are often required in tying up a loom. A simple way of measuring the lengths off, is to drive two nails into a board, or wall at the necessary distance apart, and to wind the cord on to them. If double cords are wanted the skein so made can be cut through at one end only, but if single cords are required both ends will have to be cut.

NOTE 4.—The weaver must know how to make the leashes for the headles of the harness, as well as the smaller ones for the heck of the warping mill (fig. 25, No. 4), as they often break and have to be renewed. For use with coarse warps of linen, woollen, or cotton threads

the leashes act quite as well if made separately and simply slipped, or tied on to the headles. When such

Notes




FIG. 48.—Knots

a warp is entered the action of the loom in working is sufficient to keep the leashes in their proper places on

Notes the headles. When the leashes are thus separate and movable the harness can be adapted for different counts and widths of warp, so that, when practicable, it is as well to have them so. But in the case of fine silk or cotton warps, of a great number of threads, the leashes must be fixed, and carefully spaced and knitted together on the headles. The appliance for making the separate




FIG. 49.—Headle or Leash Gauge.

leashes is shown at fig. 49. It is simply a board about fourteen inches long, one inch thick, and six inches deep. On the top edge are four smooth metal, or strong wooden pegs, arranged as in the drawing. The short loop A is made first, on the pegs 2 and 1. The thread is passed through it, and the centre loop, B, is tied round pegs 2 and 3, being double-knotted to prevent its slipping. The leash is finished off by the ends of the thread being tied together round peg 4. The size of the small loop or eye B, is regulated by the position of the pegs 2 and 3. When a large number of leashes are wanted, time may be saved by tying several A loops

before turning the board to tie the double loops B, C. The board may either be held between the knees of the worker or be fixed on a table in such a way as to be easily turned.

NOTE 5.—The knitted and spaced leashes for fine weaving have to be made on a frame prepared for the purpose (fig. 50). It is constructed as follows: Two




FIG. 50.—Headle Frame.

strong laths, A, A, four inches wide by half an inch thick, and at least three feet long, are neatly mortised into two thick end-pieces, B, B, so as to form an oblong frame not less than fourteen inches wide. The corners are not permanently fixed, but are held together by movable pegs. A wooden lath or brass rod crosses the frame, from end to end, passing through the end-pieces rather nearer to one lath than the other. The diameter of the rod or lath is determined by the size of the eyes the leashes are required to have. Both laths, A, A, are marked out in inches from one end to the other. This is for the spacing of the leashes, so many to the inch. The harness thread, which is made specially strong for the

purpose, is wound upon a small *mesh*, such as is used for the making of string nets.

The leashes are knotted to a strong, thin cord, which is tied and wound several times round one end of each lath and tightly stretched along the outer edge of the frame to the other end, where it is also wound and tied. As in the case of the separate leashes, the small loops of the continuous leashes are made first. The thread must be double-knotted to the cord by means of the mesh at the place where the headle is to begin. The mesh must then be passed round the brass rod, underneath the lath, and the thread again tied to the cord. Another loop is made in the same manner without severing the thread, and so on until the right number are made to the first inch. These being adjusted, the second inch can be made in the same way, and so on till the complete number required has been reached. In the drawing the loops are shown loose in order that their interlacement may be indicated, but they must actually be just tight enough to lie straight on the frame without bending the rod. The thread for the double loops must be tied at the beginning to the opposite lath in the same way as for the single ones. The mesh must then be passed under the frame and brought up through the opposite loop, over the rod, and, usually, double-knotted close by it; then, being brought over the lath, it must be knotted at the place it started from. The first leash will now be complete, and all the others must be finished in the same way. The eyes of the leashes for silk-weaving are not always double-knotted; many weavers prefer single knots as being less bulky. Single knots are, however, especially when the harness is new, very apt to slip out of place and give trouble. When finished the centre rod is drawn out of the frame, the pegs removed from the corners, and the collection of leashes thus freed is tied, by the cord to which they are knotted, to the laths of the headle.

CHAPTER VIII

THE ACCESSORY APPLIANCES OF THE LOOM

The Hand-shuttle—Superiority of Hand-shuttle Weaving—The Fly-shuttle—The Batten for the Fly-shuttle—The Raceboard—The Shuttle-boxes—The Pickers—The Picking Stick—The Action of the Fly-shuttle—Advantages of the Fly-shuttle—The Temple—The Skein Reels—The Doubler—The Quill-winder—Other Tools—Method of Weaving with Hand-battens—Method of Weaving with Box-battens.

THERE can be no doubt that as long as the upright loom only was used, the weft was passed through the opening in the warp in little skeins wound on the hand, or on the long spindles on which it had been spun. But as soon as the horizontal position of the warp was adopted, especially for plain weaving, it is certain that some kind of shuttle for carrying the weft came into use. The advantage given by the invention of the shuttle, was, that it could be thrown swiftly by the weaver through the opening, from edge to edge of the cloth. The ease and speed of the work would thus be considerably increased.

The hand-shuttle now used for silk-weaving is a

The Hand-shuttle very different tool from the shuttle of the ancients, if we may judge from the few specimens preserved in the British and other museums. The general shape of it is, however, very similar. The chief qualities required in the shuttle are slenderness combined with a capacity for carrying a great length of thread, weight, in order to steady it in its rapid movement, and perfect smoothness of finish, so that it may run from side to side over the most delicate threads without catching up or fraying them.

Description of the Hand-shuttle The best hand-shuttles are made of good, hard, boxwood. They are about eight inches long and one inch wide by three-quarters of an inch deep. The general shape and section are shown in fig. 51. The front edge, lower line, no. 1, is straight, and the back edge, which, when the shuttle is thrown, is towards the reed, is curved near the ends. At the ends, which are sharp and smooth, slips of metal are inserted in order to protect the points from damage should the shuttle fly out and fall. The curved shape of the ends is beautifully adapted for delicate throwing and catching. The top of the shuttle is flat, with rounded edges, but the bottom has the edges not only rounded, but slightly raised, in order to present less surface for friction with the threads over which it slides. The shape of the bottom is shown by the section at no. 2. In the centre of the top of the shuttle an oblong hollow is carved, as deep as it is wide. This is for the reception of the *quill*, as it is called, on which the weft thread is wound. At each end of the hollow a small, flat hole is made, and into one of these a minute, spiral spring is fixed. By means of this spring a piece of thin, hard steel wire, bent

in the form shown at no. 3, is kept in position, after it has been inserted by pressing one end against the spring and allowing the other end to be pushed by it into the opposite hole. The bent wire is for the purpose of holding the quill in the hollow of the shuttle, and it is bent to the shape shown in the drawing in order that it may act as a gentle brake to prevent the quill being unwound too freely. By

Description
of the Hand-
shuttle




FIG. 51.—Hand-shuttle.

means of closing up or extending the ends of the bent wire the tension of the thread on the quill can be regulated to a nicety. At no. 4, the quill, with weft wound on it, is shown on the wire; it may also be seen in its place in the hollow of the shuttle in no. 1. The quills are now mostly made of paper, but occasionally a weaver will prefer a quill made of a small piece of hollow reed. Originally, no doubt, feather quills were used, as the name denotes. As the shuttle is thrown from side to side, the weft is unwound through the small hole shown in the centre of no. 5, into which a porcelain or glass eye is fixed. The quill must be short enough to move longitudinally as the weft is unwound, or the latter will be apt to break, how-

The Hand Shuttle in use ever skilfully it may have been put on to the quill.

Fig. 52 represents the hand-shuttle in use. It is lightly held in the right hand of the weaver, partly within the open shed, and resting on the race-board, ready to be thrown by a slight, quick wrist movement. The throw causes it to glide along the beading, over the lower warp threads, to the opposite edge, where it is caught by the fingers of the left hand and guided into the palm. As soon as it is out of the shed the hand is withdrawn from the batten. This allows the reed, fixed in the batten, which has been held off by the thumb of the left hand, to fall against the weft and press it home. In the meantime the right-hand thumb is prepared, as soon as the blow has been given, to push the batten away for the next throw of the shuttle from left to right. In gating the loom the batten is so hung, that when at rest, the reed is just at the place where the weft is to lie. THE QUALITY OF THE WORK DEPENDS VERY MUCH UPON THE WAY IN WHICH THE SHUTTLE IS CAUGHT AND THE THREAD DRAWN THROUGH THE SHED. IN FACT, IT IS THE DELICATE MANNER IN WHICH THIS CAN BE DONE WHICH MAKES GOOD, HAND-SHUTTLE WEAVING SUPERIOR TO ALL OTHER KINDS WHATEVER.

The Fly-shuttle

The simple invention of the fly-shuttle, in the eighteenth century, was an extremely important event in the history and development of weaving. Its effect will be referred to later on, but it will be best to describe its construction in the present chapter, in which the weaver's tools are especially being dealt with.

The fly-shuttle differs from the hand-shuttle




FIG. 52.—Method of handling One, or Two, Shuttles.

If more than two shuttles are used they are
laid in order on the web.

The Fly-shuttle

both in form and in the manner in which it is thrown and caught. The shuttle itself is represented in fig. 53. The difference in its form will be at once perceived. The fly-shuttle has both sides curved exactly alike, and the metal points are set exactly in the centre of the ends; they are also heavier than those of the hand-shuttle. The shuttle itself is longer, and deeper and broader in proportion




FIG. 53.—Fly-shuttle.

to its length. The weight of a fly-shuttle for silk-weaving is from three to four ounces, but for heavy work and power-loom weaving it is made much heavier. The oblong hollow for the reception of the quill, or spool, is in the same position as in the hand-shuttle, but differs in that it is cut right through. The opening at the bottom, however, is not so large as at the top. It is shown in the section between the runners b, b, and also in no. 2. In the hollow at no. 1, instead of the bent wire on which the quill is fixed, a thin metal spike is securely fastened. This spike is hinged at the end near where it joins the shuttle, so that it can be

turned up into the position shown in the side view The Fly-
view, no. 3. For use, in this shuttle, the weft shuttle




FIG. 54.—Fly-shuttle Batten.

is wound on to small hollow boxwood *plugs* (no. 4). When filled, these are pressed on to the spike, which is then turned down into the hollow. The weft, which is put on the plug in

The Fly-shuttle

such a manner that it unwinds uninterruptedly from the end, is threaded through the endmost hole, no. 3, and in and out of the other holes; according to the degree of tension desired by the weaver. In order to increase the weight of the boxwood, both the fly- and hand-shuttles often have holes drilled into them, which are filled with plugs of lead. The ingenuity of the fly-shuttle invention does not, however, lie in the shuttle itself, but in the contrivances for throwing and catching it. These consist of the shuttle-box, the picker or propeller, and the picking stick.

The Fly-shuttle Race

The *shuttle-box* is constructed on the race-block, extended, for the purpose, to about fourteen inches beyond the swords, on both sides of the batten (fig. 54). The shuttle race in a box-batten, instead of being merely a small rounded beading as in the hand-batten, is a perfectly even strip of hard wood, not less than two and a half inches wide, and long enough to reach from A to A, fig. 54. It is slightly bevelled, and when glued firmly to the race-block the surface gently slopes toward the reed. It is bevelled at such an angle that when the batten is pushed back, the race cannot slope outwards and cause the shuttle to fly off, as it passes along. The shuttle race has to be most truly and evenly made, as the least irregularity on its surface is fatal to the action of the shuttle. No. 2 is a section of the race-block, the race itself being indicated by solid black.

The Shuttle-box

The shuttle-box is shown in section at no. 3. It will be seen that it has a high back and a low front, C and B. Also that a groove is cut in the race. This groove extends from the end of the box to the edge of the sword D, no. 1.

Immediately over the groove, and a trifle longer than the groove itself, a thin metal rod, having a small flat head, is fixed. It is passed through a screw staple which projects from the sword to a hole in the end of the shuttle-box, where it is fastened by a screw and wing-nut, E. The Shuttle-box

The *picker* is represented at no. 4. It is usually made of buffalo-hide, which is very tough and hard, qualities most necessary for the purpose. Two pieces of hide cut to the shape of G, no. 4, are joined together by a piece of hard wood, strengthened with twisted wire, as at F. The tongues at the bottom of the pickers fit easily into the grooves in the bottom of the shuttle-boxes. The iron rod E, no. 1, passes through the hole at the top of the picker indicated by the dotted line (no. 3). No. 1 shows both boxes fitted up, each being furnished with a picker. The pickers have to move freely and firmly from end to end of the shuttle-box to the fullest extent allowed by the iron rod. The Pickers

The *picking stick* is represented at H, no. 1. It is simply a convenient handle attached to the centre of a strong cord, which is long enough to join the two pickers together loosely as in the drawing. It will now be readily understood that IF THE PICKING STICK BE PULLED WITH A SLIGHT JERK TO THE LEFT, THE SHUTTLE IN THE RIGHT-HAND BOX WILL BE DRIVEN OUT BY THE PICKER, ACROSS THE RACE, INTO THE OPPOSITE BOX. IT WILL THERE BE CAUGHT BY THE OTHER PICKER, AND ANOTHER JERK FROM LEFT TO RIGHT WILL BRING IT BACK AGAIN. This, roughly speaking, is the method of using the fly-shuttle. The Picking Stick

Action of the Fly-shuttle

Advantages of the Fly- shuttle

The advantages of the use of the fly-shuttle are, mainly, two: (1) The weaving can be done with increased speed. One hand only is required to work the picking stick, the other being left free to manipulate the batten, the beat of which may consequently be made much more rapid. (2) Webs of great width, which would be impossible to weave with a hand-shuttle, can, by means of the fly-shuttle, be as quickly woven as narrow ones. It is very rare to find any woven stuff, more than thirty inches wide, made before the invention of the fly-shuttle. If ever such wide work were attempted, two weavers were employed, one to throw, and the other to catch the shuttle.

It should also be noted, that, the invention of the fly-shuttle rendered that of the power-loom possible. the throwing of the shuttle being the chief difficulty which the inventors, who attempted to apply steam-power to the loom, had to overcome.

The Temple

The temple is an appliance that should not often be required in hand-loom weaving. If the warp and weft are properly proportioned one to another, the cloth, as it is woven, will not "draw in" narrower than the entering of the warp in the reed, to any appreciable extent. When, however, it is found that this "drawing in" takes place, it may be readily corrected by the use of the temple.

The temple for hand-loom weaving is quite simple in construction. Two pieces of hard wood are cut to the shape shown in fig. 55, no. 1. At the broad end of each of these a row of fine points is set. These, when joined together, are for the purpose of holding out the edges, of the material being woven, to the required width. The means

of adjusting the length of the temple are shown at A and B, nos. 1 and 2. A is a loose metal band fitting closely to the two parts of the implement. B is a long pin, which may be put through any of the holes in the two members, in order to join them together. The pin is first inserted, and the temple placed on the cloth a few inches from the reed, with the end points catching the edges of the

The Temple




FIG. 55.—Temple.

material. This position is shown at no. 3. When placed thus, if the temple be pressed down it will slightly force out the edges of the web. The metal band A will keep it flat if slipped on as at no. 2.

When the weft is supplied to the weaver in skeins, a pair of reels, mounted on a stand in such a manner that the distance between them can be regulated, will be required (fig. 56). The upright of the stand has a slot cut in it for the greater part of its length. The reels revolve on elongated axles, and may be fixed in the slot, at any height, by means of a screw and collar. This is for the purpose of adjusting them to different-sized skeins. The weft is usually wound

The Skein
Reels

The Skein
Reels
The
Doubler

first on to bobbins, and from the bobbins on to the quills or plugs ready for filling the shuttle.

Several threads of weft often have to be slightly




FIG. 56.—Skein-winder.

twisted together in order to make up the required thickness for each shoot. It is seldom, indeed, that a weft is made up of less than two ends. The little contrivance generally used for this *doubling*, as it is called, is shown in fig. 57. It has a solid square stand, A, and an upright, B, from the top of which a short arm extends, having a smooth hook, C, at the end of it. About a foot above the stand there is a shelf, D, in the centre of which a thin tube of glass, or metal, is fitted into a hole. The tube is small enough to go through the hole in a bobbin

when one is stood over it in the centre of the shelf. For example, let it be supposed that four threads of weft have to be wound together on a quill. Three bobbins must be placed on end, together,

on the stand, in such a position that the silk upon them all unwinds in the same direction. The three ends of thread from these bobbins have to be carried up through the tube in the shelf D, on which the full bobbin, E, has previously been placed, as shown in the drawing. The ends of the threads from the four bobbins are then taken over the hook C, and as the silk is drawn off the bobbins, that from E gently winds round the other three threads and loosely unites them. No. 2 shows the shape of the rimless bobbins used for weft.




FIG. 57.—Doubling Stand.

The *quill-winder* is a very important adjunct to the loom, as good winding is very necessary for successful weaving. This is especially the case when several threads are wound together on the quills. A drawing of the most useful kind of winder is given in fig. 58.

A small, low table, about two feet long, has two,

The
Doubler

The Quill-
winder

The Quill-
winder

firm uprights fixed near the right-hand end. Between these a small, heavy wheel, having a broad, shallow groove on its edge, is truly poised on an axle, which terminates in a small handle. By means of this handle, the wheel can easily be made to revolve with




FIG. 58.—Quill- or Plug-winder.

great rapidity. At the opposite end of the table a slot, A, is cut, and into this a shaped block is made to fit. The large screw C, which, after passing through the edge of the stand into the slot, runs into the block, not only secures it firmly in position, but is used to regulate the distance between the block and the wheel. D, D is a pair of thick leather bearings, in which a metal spindle, having a pulley in its centre, is carefully fitted. The pulley is connected by a cord to the large wheel, and the latter being turned causes the spindle to revolve with great rapidity. The elongated end of the spindle E is tapered, so that the hollow plugs or quills can be fixed on it, and on these the weft is wound very carefully as the spindle

revolves, and with perfect evenness (see Note 1 at end of chapter, p. 127).

Fig. 59 represents the weaver's shears, the picker and nipper, and the rubber. The shears and nipper are in constant requisition, but need no explanation. The rubber is made of sheet steel, with a wooden handle, and is used for rubbing the surface of the woven material after it has been cleared of knots and ends. Its




FIG. 59.—Shears, Picker and Nipper, and Rubber.

use is particularly needed in plain silk-weaving, the evenness and beauty of which it much enhances.

The hand-loom for plain weaving and all its appliances, as well as the necessary preparations for the work itself, having been described, the actual process of making cloth, both by hand-shuttle and fly-shuttle, will only require a very brief explanation. For this purpose reference must again be made to fig. 42, which fairly represents a gated loom, except in respect to the harness, which is placed too far from the batten. This was purposely done in order to show the headles quite clearly.

The weaver takes his seat in the loom, his feet

The Quill-winder

The Shears, Nipper and Rubber

Method of Weaving

Method of
Weaving

lightly resting on the treadles. He begins by pressing with his left foot the treadle on which it rests. This immediately raises the back headle and depresses the front one. The result of this action is the first open shed. On pushing back the batten a few inches, by pressing the thumb of his left hand against it, a part of the shed appears in front of the reed, and if the loom be properly gated, the opening will be found large enough for the insertion of the shuttle. The method of throwing the hand-shuttle has already been fully described at p. 114, and should here be referred to, together with fig. 52, which shows the hand-shuttle in use. It must be added, however, that as soon as the shed is free from the shuttle after every shoot, and the batten is released in order to beat the weft into place, the opposite treadle must simultaneously be used and the shed changed. This prevents the newly laid weft from springing out of position, and makes all ready for the following shoot. It must also be emphasized, that, when catching the shuttle after the second and following shoots, the weaver gives a slight pull to it, which causes the weft to lie straight in the warp, and brings it exactly to the edge, where it turns in, at the opposite side. Unless this is properly done the *selvage* will be disfigured either by a pucker or a loose loop.

As the weaving progresses the breast roller has to be turned from time to time, in order to roll the newly made cloth upon it. This is done by means of a short, strong stick which fits into the holes in the roller, one of which is shown near C, fig. 42. (See *take-up motion*, note 2, at end of chapter).

With regard to the friction brake on the cane

roller, both the heavy and light weights must be kept suspended. Neither must be allowed to approach too near either to the roller or the floor, or their effect will be marred.

Method of
Weaving

When the box-batten and fly-shuttle are used, the left hand of the weaver is kept on the cap of the reed (fig. 54), near to its centre, and the right hand holds the picking stick. The way the box-batten is balanced in the loom is rather different from that of the hand-batten. Instead of the weaver merely allowing the batten to fall against the weft to beat it together, in this case, he pulls the batten towards him with his left hand, with whatever force is required for the blow. The box-batten, therefore, is not hung so near to the front of the loom as the hand-batten. The quality of the work, when the fly-shuttle is used, depends, of course, mostly upon the way in which the picking stick is manipulated. The shuttle has not only to be driven by a jerk of the hand, but to be caught on the picker at the other edge in such a way as to cause it gently to slide into the shuttle-box without any rebound. The knack of doing this, as it should be done, by a simple drop of the hand, is only to be acquired after a great deal of practice. The evenness of the selvages of the web, which is the final test of good weaving, depends almost entirely upon the manner in which the shuttle is caught in the box.

Weaving
with Box-
battens and
Fly-Shuttle

NOTE 1.—The winding of the plugs or quills for the shuttle is most important. If it be badly done it is impossible to do good weaving. This is particularly the case with regard to winding for the fly-shuttle. Loose, uneven shoots, knots, loops, and all sorts of disfigurements in the web, are the result of careless winding ; to say nothing

Notes

Notes

of breaking threads and the flying out of the shuttle from the loom. Fig. 59A will show the proper method of winding the weft. No. 1 is the correct shape of a wound quill. No. 2 shows the way it should be started. The thread must first be wound from A to B, and each layer should gradually diminish in length until the shape of No. 1 is attained, and is finished off in the centre.




FIG. 59A.—Quills and Plugs.

The plug for the fly-shuttle (no. 3) must be so wound, that it will run off clearly from the point. It must be filled up at the thick end, to its full size, and the shape of no. 4 must be retained until it is finished off at the thin end. A well-wound plug will run off quite freely from the fixed plug, in a single thread, from beginning to end. A badly wound, soft quill or plug will come off in lumps, get entangled, and give much trouble to the weaver.

NOTE 2.—What is called a *take-up motion* is sometimes fitted to a hand-loom. This is an arrangement of cog-wheels, or worm and wheel, which causes the cloth to wind on to the breast roller automatically as it is woven. That this is not necessary is proved by the fact that weavers usually wind the motion by hand, instead of connecting it to their treadles or Jacquard machine, as is intended.




Plate VII.—Tapestry Ornaments. Fragment of a Robe of Amenhetep II., found in the Tomb of Thothmes IV. Amenhetep, whose Ka name is woven in the design, reigned in Egypt, B.C. 1500.

See page 133.

FRONTISPIECE TO PART II.

Cairo Museum.

PART II
SIMPLE PATTERN-WEAVING

PART II

SIMPLE PATTERN-WEAVING

CHAPTER IX

TAPESTRY-WEAVING

A Definition of Pattern-weaving—Ancient Textile Decoration—The Origin of Tapestry-weaving—Tapestry a Variety of Plain Weaving—The Effect of tight and loose Wefting—Tapestry-weaving necessarily an Artistic Handicraft—Tapestry akin to Embroidery.

THE art of pattern-weaving consists in the mechanical repetition of a simple or a complex ornamental design, wrought in as the fabric is being woven, and occurring at regular intervals in more or less obvious geometrical shapes and spaces. With this kind of pattern-weaving there is no evidence to prove that the ancients, with the exception, perhaps, of the Chinese, had any acquaintance. The webs of Egypt were famous throughout the ancient world, and the Egyptians exchanged the productions of their looms for the manufactures and other merchandise of neighbouring, and even far-distant, nations; but amongst the examples of Egyptian webs, so many of which

Definition
of Pattern-
weaving

Pattern-
weaving
Unknown to
the Ancients

Pattern-weaving have been preserved to the present time, there have been found no specimens of mechanical pattern-weaving. It is true that a few trifling attempts seem to have been made to vary the texture and appearance of these ancient weavings, by means of the use, both in warp and weft, of different-sized and different-coloured threads, but even these are extremely rare, and in some cases may even be accidental.

Unknown to the Ancients

The Kind of Textile Decoration practised by the Ancients Although the mechanical weaving of design does not seem to have been practised by the ancient Egyptians, it must not be supposed that the plain, fine webs made by them remained undecorated, for, on the contrary, many of them were highly ornamented. Such ornamentation, however, was not produced in the loom automatically or in the actual texture of the fabric. It was added to the material either when in progress or after it was finished, and was done by means of painting, dyeing, stencilling, stamping, printing, or embroidery, with or without a needle. The designs thus applied to these ancient textiles consisted, for the most part, of bands of ornament and detached spots powdered over the ground.

Origin of Tapestry-weaving Towards the middle of the dynastic period in Egypt (B.C. 2000) the fine linen mummy-cloths, which had hitherto been quite plain, are found to have stripes of different-coloured weft, occasionally shot across them. They also often have short spaces of warp left unwoven, forming bands across the material. It may well be assumed that the idea of darning in a pattern on these bare spaces of warp, in imitation of the applied borders of ordinary needle-work, would occur to some enterprising embroiderer, and, being carried out, would be the beginning of a

new form of textile decoration. This in turn might lead to the cutting away of the weft in spots and spaces, as in drawn-thread work, and to these being filled in with darning in a similar manner. At any rate, whatever may have been its origin, there is now evidence that such work was done in great perfection as early as B.C. 1500. It was practised as a traditional method for the ornamentation of woven materials in Egypt until the Ptolemaic period (B.C. 305), was continued through the Roman period and during the early centuries of the Christian era. The British Museum and the Victoria and Albert Museum at South Kensington are particularly rich in specimens of the Egypto-Roman work, but at present there are only three samples of ancient Egyptian weaving of this kind known to exist. These are in the museum at Cairo. They were found in 1893, in the tomb of Thothmes IV., who reigned in Egypt B.C. 1450. The smallest and oldest piece of the three has, worked into it, the cartouch of Amenhetep II., who reigned fifty years earlier than Thothmes IV. They are fine, delicate pieces of workmanship, and must be typical of the best textiles of that period (plate VII).*

With regard not only to Egyptian, but to almost all ancient, ornamental textiles of earlier date than A.D. 600, it may safely be said, that, however elaborate they may seem to be, they exhibit only two sorts of simple, plain weaving, and that these two sorts of weaving only differ in the manner in which the weft is laid in the warp.

* For a full and interesting description of these precious fragments see Mr. W. G. Thomson's "History of Tapestry."

Origin of
Tapestry-
weaving

Ancient
Ornamental
Textiles
consist of
only Two
Sorts of
Plain
Weaving

Ancient
Ornamental
Textiles
consist of
only Two
Sorts of
Plain
Weaving

In the plain ground of these ancient webs, the weft is passed across in the shed with sufficient tension to pull it straight, as has been fully explained in Part I., on plain weaving. The effect of this is, that the warp and weft show in almost equal proportion in the finished material. For the ornamental parts, however, the weft is placed quite slackly in the shed, with the result, that, when it is pressed down, the warp is completely covered up and hidden by it. For example, if a white warp be shot with white weft in the ordinary way, white cloth will, of course, be made. But if the weft be changed to black for, say, twelve shoots, a grey stripe or band, across the material, will be made by the mixture of the black weft with the white warp, each showing equally. If, instead of the black weft being shot in the usual way, it be put in quite loosely, the first shoot, when pressed down, will cover the first, third, and all the odd-numbered threads in the front, and the second and all the even-numbered ones at the back. The next shoot will cover the even-numbered threads in the front and the odd-numbered ones at the back, so that, the two shoots together will make a continuous line of black weft right across the cloth. If the loose wefting be continued for twenty-four shoots, the result will be a band of solid black, of about the same measurement as the grey band obtained by the ordinary manner of weaving.

Example of
Tight and
Loose
Wefting

In fig. 60, a piece of cloth worked, in the above manner, in two sorts of tabby weaving is shown. At A, A, A, A the white warp and weft are interlaced in the usual manner. At B, the white warp is shot in the same way, but with a black weft, thus




FIG. 60.—Bands of Tabby and Tapestry-Weaving.




Example of
Tight and
Loose
Wefting

forming a grey band. At C the white warp is shot loosely with black weft, so that the warp is entirely hidden. At D the loose weft, instead of being carried right across, is worked up in pyramidal shapes, from their bases on nine threads to their point on one thread. Into the spaces between these pyramids, diamond shapes, in some other colour are fitted, still with loose weft. They begin on a single thread, and, after filling the space, are diminished again to a point. The triangular shapes now remaining, are filled in with black, until a line is reached at which the ordinary white ta by weaving again begins.

This is precisely the method in which all the beautiful textiles of ancient production, that remain to us, were woven. Figs. 61 and 61A are examples copied from the borders of a Coptic textile in the Victoria and Albert Museum. The exquisite designs of these tapestry-woven ornaments in plain linen webs, have often been commented on, but the technique of the work has seldom, if ever, been described. The spaces for the patterns were either left unwoven, or the weft was cut away, in the desired shapes, after the length of fabric was taken out of the loom, as in drawn-thread work. On the warp threads thus laid bare, the pattern, in two or more colours, was darned by means of a needle, or worked in with the fingers, the loose weft being passed backward and forward between alternate threads in the manner above described.

There are no examples remaining from classic times of tapestry hangings of any considerable size, but it may be assumed that the famous picture tapestries, so often referred to in Greek and Roman



Example of
Tight and
Loose
Wefting

FIG. 61.—Coptic Border.

history and poetry, were made in the same manner as the textile ornaments of these Egypto-Roman and Coptic webs—that is, they were a mosaic of many coloured pieces of simple weaving with a loose weft, the plain ground between the ornaments probably being entirely dispensed with. Whatever may have been the technique of these ancient works, there is no doubt that this was the simple method used in weaving the wonderful Mediæval, Renaissance, and later tapestries with which our museums and private collections abound. It is an interesting fact, that, the loose weft cannot be put in by machinery, or



FIG. 61A.—Coptic Border.

Tapestry-weaving necessarily a purely Artistic Handicraft

thrown swiftly across the web in a shuttle. As this must always be done with judgment, tapestry-weaving is likely to remain a purely artistic handicraft as it has ever been.

Tapestry akin to Embroidery

Tapestry-weaving is really, as has been pointed out, akin to embroidery, and only differs from it, in that it is freely darned or woven in the simplest manner on a bare warp, instead of being wrought upon an already woven material. It was therefore quite appropriate, that it should have been treated of in the volume of the present series devoted to needlework. To that book any reader desirous of following out the subject in detail must be referred.* It was necessary, however, to give some little attention to the matter here, in order that the automatic weaving of repeated pattern might be clearly distinguished from tapestry-weaving.

* "Embroidery and Tapestry-weaving," by Mr. A. H. Christie. Artistic Crafts Series of Handbooks (John Hogg, publisher).

CHAPTER X

THE SIMPLEST WARP AND WEFT EFFECTS OF PATTERN

Further Definition of Pattern-weaving—Patterns possible on the Loom with only Two Headles—The Striped Webs of India—Ancient Use of Striped Cotton Hangings—Patterns resulting from striping the Warp—East African Woven Design—Various Simple Warp Patterns—Simple Weft Effects—Tartan Patterns—Inlaying or Brocading—Primitive Indian Brocading—Usual Method of Brocading—Binders or Ties—Brocading on Weaving Board—Extra Headle for Brocading—Long and Short Eyes of Headles—Cashmere Shawl Weaving—Origin of Brocading.

WE have seen how entirely dependent, in tapestry-weaving, is the working out of any ornamental design, on the artistic skill and taste of the weaver. We have seen also, that as the technique of tapestry is so simple, scarcely any tools or mechanical appliances are necessary in order to weave it. Ordinary pattern-weaving, on the contrary, whether simple or complex, is done by means of certain devices and appliances which have been invented from time to time in the course of ages. By their use the loom is *set up* or *tied up* under the direction of the designer, in such a way, that, when the weaver begins his

Further
Definition of
Pattern-
weaving

Further
Definition
of Pattern-
weaving

shuttling, the design will be woven and repeated automatically, in the loom, as the work proceeds. This being so, the weaver's whole attention can be given to the keeping his loom and all its fittings in order, and his threads of fine silk, or other material, mended and even, both in warp and weft. In a fine silk loom, of thirty or forty thousand threads in the width, this is quite sufficient occupation for one man or woman.

Needless to say, the mechanism by means of which the pattern is worked out, which is often a marvel of ingenuity, was not all invented at one time. In fact, every weaver is continually devising little helps and dodges for his own use. But the most important contrivances were invented very early in the history of the loom, and succeeding generations of craftsmen have only extended and developed them. It must never be forgotten, however, that **EACH STEP TOWARDS THE MECHANICAL PERFECTION OF THE LOOM, IN COMMON WITH ALL MACHINERY, IN ITS DEGREE, LESSENS THE FREEDOM OF THE WEAVER, AND HIS CONTROL OF THE DESIGN IN WORKING.**

Patterns
possible on
the Loom
with Two
Headles only

We must now return to consider the old English loom, fitted up as represented in fig. 42, and inquire as to the possibility of designing patterns which can be woven automatically upon it—patterns, that is, which will work out, as the weaver proceeds, shoot by shoot, as if he were making plain cloth. It is obvious that such designs must be very simple in character, and must depend entirely on some arrangement, or diversity of the threads, in warping. It is interesting to find that a great variety of patterns can be designed to work out in this simple way.

The Indian weavers of fine cotton fabrics have always been famous for warp pattern effects. They were perhaps the first to make use of broad and narrow stripes of contrasting colours in their webs. This is of course the simplest of all pattern effects to be obtained. Many of these Indian fabrics, by reason of their finely contrasted colours and the pleasant proportion of their stripes, are very beautiful in effect, and can be used with great advantage in personal and architectural decoration.

The Striped
Webs of
India

The garden court of the palace of Shushan, where the little drama of Esther and Ahasuerus began, was hung, no doubt, with material decorated with coloured stripes. The hangings are described as of "white, green, and blue, fastened with cords of fine linen and purple, by silver rings, to pillars of marble" (Book of Esther, ch. i. v. 6). This account of an ancient decorative scheme, furnishes us with another evidence of the frequently remarked unchangeableness of the East, for just such striped and coloured webs, are being made by the Indian weaver of to-day on his simple hand-loom, a counterpart of the ancient loom, on which, the hangings for the Persian palace court were woven so long ago.

Ancient Use
of Striped
Cotton
Hangings

By means of striping the warp, in quite a different manner from the above, a large range of small patterns can be made which are very interesting. As these are constructed on the same principle as that on which suitings and homespun cloths are designed, it will be well to devote some little space to their particular consideration.

Patterns
resulting
from
striping
the Warp

A delicate and pretty example of this simple kind of pattern-weaving may be seen in a case of

East African Woven Design “personal ornaments” made by the natives of East Africa, exhibited in the ethnographical galleries of the British Museum (see plate 1). The pattern is in very dark blue (almost black) and bright red, on a white ground. This design, in common with those just referred to, is made by taking advantage of the fact that in plain, or “tabby,” weaving, one shoot of weft has all the odd-numbered warp threads above it and the even ones below, while in the next shoot the order is reversed, the even threads being above and the odd ones below.

Copy of East African Woven Design The collotype illustration plate VIII is taken from a woven copy of the edge of the East African web just mentioned. It is shown in process of making. The loom is simply a small board with a warp stretched on it. The sheds are opened by a shed-stick and leashes as described at p. 85. The actual width of the web is an inch and a quarter, in which space there are sixty threads, eighteen being black and forty-two white.

It certainly appears curious that if white and black threads are warped alternately rather close together, so as to well cover up the weft, the effect of black and white lines running, as might be expected, in the direction of the warp, will not result when the web is woven. Instead of running longitudinally, the black and white lines will be across the web, as in no. 1, fig. 62. In this diagram the black vertical lines represent the odd threads of a warp, and the white lines the even ones. If a shed be made by raising the odd threads and depressing the even ones, it is manifest that only the black portion of the warp will show on the front of the material. The next shed being

made, the position of the threads will all be reversed, and the white portion of the warp now being above the weft, no black will be visible at all. If, as is necessary for this kind of pattern, the warp be full enough to well cover up the weft, the latter will interfere very little with the colour of the latitudinal stripes.

Copy of
East African
Woven
Design

No. 2 shows the warping of an even and odd, and an odd and even black thread, warped alternately at regular intervals in the whole width, the result of this warping being, when the stuff is woven, two vertical zigzag lines with opposing curves.

By warping the black and white threads in the order shown at no. 3 the latitudinal lines given by the warping of no. 1 are cut up into alternate squares, and form a common checker pattern.

The warping of no. 4, weaves into detached squares, and no. 5 forms quite an elaborate pattern, with border.

The warping represented by no. 6 is that of the border of the East African web, a copy of which is shown in plate VIII.


These diagrams give only a few of the designs which can be made for this simple form of pattern-weaving. The number possible is infinite, especially if threads of various colours are used in addition to the black and white ones.

By striping the *weft* an additional number of simple patterns can be made. But weft effects cannot be rendered automatic except by the aid of much more complicated machinery than the loom, as at present described, is furnished with. For weft effects, the weaver would have to count his shoots, or measure off spaces, in order to keep any

Simple
Weft Effects

Warp.


Effect.




1

Warp.


Effect.



3



2



4





Plate VIII.—Copy (in progress) of a Portion of the East African
Web illustrated by Plate I.

See page 143.


By the Author.

Warp.

Effect.



5



6

FIG. 62.—Warping Patterns.

Simple Weft effects uniformity or proportion in the stripes. As already noticed, by striping the weft, the Egyptians first began to ornament their plain weaving. It is quite probable that the stripes of red, blue, white, and purple, in the hangings made for the Hebrew tabernacle, were weft effects. If these were so the striping would be horizontal, and would form a fine background for the gold figures of cherubim, which, we are told, were wrought cunningly on them with the needle.

The Principle of Tartan Patterns By means of striping both the warp and weft in various colours, the well-known *tartan* effects are produced. The tartan is a very ancient kind of ornamental weaving, and is capable of an infinite number of combinations. This is proved by the variety and individuality of the Scottish *plaids*. It has been supposed that the "variegated webs made by Sidonian women" mentioned by Homer, were a kind of tartan mixture of colour.

Example of Tartan Striping Fig. 63 shows the manner in which tartan striping is arranged. In this case both warp and weft are variegated by stripes of blue, red, yellow, and white.

At the crossing of the stripes the additional mixed colours made are, deep red, deep blue, orange, green, and purple. When fine, rich colours and good yarns are made use of, very gorgeous effects can be obtained in this simple manner.

Other Methods of ornamenting Simple Webs There are many other easy methods for ornamenting plain woven webs, such as the use of different-sized threads, both in warp and weft, the use of different materials, such as glossy silk or cotton in contrast with linen or woollen yarns, the use of threads of different twist texture, &c., &c. ;




FIG. 63.—Tartan-weaving.

Other Methods of ornamenting Simple Webs so that even with quite the simplest looms, plenty of scope is given for the exercise of ingenuity and design.

Inlay or Brocading

An ancient and favourite method of decorating woven fabrics was by inserting, in addition to the ordinary weft, secondary wefts of rich threads, such as gold, silver, silk, or rich coloured wools. These additional wefts were so arranged as to form spots, or detached ornamental shapes, distributed over the ground. This decoration is called *inlay* or *brocading*. At the beginning brocaded ornaments were not worked automatically in the loom, as they afterwards gradually came to be. It will be necessary, therefore, as well as advantageous, to trace, as nearly as possible, the manner in which the brocading process was developed. Especially as it led to some of the most important inventions in the history of weaving, and, moreover, many suggestions useful to the artistic craftsman may be gathered by the way.

Indian Brocading

A most primitive manner of brocading is described by Dr. J. Forbes Watson in his book on the textile manufactures of India, as follows :

Dr. Forbes Watson on Indian Brocading

“Two weavers sit at a loom. They place the pattern, drawn upon paper, below the warp, and range along the track of the weft a number of cut threads equal to the flowers or parts of the design intended to be made. Then with two small, fine-pointed, bamboo sticks they draw each of these threads between as many threads of the warp as may be equal to the width of the figure which is to be formed. When all the threads have been brought between the warp they are drawn close by a stroke of the reed. The shuttle, with ordinary weft, is

then passed by one of the weavers through the shed or opening in the warp, and the weft having been driven home, it is returned by the other weaver. The weavers resume their work with the bamboo sticks, and repeat the operation of the reed and shuttle in the manner above described, observing each time to pass the cut threads between a greater or less number of the threads of the warp, in proportion to the size of the design to be formed."

Dr. Forbes
Watson on
Indian
Brocading

Although brocading is sometimes done in the way described above—viz., by using short pieces of coloured threads cut to the required sizes—it is much more usual to find a continuous thread, carried in a small shuttle, made use of for the purpose, each colour, and each separate piece of design having its own shuttle and being worked backward and forward to the shape of the ornament.

More Usual
Method

The working of brocaded ornament into a plain warp between the ordinary shoot, does very well so long as the warp is fine and very scanty, as is the case with that used for the gauze-like Indian muslins. These are open enough to allow the sparkling gold and bright-coloured silk to shine out from between their threads, but in denser warps the ornamentation would be buried and almost invisible if merely placed between the ordinary shoots of weft.

Above
Method
only Suitable
for Scanty
Warps

In order to make these inlaid ornaments have their proper effect in a close warp, the brocading weft must be made to pass under only one in every three or more warp threads, instead of being tied down closely like the ordinary weft. By this means the rich gold or coloured weft not only shows for all it is worth, but, being tied down by

Ties or
Binders for
Brocading

Brocading
or Weaving
Board

only one in every three or more threads, stands clearly and boldly up on the surface of the cloth.

This effect can be tried on the weaving board, fig. 39, and a practical experiment will best demonstrate the theory of ties and binders. The mechanical contrivances for binding the brocaded ornament in the loom can then be readily explained.

For this experiment the board must be set up with thirty-one strings, and plain weaving with self-coloured weft begun on it as in fig. 64, AA. At B brocading commences. It will be seen that the brocaded form in the illustration is drawn in two shades, half-tone and black. These shades may represent any two colours that may be selected. Beginning with the lighter colour, and counting from the right hand, the weft must be brought from the back between the seventh and eighth strings of the warp, passed underneath the tenth, and over the eleventh and twelfth strings. The brocading weft must now pass at the back of seven strings and reappear in the front between strings nineteen and twenty. The coloured thread must then be carried over two strings, under one, over two more, and between strings twenty-four and twenty-five, pass to the back, and be left hanging there, while the ordinary weft is thrown twice across the warp, after the usual sheds have been opened for it. As soon as the shoot has been pressed down the brocading may proceed, beginning this time from the left. The coloured weft must now be brought forward between the twenty-fourth and twenty-fifth strings and taken back, over and under the same strings as in the first line, until it reaches the point of starting. Here it must be again taken to the back, and the two shoots




FIG. 64.—Brocading on Board.

Brocading
on Weaving
Board

of ordinary weft repeated. This will complete the space marked B in the drawing. It will be seen that the brocading in space C must approach three strings nearer to the right and left edges of the web than that of B. In all other respects the space C must be worked in exactly the same manner as B. In space D, however, two brocading colours are indicated. The new colour, represented by black, should be put in first. It will be seen that the black only covers four strings, two on each side of the centre, with a space of seven strings between them. As soon as the dark weft is in its place the lighter colour may be filled to right and left of it, and this being repeated twice, the space D will be filled. At E only the dark colour occurs, and that in the centre of the web, where it covers two spaces of two strings each, with one string between to bind them. From this point the brocaded figure can readily be completed without further instructions. In order more clearly to illustrate the process, at the top right-hand corner of the drawing, the portion D of the brocading is represented in progress, but without the web having been beaten together. At the top left-hand side of the illustration a part of the ground and figure is shown as it would be expressed or designed on weaver's ruled paper.

To return to the old English loom fitted up as in fig. 42. Brocading up to this point and in the above ways may be done upon it without extra appliances. The process, however, of picking up the threads for the binders and counting the spaces in the undivided warp would be a very tedious one. It will therefore be readily understood that it would be a great advantage if the binding threads necessary for the

brocading could be separated in the warp automatically when they were required, without interfering with the making of the plain groundwork of the cloth.

Brocading
on Weaving
Board

The facility of selecting certain threads can be secured if another headle be added to those already in the loom. This additional headle must be so arranged, that, after two or more shoots of plain ground have been made, the proper shed for the brocading may be opened. This shed may be so made as to act across the whole of the warp, or in particular spaces, such as borders of a certain width, at the centre of the web, or at any regular intervals that may be desired. This contrivance not only facilitates the binding of the brocaded figure, but by dividing the threads into small groups makes it much easier to *count in* the shapes of the ornaments, previously designed on ruled paper. The method of drawing figures for inlaying or brocading is shown by fig. 65.*

Use of
an Extra
Headle for
Brocading

The extra headle required for brocading has to be fixed in front of the two already in the loom, and through the eyes of its leashes the warp threads must be entered, after they have passed through those of the ground headles, and before their entry in the reed. The new headle will only require one leash to every three of the warp threads for the production of the brocading suggested by fig. 65, and of

* In designing ornaments for brocading, on squared paper, it must be remembered that each square of the paper represents the group of threads between the binders, and also that the size the figure will be, when woven, depends on the number of ties to the inch laterally and the thickness of the weft longitudinally.

Use of
an Extra
Headle for
Brocading




FIG. 65.—Design for Brocade, on
Ruled Paper.

these, two must be entered together in one eye and one drawn, without entering, between the leashes. The effect of this arrangement will be that, when the new headle is raised, either by an extra treadle or a hand-cord and pulley, two threads will be raised and one left down, right across the loom, or wherever, in the width, spaces to be brocaded are arranged for. Thus the necessary shed for the brocading weft is made. When one line of the brocading has been done and the following shoots of plain tabby ground have been made

the strips of coloured weft will be found slightly but firmly tied down on the under surface of the cloth, which is really the face of it. In a horizontal loom webs are generally worked face downwards, and, indeed, must be if brocaded.

Use of
an Extra
Headle for
Brocading

There must be an important difference between the leashes of the ground headles and those of the brocading headle. It will be at once perceived that if the leashes of the latter had *small eyes* similar to those of the former, the back headles could not work freely, as two out of three of the threads would be fixed by the new row of eyes standing in front of them. This difficulty is obviated by making long eyes in the leashes of the front headle, so that when it is at rest there is room for the ground headles to work without hindrance. It will be found that this arrangement does not interfere at all with the lifting power of the front headle.

Difference
in Eyes of
Leashes

By means of fig. 66 this important difference in the leashes of the two sorts of headles may be readily understood. Nos. 1 and 2 show in section the ground and the brocading headles. In no. 1 the headles of the ground harness are depicted one raised and the other depressed, whilst the brocading headle is at rest. In this position the front headle does not affect the warp at all, the long eye allowing the threads to rise and fall, as necessary for tabby weaving. In no. 2, however, the front headle being raised, takes up with it all the threads entered in it, and allows all those passing between its leashes, which are the binders, to remain at the level of the warp as long as the ground harness is at rest.

Two Sorts
of Leashes

This simple difference between the leashes of the headles, some having long and some short eyes,

Importance
of the Use of
Long and
Short Eyes
in Figure-
weaving

plays a very important part in the development of pattern-weaving. The invention of damask-weaving in particular is based entirely on it.




FIG. 66.—Section of Two Sorts of Leashes.

Cashmere
Shawl
Weaving

The exquisite work which may be done on a loom with mechanical fittings such as have now been described, is shown by the wonderful shawls for

which Cashmere has been famous for many centuries (see fig. 67).

Cashmere
Shawl
Weaving

The process of weaving the Cashmere shawls has been instructively described by a traveller in India : *

“The loom differs not in principle from that of Europe, but is inferior in workmanship, and the factories contain from three to three hundred of them, crowded together into very small spaces. About three weavers work at each loom. When the warp is fixed in the loom the pattern-drawer makes a design in black and white. He shows it to the colourist and the scribe, and they confer together. The colourist, having well considered it, points out the proportion of the colours, and, beginning at the foot of the pattern, he calls out the colour and number of threads to which each is to extend, that by which it is to be followed, and so on in succession until the whole pattern has been described. From his dictation the scribe writes down the particulars in a kind of shorthand, and delivers a copy of the document to the weavers.

“The workmen then prepare the needles by winding on each, coloured yarn of about four grains weight. These needles without eyes are made of smooth wood, and have both their sharp ends slightly charred to prevent their becoming rough through use. Under the superintendence of the colour-master, the weavers next knot the yarn of the needles in their proper places to the warp.

“The face or right side of the cloth is placed next to the ground, the work being carried on at the back, where the needles all hang in a row, making from four to fifteen hundred, according to the lightness or heaviness of the ornament. As soon as the designer is satisfied that the work in one line is completed the reed is brought

* Moorcroft's “Travels in Cashmere,” 1841.

Cashmere
Shawl
Weaving

down upon it, with a vigour and repetition apparently very disproportionate to the delicacy of the material."

It is a grievous fact that this beautiful handicraft of shawl-weaving has almost died out in India, owing to the competition of the cheap, meretricious,




FIG. 67.—Border of an Indian Shawl.

European, machine made imitations of the Cashmere weaving and design, with which the markets of both the East and West were flooded in the last century.

Origin of
Brocading

Before leaving the subject of brocading, for the present, it may be interesting to remark that, no

doubt, like tapestry decoration, it was suggested at first by the work of the embroiderer, to which it bears even a closer resemblance than does tapestry itself. Brocading has been called "embroidering with the shuttle." There is a beautiful passage in the *Iphigenia among the Tauri* of Euripides in which the phrase is used :

"But now beside the ruthless sea I make my cheerless home, an alien, torn from home and friends, with none to call me wife or mother ; never singing Hera's praise, my Queen in Argos, nor mid the merry whirr of looms broidering with my shuttle a picture of Athenia Pallas or the Titans."

CHAPTER XI

SINGLE-HARNESS PATTERNS

Ruled Paper and its Uses—Sketches of Entering and Tie-up—Designs possible on a Loom with few Headles—The Position of Cloth in Weaving—Tying up the Loom—Plan of a Tie-up—Simple Twills—The Broken Twill, its Importance—Origin and Peculiarity of Satin-weaving—The Four-headle Twill—Method of drawing Designs for Simple Looms—Simple Pattern with Tabby Ground throughout, its Advantages.

Single
harness
Patterns

AN important range of small patterns can be woven by the use of a single harness * composed of several headles, and the range may be very much extended by entering the warp in varying order instead of in regular succession.

Before giving a few examples of these patterns, it will be necessary to devote a little space to the explanation of three things. (1) The setting out and use of designer's *ruled paper*; (2) the method of expressing on paper the order in which the warp is *entered* in the headles; and (3) the *tie-up* of the loom, as the connection between the treadles and headles is called, which renders pattern-weaving automatic.

* Leashes with short eyes have some advantages over those with long ones. A single harness, therefore, should be made with leashes having short eyes.

All designs for weaving, except those of the very simplest description, have to be worked out on ruled paper, and it is possible, after a practical acquaintance with the principles of the craft has been obtained, to arrange *all* the details of the most complicated webs in this manner. Fig. 68 will show the manner in which the paper is ruled. In the first place, the paper is always set out in exact squares ruled in thick lines, and these squares are subdivided both vertically and laterally. To the left of the line AA the partial ruling consisting of vertical lines only is shown, and the spaces between these represent the threads of the warp, in some cases single and in others in groups of equal numbers. To the right of the line AA the squares are divided laterally as well as vertically. These lateral divisions are for the purpose of enabling the designer to indicate the weft wherever it is intended to show as it crosses a thread of the warp. The proportional thickness of the weft in relation to the warp is indicated by the size of the spaces in the lateral divisions. For instance, to the right of the line AA the lowest squares, B, are divided into four spaces, both vertically and laterally; this indicates that the weft is of the same thickness as the warp thread, or group of threads, indicated by the vertical spaces. If the weft be thicker than the warp, as would usually be the case if single threads of the latter were intended, the lateral spaces must be larger in order to keep the right proportion in the woven design. In the case of the weft being one-third thicker than the warp the squares would have to be divided 4×3 , as in the middle squares, C, instead of 4×4 . If this were not so the design, when woven,

The Use
of Ruled
Paper for
Designing





FIG. 68.—Ruled Papers.

would be one-quarter longer in proportion to its width than the drawing as set out on the large squares. The general shape and proportion of the design, therefore, is sketched, in the first place, on the thick-lined, large squares, and the edges of the shapes, the details of ties, &c., are worked out correctly by means of the subdivisions. No. 2 shows some of the most usual ruled papers in use, but papers of all kinds of sub-division may be obtained. Unless otherwise specified, in the illustrations throughout this book each vertical space, as well as each lateral one, may be understood to represent only one thread respectively either of warp or weft.



Drawn.

Woven.

FIG. 69.

The filling in of a single space, in a ruled-paper drawing, indicates that in that particular spot the weft crosses the warp and covers it up (see fig. 69).

Fig. 70 shows the method by which the designer indicates to the weaver the way of entering the warp in the harness. The vertical lines represent the warp threads, and the horizontal lines the headles of the harness. The headles are numbered 1, 2, 3, and 4, beginning, as is generally the case, at the back. A tick or dot on the cross-line indicates the headle through which the thread is to be entered.

A HARNESS OF ANY NUMBER OF HEADLES MAY ALWAYS BE UNDERSTOOD TO BE ENTERED IN THE

General
Method of
entering and
expressing it
on Paper

General
Method of
entering and
expressing it
on Paper

Cloth
mostly
woven Face
Downwards

REGULAR ORDER SHOWN IN THE SKETCH, FROM BACK TO FRONT. IF ANY OTHER ENTERING IS INTENDED SPECIAL INSTRUCTIONS ARE GIVEN FOR IT.

In order that the weft may cross the warp as shown in fig. 69, the cloth being made, as is




FIG. 70.—Sketch of entering in Harness of Four Headles.

usual, face downwards, it is of course necessary that the headle in which the warp threads covered by the black cross are entered must be raised, so that the shuttle carrying the weft may pass beneath them. It has already been explained that the headles are raised by means of treadles, which the weaver controls

with his feet, and the simplest way of connecting the headles and treadles for this purpose is shown by fig. 42. There are, however, various ways of doing this, which will be described later on, under the head of *Shedding Motions*, but they are all alike in one particular, which is, that they all provide for the lifting of the headles as indicated on the ruled-paper drawing. This being so, the drawing out of the design is not affected by the particular kind of shedding motion with which the loom, on which the web is to be made, is fitted up.

Tying up the headles and treadles is a matter for the weaver to arrange according to the sequence of rising indicated by the design of the pattern on

Designs on
Ruled Paper
not affected
by Shedding
Motions

Tying up
the Loom

ruled paper, and much ingenuity has often to be exercised in doing this in the most convenient manner for weaving. If, as he were working, the weaver had to think of the pattern, however simple, and the necessary succession of treadles to form it, the weaving would be slow and not automatic. He therefore has to arrange a plan for the *tie-up*, which will allow of his treadling in the order to which he is accustomed, and will, at the same time, cause the headles to rise in such a succession and combination as will work out the pattern correctly.

Tying up
the Loom

The usual order in which a set of treadles is worked is from the outside right and left to the centre. For instance, with eight treadles, the outside right one is no. 1 and the outside left no. 2. Next to no. 1 is no. 3, and next to no. 2 is no. 4. No. 5 is on the right by no. 3, and no. 6 on the left by no. 4. No. 7 is the last trodden by the right foot, and no. 8 the last taken by the left. Some weavers prefer to begin with the left foot and others prefer to work right across, in which cases they make out their plan or draught to suit themselves; but this does not alter the method of tying up.

The Plan
of Tie-up

Fig. 71 shows two plans of tie-up, together with the effect produced by them when woven. They also illustrate the simple method generally used by weavers to indicate the tie-up on paper. Both figures represent a set of eight headles, each harness being entered in the usual straightforward manner. This is shown by the ticks to the right of the diagrams above B. The vertical lines C, C are the treadles, numbered according to the above-mentioned sequence of treadling from the right and left to the centre. The tie-up of the treadles

Examples of
Tie-up

Examples of Tie-up to the headles is indicated by the crosses, on the several lines, at places where they intersect. In diagram 1, where only two treadles are necessary to produce the effect designed at A, each treadle is tied up to four headles, no. 1 to headles 1, 3, 5, and 7, and no. 2 to headles 2, 4, 6, and 8, so that treadle 1




FIG. 71.—Plans of Tie-up.

will raise headles 1, 3, 5, and 7 and produce the effect of the lowest and other similar lines in the design A. The second treadle will in like manner raise the headles for the four alternate lines of the sketch, nos. 2, 4, 6, and 8. Diagram 2 has the same headles and entering as diagram 1, but instead of only two, there are eight treadles, C, C, one headle being tied separately to each treadle. The result of this tie-up, when the treadles are used in the order in which they are numbered, is shown in the sketch above A.


An amazing amount of ingenuity has been exercised by weavers in arranging for the lifting of

large numbers and complicated systems of headles, and pattern-weaving was formerly done to quite an astonishing extent in this manner. The use of simple automatic contrivances has, however, quite superseded the use of an inconvenient number of treadles. But for small patterns, grounds, satins, twills, &c., there can be no doubt, that the direct tie-up of the treadles to the headles is better and more certain in action than any other contrivance whatever.

The principles of the use of ruled paper, the entering of the warp in the harness, and the connection of the treadles to the headles being understood, it will now be interesting to exemplify and examine a few of the patterns that can be woven on a loom with a single harness of only four headles, and an equal number of treadles. Fig. 72 gives examples of the simplest possible designs. The treadles for these are tied up singly to each of the four headles.

At no. 1 a right-hand *twill* is given, with the plan of entering it and also the tie-up of the treadles. The numerals in the circles on the treadle lines show

Examples of Tie-up



Pattern-capacity of a Loom with Four Headles and Four Treadles

Simple Twills

FIG. 72.—Examples of Simple Twill Patterns

Simple Twills

the order in which the treadles are to be worked. At no. 2 the tie-up is seen to be reversed, which throws the twill in the opposite direction, making it a left-hand one. At no. 3 a combination of both the above is shown, the result being a zigzag. This is made by extending the treading as indicated by the numerals in the circles of no. 3 itself, and

may be used with either the tie-up of no. 1 or no. 2 indifferently.

The Broken Twill




FIG. 73.—Broken Twill treadles, but the tie-up is rather different; fig. 73 is a draught of it. It will be seen that the direct diagonal line of the twill is broken by missing headle 2, and making it rise between the fourth and the first headles. The result of this arrangement is that if a rich close warp is being used the weft will scarcely show at all, the tie being distributed so evenly over the ground that no ribs or lines are visible. This is a most ingenious invention, and shows the principle on which the various satins are formed. It is said to be of Chinese origin, which is most probable, as it is particularly adapted for displaying the rich, glossy quality of silken thread, which the Chinese were certainly the first people to use for weaving. Before passing on, it should be noted particularly that IF COUNTED IN EITHER DIRECTION THE SAME NUMBER OF THREADS WILL BE FOUND BETWEEN ALL THE TIES OF THE BROKEN TWILL.

The Origin and Character of Satin Ties

THIS IS THE SPECIAL CHARACTERISTIC OF ALL THE SATINS. FURTHER REFERENCE TO THIS WILL PRESENTLY BE MADE.

Several more extended designs may be made on the same principle as the twill, with four headles and treadles only, if the entering of the warp be specially arranged for them. A sample group of these designs is given in fig. 74, and many others can be devised, both by alteration of the entering, tie-up, or order of working the treadles. The entering necessary for the designs illustrated, repeats once in every twenty-four threads of the warp. It will be seen that three courses of four threads are entered from back to front, then one thread by itself on the back headle, followed by three courses of four threads, from front to back, the fourth thread in the last course beginning the next repeat. If the treadles are tied up and trodden as for ordinary twill a large lateral zigzag will be woven (fig. 1); by working the treadles in the order shown by the numerals in the lower part of the diagram no. 2 will be made; and on taking the treadles in the following order, 1, 2, 3, 4, 13, 14, 15, 16, no. 3 will result.

With the same entering and tie-up plain cloth may be made at will, so that lateral spaces or panels of any of these small designs may be woven by way of ornament at intervals in the plain material. Very pretty effects may be arranged for, especially if the bands are shot with gay-coloured wefts. In order to make the plain cloth in alternation with the ornamental bands, it is only necessary to depress the first and third treadles together with the right foot, for one shoot, and the second and

The Origin
and Character
of
Satin Ties

Extension of
the Four-
headle Twill

Extension of
the Four-
headle Twill




FIG. 74 —Extended Twill Patterns

fourth treadles together with the left foot for the next. Extension of the Four-headle Twill

In order to produce the design shown at no. 4, fig. 74, the same entering and treading are required as for no. 3, but the tie-up must be different (see fig. 75). In this case two headles must be tied up to each separate treadle, in the following order: Headles 1 and 2 to treadle 1; headles 2 and 3 to treadle 2. Treadle 3 has headles 3 and 4 tied to it, and treadle 4 must be tied up to headles 4 and 1. The effect of this tie-up may be seen in the diagram, and requires no further explanation.




FIG. 75—Tie-up for fig. 74, no. 4

It will have been gathered from the last illustration that more than one headle may be tied up to each treadle. This being so, a much greater variety of patterns is possible than would be the case if only single tie-ups were practicable. The tie-up may really be of any number of headles to one treadle, only short by one of the number that would raise the whole of the warp. If four headles are used, one, two, or three




FIG. 76.
Pattern with unequal Tie-up.

of them may be tied to any one treadle, it not being necessary that an equal number be tied to each treadle, as is the case in fig. 75. Fig. 76 is

Extension of an illustration of a pattern and tie-up in which one, the Four-headle Twill two, and three headles severally are connected with single treadles, as will be seen by the plan.

The curious diagonal design fig. 77 requires six treadles tied up to four headles, as shown in the




FIG. 77.




FIG. 78.

plan. The entering in this case is remarkable, as half the warp is raised by means of the fourth headle and the other half is distributed equally over the other three. Plain ground cannot be woven with this tie-up of six treadles, but two extra ones, one on each side of the six, will render it possible. These tabby treadles must be tied up as shown in the plan no. 2.

With the same entering as that of the last design, and a tie-up to three treadles, the pattern fig. 78 can be made, and by the use of treadles 2 and 3 plain tabby ground can also be woven in alternation with broad bands of ornament.

Fig. 79 gives the plan of one of the most elaborate designs workable by this simple method of weaving. It requires the use of a harness of ten headles and a set of ten treadles to produce it. The entering is

Extension of
the Four-
headle Twill




FIG. 79.—Elaborate Design for Simple Weaving.

on twenty threads of the warp, and the tie-up is rather complicated, as will be seen by the plan.

It will have been noticed that this design and plan, (fig. 79) are worked out entirely on ruled paper. This is a convenient method of setting out complicated weavings, as the order in which the treadles follow can be marked in the line of the design they each govern. A careful study of the

Setting out
Complete
Plans on
Ruled Paper

drawing and a comparison of the numerals will elucidate the relation of the various parts one to another. The final arrangement of the position of the treadles for working is always left to the weaver, and is, indeed, quite immaterial, so long as it causes the headles to rise in the order set down in the design. In setting out such a drawing, the entering must be indicated first, and then the design filled in below it on the same number of squares as one repeat of the entering contains. The number in this case is twenty. The scope of this design is also further limited, by the nature of the entering, to a figure having its centre line on the eleventh thread, and both its halves alike except that they are reversed and point in different directions. In weaving this is technically called a *point* design. The length of the design is not limited, as its breadth is, by the entering of the harness; this is decided to some extent by the number of treadles employed. Any treadle, however, may be made to rise and repeat the same lateral line of the design any number of times, and the whole number of treadles, or any portion of them, may be worked backward and forward or in any sequence necessary to form the pattern.

After the design and entering are set out, the design must be dissected, in order to find how many different lateral lines there are in it, as the several headles forming each different line have to be tied up to a treadle. In fig. 79, for example, there are ten different lines, which necessitates the use of ten treadles. By repetition, however, their scope is extended to twenty lines. Many designs will allow of even a great deal more repetition than this.

Designs of the kind exemplified by figs. 71 to 80 are particularly adapted for weaving on small looms such as may conveniently be used in the home. They are very suitable for linen and cotton fabrics intended for domestic use, such as table linen, bed furniture, and simple garments of the kind for which linen and cotton materials are required. These simple woven patterns are for the most part only effective when the yarns from which they are made are not very fine. They should generally be not more than forty to a reed space of one inch, and not less than thirty. The best effects also are to be obtained if good, even, hand-spun yarns are used, especially in the weft.

Setting out
Complete
Plans on
Ruled Paper

It will be remembered that good cloth requires the weft to be thicker than the warp (see p. 5), and it will be at the same time observed that in order to weave most of the patterns illustrated, in the same proportion as the drawings, the warp and weft should occupy equal spaces. This difficulty is to be obviated by using a warp made of fine threads half the size of the weft. If these fine threads are warped and entered double, the condition of the proportion of the warp to the weft can be kept, and as the two warp threads will only count as one, the proportions of the design will also be maintained.

The Use of
Double
Threads in
the Warp

When designing these small patterns for simple weaving, care must be taken to break up the spaces by intersection of the warp and weft as much as possible. Not more than five threads either way should ever be left to cross each other without interlacing, or the cloth will be found to be too weak for good wear. Even five loose threads must not occur too frequently

Frequent
Intersection
of Warp
and Weft
necessary

Frequent
Intersection
of Warp
and Weft
necessary

in the design. If broad spaces of ornament are desired in this kind of weaving, some means must be used to strengthen the cloth without interfering with the effect of the ornament. This can be done, and a similar effect obtained to that of brocading, except that the ornaments, instead of being in




FIG. 80.—Pattern with Tabby Ground

detached spots, will be repeated in a close geometric pattern all over the cloth. Fig. 80 is a type of the design suitable for weaving in this way, and will clearly exemplify the weaving together of the ornamentation and the ground cloth. This design requires only four headles, entered in the order shown above the sketch, and four treadles, two of which are used for the tabby groundwork and two for the pattern. On the two outside treadles the pattern is tied up, and on the two inside ones the tabby ground is tied. An extra shuttle and richer weft must be used for the *design* part of the weaving, and it is better for this purpose to use several fine threads together as a weft, than one

Pattern-
weaving
with Tabby
Ground

coarse one, as they will lie flatter and cover the ground better. Ordinary plain cloth is woven by using only the centre pair of treadles, but as soon as it is determined to introduce the design one of the outside treadles must be brought into use after any one of the tabby shoots, and the pattern weft introduced in the shed made by it. The next shoot of tabby ground must then be made, and after it the same pattern treadle again depressed and another pattern shoot thrown. These alternate shoots of ground and pattern must be repeated until the first row of squares is complete, in which there will be found four shoots of ground and four of pattern. When this point has been reached, the opposite pattern treadle will have to be used, in the same alternation with the ground ones, for the same number of shoots, thus making the second row of squares. After this the first pattern treadle must be depressed for one shoot only, in order to make the thin strip dividing the squares. After four more shoots in the shed, made by the second pattern treadle, the first one is returned to, and after four more shoots and a single one, the first repeat of the design will be found to be complete. It will be readily understood that the squares of this pattern may be made of any size desired, by extending the entering in the harness and the number of sheds made by the pattern treadles. At the same time this will not weaken the cloth, as the same tabby ground will run throughout, whatever size the squares may be. Whilst weaving this kind of design it will be found necessary to beat the weft together with more force, or with a double blow, in order to keep the ground as close as the plain

Pattern-
weaving
with Tabby
Ground

Pattern-
weaving
with Tabby
Ground

parts of the web, if there are to be any such. If properly beaten together the pattern woven by this method should appear quite solid, and entirely hide the tabby ground which is beneath it.

The great importance of the satin ties in the development of weaving, especially of fine silk, renders it necessary that the next chapter should be set apart for their exclusive consideration. But at the same time it must be noted here, that many useful and beautiful satin and partly satin webs may be designed for weaving on small domestic looms in which either linen, cotton, woollen or spun-silk yarns can be used.

CHAPTER XII

THE SATINS AND DOUBLE CLOTH

Construction and Utility of the Satin Tie—
Meaning of the Term *Satin*—Peculiar Quality of
the Satin Tie—Various Satins and the Number of
Headles required for weaving them—Reasons for
weaving Webs Face Downwards—Exceptions—The
Selvages of Satin and other Webs—Separate Selvages
and their Fitting up—When Separate Selvages are
necessary—Contrast of Colours in Satin Webs and
its Limits—Double Cloth, its Advantages—Pre-
paring and entering the Warp for Double Cloth—
Weaving Double Cloth.

THE construction of the broken-twill has already been explained (p. 168, fig. 73) and its importance as an example of the principles of satin-weaving commented on. Its reputed Chinese origin was also mentioned. It is remarkable that, apart from Eastern influence, there seem to be no traces of this tie in ancient weaving, although there are a few examples of the ordinary twill. The earliest known specimens of weaving in which the use of satin ties is a feature belong to the fourth or fifth centuries of the Christian era, and even of that date the fragments that remain are very few in number.

The satin tie for plain webs is not much used, except in the case of warps of fine silk, the richness

The Con-
struction and
Utility of
the Satin
Tie

The Construction and
Utility of
the Satin
Tie

of which it is peculiarly fitted to display. But it is in the weaving of the extensive and elaborate pattern webs known as damasks that its chief utility consists, and that not only for the weaving of silk, but for the weaving also of linen, cotton, and woollen ornamental fabrics.

Meaning of
the Term
"Satin"

The name satin is generally misunderstood. It is usually taken to signify some kind of silk material. This is no doubt owing to the fact that this tie is for the most part restricted to silk in the case of plain materials. The term, however, has no reference to the yarn employed in the web, but only to the manner of weaving it.

There are various kinds of satin in use, all being based on the same principle. They are distinguished according to the number of headles required in the harness used for weaving them. The broken twill, which we have seen requires a harness of four headles, is not always called a satin, but is often designated a satinette.

Valuable
Quality of
the Satin
Tie

Peculiar value is given to the satin tie because of its throwing a very large proportion of the warp to the face of the material woven, so that if the warp consists of fine rich silk and the weft of common silk, linen, cotton, or wool, the rich silk, in the case of a very rich satin of, say, sixteen headles, will almost entirely cover up the poorer weft. The latter will in its turn show almost entirely at the back of the cloth. Fig. 81 represents the front and back of such a satin-woven material, very much enlarged.* In the actual cloth

* The square of sixteen-headle satin represented would repeat from nine to twelve hundred times in a square inch.

Valuable
Quality of
the Satin
Tie




FIG. 81.—Satin Cloth (much enlarged).

Valuable
Quality of
the Satin
Tie

represented the sixteen threads between the ties would probably not occupy a space of more than the thirtieth part of an inch. At no. 2 the face of the cloth is shown, and it will be seen that fifteen threads of warp intervene between each intersection of the weft laterally, and also that the warp threads each float over fifteen shoots of weft between the ties vertically. In the actual stuff when loose and out of the loom these infrequent ties would scarcely be seen at all, and the glossy surface of the silken warp would appear to be unbroken. At no. 1 the back of the stuff is shown. Here the weft only for the most part shows, held together at regular though infrequent intervals by the intersection of the fine warp.

Various
Satins

Satins may be made on harnesses of almost any number of headles from five to twenty-four. The satin most generally used is that made on eight headles, and is called *eight-headle*, *eight-lam*, or *eight-shaft* satin. In some respects this is the best of all satins, as in it the ties are most evenly distributed, and the twill from which it, in common with all satins, is derived is less in evidence. (See no. 3, fig. 82.)

Five-headle satin is more used for linen damasks and other coarser woven ornamental fabrics than for silk. A great many of the mediæval silk damasks were, however, made with this tie, which gives the dry and more subdued effect often to be seen in them. (See no. 1.)

In fig. 82 are given ruled-paper drawings of all the satins. Many of them, however, are not in general use, as nine, seven, eleven and other odd numbers of headles would be inconvenient in a

harness, as plain tabby cloth could not be made on it. Five-headle satin (no. 1) is generally made

Various
Satins




FIG. 82.—Satin Ties.

on a harness of ten headles, for the above reason,
and tied up so that two of the headles rise at each

Various
Satins

tread. Such a harness can also, of course, be used for the ten-headle satin (no. 5). Nos. 2, 4, and 11 would only be used as ties on portions of a design woven on a different principle, as if made on a harness they could only be worked with an awkward number of headles, although the eleven-headle satin is perhaps the most well-distributed of them all, not excepting the eight-headle one. Nos. 7, 8, and 9 are only used for the very richest and finest silks, or as ties in portions of designs in fancy-silk weaving, which will be treated of later on.

Reasons for
weaving
Webs Face
Downward

Returning to the representation of sixteen-headle satin, fig. 81. It will be noticed that the back of the cloth, no. 1, corresponds more closely with the sketch of the same satin in fig. 82 than no. 2 (the front of the cloth) does. The reason of this resemblance is that the black squares of the sketch represent the lifted threads of the warp. It has already been stated that most weaving is done with the face of the cloth downwards. This is particularly the case with satin webs. Obviously the lifting of one headle out of many instead of the lifting of all but one, makes the work lighter for the weaver. The raising of one thread instead of many causes also much less friction and wear, not only in the warp itself, but in the harness and general fittings of the loom. There are several other minor advantages, so that, taking all into consideration, the inconvenience to the weaver caused by not seeing the front of the web as, the work proceeds, is more than compensated for. Moreover, the difficulty of weaving webs face downwards is not so great in most cases as would at first appear, for if the back is right and the loom in all its parts is seen to be

working properly the weaver need have little doubt that the surface of the material will be satisfactory. Although weaving is usually thus done face downwards, it is not absolutely necessary that it should be. In the case of some complicated fancy webs, where two or three thicknesses of cloth are woven together, and it would be impossible to judge from the back if the surface were weaving properly or no, it may be possible and advantageous to so arrange that the fabric may be made face upwards. This is effected by tying up in accordance with the white spaces of the ruled-paper design, instead of the black ones.

Exceptions
to weaving
Webs Face
Downward

When a piece of cloth is being inspected by an expert one of the first points to be examined is the edge of the web, generally called the *selvage*. It may be pretty confidently expected that if the edges are straight and even, and at the same time neither tighter nor looser than the body of the stuff, the cloth will prove to be well woven throughout. A good selvage is the finishing grace in a woven fabric, and none but good weavers can keep perfect the edges of their work.

The
Selvages of
Satin and
other Webs

In tabby or plain weaving, when the warp and weft are properly proportioned, there is not much difficulty in keeping a perfect edge, and it is only necessary to fortify the warp by making a few of the edge threads double ; but in the case of the looser satin, or the various kinds of fancy webs where two or three different warps and wefts are used, an arrangement of the selvage warps to work independently of the main warp becomes necessary, and often requires a good deal of ingenuity on the part of the weaver to devise. Another reference to

The
Necessity for
Selvages

The
Necessity
for Selvages

Fitting up
Separate
Selvages

Why
separately
warped
Selvages are
required

fig. 81 will be sufficient for the purpose of explaining the necessity and working of the selvages on the edges of satin webs. Although there are only two threads shown in the drawing, it is quite clear that they make a straight tabby edge and prevent the weft being drawn back, by the returning shuttle, as far as the first tie of the satin. This might be any distance from the edge up to the space of sixteen threads of warp. Without these tabby-woven threads the edges would be extremely uneven, however carefully the weaving might be done. The defective edge can be avoided if a few strong threads are so arranged that a narrow strip of tabby weaving may be made along each side of the web. There are various ways of arranging for the separate tabby shedding of the selvages, but the simplest way is to provide two extra pairs of headle shafts at the back of the harness, at the ends of which the selvage leashes are fixed, so that the extra threads passing through them, by the sides of the main warp, may be entered close to it in the rather wider dents usually provided for them in the reed. These selvage headles are each tied up to half the treadles in such a way that they will be raised alternately as one of the right or left half of the treadles is depressed. In the case of satins and other loosely tied webs it is found necessary to warp the selvages and weave them off small rolls, separately fitted up and weighted, as shown in fig. 83. This separation from the main warp is necessary, because the more frequent intersection of the warp and weft, in tabby weaving, causes the warp to be used up more quickly than is the case with the less frequently intersected threads of the satin ground. If the

Why
separately
warped
Selvages are
required




FIG. 83
Selvage Bobbin
fitted up

No. 1 shows the position of the bobbin in the loom.
No. 2 : Details of the bobbin, with warp and method
of weighting.

Why
separately
Warped
Selvages are
required

Contrast of
Colour on
the Back
and Front
of Satin
Webs

Double-
cloth
Weaving

tabby selvages, therefore, came off the same roller as the satin warp, as soon as about half a yard of stuff had been woven, the edges would get so strained that the work could not go on. They would then break out altogether and spoil the web.

It will be readily understood from the foregoing description of satin-weaving, that the back and front of a web may be made different in colour, to a very large extent, providing the warp and weft used are distinct in that respect. The colour of the warp will predominate in the front, and that of the weft at the back in similar proportion. In five-headle satin, for instance, the warp colour on the face of the cloth will be in the proportion of four parts to one part of weft, and at the back the proportions will be reversed. With richer satins the difference will be greater, but however great it may be the colour of the weft will always tinge that of the warp in the front, and at the back the weft colour will be modified by the ties of the warp in the same manner. In satin-weaving, therefore, the colours of back and front can never be quite distinct.

There is another system of weaving, however, by means of which two separate webs, of perfectly distinct colours, joined at the edges may be woven at the same time, from the same warp, in the same loom. A great deal of pattern-weaving has been done by taking advantage of this possibility.

It will now be best to describe the method of weaving this double cloth, but its utilisation for pattern-weaving must be left for consideration in a future chapter.

Double tabby cloth of separate colours can be woven on a loom with a harness of four headles,

but the warp must be specially arranged for the purpose. If it be decided to make one cloth black and the other white, the warp must be made throughout with alternate threads of those two colours. The warp of black and white threads being entered in the usual way, if the first thread be black the whole of the first headle will be found to contain all black threads, the first, fifth, ninth, &c.; the second headle will carry all white threads, the second, sixth, tenth, &c. The third headle will be all black, with threads 3, 7, 11, &c.; and the fourth headle will take the rest of the white threads, 4, 8, 12, &c. In other words, all the odd threads, which are black, will be found in headles 1 and 3, and all the even ones, which are white, in headles 2 and 4.

With such a warp separate selvages would be fitted up to work in the same way as for satin, so as to bind the double cloth together at the edges.

When all is ready, in a loom so arranged, weaving must begin by raising half the black threads by means of headle 1, and throwing the shuttle carrying the weft through the shed so formed. The next shed is to be made by raising headle 3, which raises the second, half of the black threads for the second throw of the shuttle. This completes two shoots of

Entering
of Double-
cloth Warp
in Harness




FIG. 84.

Weaving
the Double
Cloth

Weaving
the Double
Cloth

the black face of the double cloth. For the next shed, headles 1 and 3 must rise and lift all the black threads, and headle 2 must rise with them to lift half the white threads. The third shoot of weft having been made, the fourth headle will have to rise, as well as the first and third again, and the fourth shoot of weft will complete the second shoot of the white face of the double cloth. This order of shedding must be repeated, and when a few shoots have been made, it will be found, that, two distinct webs united at the edges have been woven. In order to make the colours distinct two shuttles must be used, one for the black and one for the white face of the cloth, and when this is done the double cloth will be found to be perfectly black on one side and perfectly white on the other. Fig. 84 gives the sketch on ruled paper with the plan and tie-up for double cloth.

CHAPTER XIII

SHEDDING MOTIONS

The Simplest Shedding Motion—Two Typical Shedding Motions—Differences between the Two Kinds of Shedding Motions—Choice of Shedding Motion left to Weaver—Suitable Design for Shedding Motion No. 2.

THE name *shedding motion* is given to any contrivance by means of which the opening or shed is made in the warp, in front of the reed, for the passing through of the weft. The shedding motion shown on the old English loom, fig. 42, consists of two treadles and two pulleys connected with the headles of the harness by cords. A similar motion, having precisely the same effect, in which two short pieces of bamboo take the place of the pulleys, is shown in the Indian loom, fig. 41. Needless to say, these are the simplest forms of shedding motion possible, but it now becomes necessary to describe the rather more complicated arrangements by means of which headles may be lifted for the grounds and small figures exemplified in the preceding chapters.

Only two distinct shedding motions need to be described and their differences pointed out, as all others are for the most part modifications of them,

The
Simplest
Shedding
Motion

Two Typical
Shedding
Motions

Two Typical and will present no difficulties to the student if their
 Shedding principles are perfectly understood. Figs. 85 and
 Motions 85A represent these two typical motions.




FIG. 85.—Shedding Motion.

In order to keep the diagrams of these shedding motions as distinct and simple as possible, the harness to which they are attached is only represented as

Two Typical
Shedding
Motions

headles and the shedding motion are shown; all the supporting parts of the loom, which would only complicate the drawing and render it less clear, are omitted. The position of the harness in the loom is, of course, the same as in fig. 42, with its harness of two headles.

In fig. 85 it will be seen that the headles, A, A, have long lead weights, B, B, on their lower shafts, instead of their being tied directly to the treadles as in fig. 42. If any of the four headles, therefore, be raised, as soon as it is released, the weights on its lower shaft will bring it down again to its normal position. Strong wire spiral springs are sometimes, for some purposes, preferred to lead weights, but these have the same effect as regards the mechanism of the shedding motion.* At letter C four short, strong laths are shown, having a hole somewhere near their centres, through which an iron rod is passed. The ends of the rod are fixed in a long, wooden frame, which rests on the top of the loom in the position occupied by the centre cross-piece, from which the harness is suspended, in the old English loom, fig. 42.

From one end of each of these laths, just above the centre of the headles, a double cord descends, and, being divided, in the manner shown in the drawing, is attached to both ends of the top shaft of headles. This attachment is made by the use of the adjustable slip-knot, described in Note 2 to Chapter VII., p. 106, in order that the height of the headles in the loom may be adjusted to a nicety. At the opposite ends of the levers C

* The effect of the dead weight is to close the shed rather more quickly than the spiral spring, and therefore it is generally preferred.

long cords are firmly fixed. These descend, and are tied, by the same kind of slip-knot, to the ends of four long laths, D, which, reaching right across the loom at the height of about a foot from the ground, have their other ends hinged to a strong support, which is fastened to the ground, or to the framework of the loom itself. It will now be seen that the four treadles, E, placed under the weaver's feet, as he sits in the loom, only need to be tied up to the long cross-levers to enable him by pressure of his foot to pull down at will one end of any of the levers C. This will raise the other end, from which a headle is suspended, and open the shed. By this means the headles can be raised in any order or combination necessary for the formation of the pattern.

Two Typical
Shedding
Motions

In fig. 85A the arrangements for raising the headles are the same, but the weights on the bottom shaft are dispensed with. In place of the weights, four levers, long enough to reach from the side of the loom to beyond the centre of the harness are fixed, between the long levers and the bottom laths of the headles, and tied to each of the latter (see letter F, fig. 85A). If, with the motion arranged as at fig. 85A, the first treadle be pressed down, the first headle will rise, and the first lever F will rise with it. The second, third, and fourth headles, having no weights to keep them down except the light weight of the levers themselves, will neither be held firmly down nor raised. To rectify this, levers 2, 3, and 4 must be tied firmly by cords to the first treadle. The result of this additional tie will be, that, when treadle 1 is again depressed headle 1 will rise as before, but headles 2, 3, and 4 will be drawn down at the

Two Typical Shedding Motions same time. This cording has to be carried all through; thus, the second treadle must be connected with the levers 1, 3, and 4, the third treadle with levers 1, 2, and 4, and the fourth treadle with levers 1, 2, and 3. When all these connections are made the raising of any one of the four headles will cause the remaining three to sink. If when this motion is used two headles are required to rise at one time, the treadle must be connected with two long levers in order to raise them, and the remaining two levers must be tied to the same treadle. By this means two headles will rise and two sink. In short, no matter how many headles the harness may consist of, each must be connected with all the treadles either by means of the long levers which raise the headles or by the short ones which sink them.

Difference in the Two Kinds of Shedding Motions The section of the sheds below figs. 85 and 85A will show the important difference between the two shedding motions. Fig. 85 is called a *rising shed*, because, while the bulk of the warp is stationary, the required threads rise from it. Fig. 85A is called a *rising and sinking shed*, because when certain threads are raised all the others sink down at the same time.

Each of these shedding motions has its advantage, according to the kind of weaving it is used for. When only a few threads require lifting, as in the case of satins, a rising shed is preferable, but when about half the threads of the warp are raised, a rising and sinking shed may be advantageous, although there is always more friction when the latter is used.

There are various other shedding motions in use,

but they are all based on one or other of these two principles, and the above may be taken as types of all.

Also, by connecting the treadles to only certain of the remainder of the headles instead of all, another variety of shed may be made. This connection will be described later on, as it is required in a particularly important class of pattern-weaving.

The sample patterns already given can be woven with either of the above shedding motions, and the use of one of them would not affect the design on ruled paper or the indicated tie-up of the treadles. The rising of the headles would be the same in both, but in the second motion after the tie-up for raising the headles had been made, the headles corresponding to the vacant spaces in the tie-up plan would have to be connected by means of the short levers to the several treadles. The kind of shedding motion most suitable for any particular design is a point for the weaver to settle to his own satisfaction.

Difference in
the Two
Kinds of
Shedding
Motions

Choice of
Shedding
Motion left
to Weaver




FIG. 86.

Fig. 86 is an example of a small design suitable for weaving with the shedding motion no. 2—that is, with a rising and sinking shed—as the ground and figure are exactly equal in weight.

Between A and B, in the design, one repeat or the pattern is shown drawn out on the ruled paper. At first sight it would appear to require ten headles and ten treadles to make one repeat of the design. But on analysing it, it will be found possible to weave it on six headles, governed by six treadles provided the entering of the warp in the harness be done as indicated in the sketch above letter D. The real design is only a quarter of one repeat, but it is turned over or “pointed” both laterally and vertically. Instead, therefore, of containing ten different lines of squares, the design has only six, four lines being repeated twice in it. The lateral turnover is effected by the entering of the harness, the vertical one by reversing the order of treadling. The tie-up for this design with no. 2 shedding motion must first be made, as shown in the sketch, to the long levers, or *long marches*, as they are more correctly called. When this is done it will be found that there are three connections to each treadle, and three headles will still remain unconnected with each of them. These unconnected headles must, by means of the short levers, be connected with the treadles, as indicated by the unmarked crossings. The effect of this second tie-up has already been fully explained in the description of the second shedding motion, fig. 85A, p. 193.

CHAPTER XIV

DOUBLE-HARNESS PATTERN- WEAVING

Diaper-weaving — Example — Patterns in Double Cloth—Indian Example—Use of the Figure Harness —Use of the Tabby Harness—Importance of the Two-harness Method of Weaving—The Weaving of Small Damask Patterns with Two Harnesses —Details of Weaving Figured Damask—Analysis of the Effect of the Two Harnesses—Shed-making for Damask Patterns—All Modern Weaving of Pattern based on Two-harness Principles—Weaving from Two Separate Warps—Velvet-weaving and its Methods—Arrangement of the Loom for Velvet-weaving—Actual Process of Velvet-weaving — Principal Tool for Velvet-weaving—Terry Velvet—Superiority of Hand-loom Velvet —Small Designs in Velvet—Tobine Weaving.

THE name diaper is now usually understood to signify any small design which is repeated geometrically over the surface which it decorates. The term diaper-weaving, however, does not really refer so much to the kind of pattern woven as to the method of weaving it. This ingenious method, although invented in Asia, was as early as the eleventh century practised in England, especially for weaving the silken groundwork of the embroideries for which the ladies

Diaper-
weaving

Diaper-
weaving

of England were famous at that time. A great deal of quite large pattern weaving was formerly done in this way, but on account of its being, except for simple designs, difficult to set up as well as to manage, it was superseded by less complicated contrivances.

When
Useful

For small patterns, however, especially in linen and cotton materials, it may still be used with advantage. It must therefore now be described.

Diaper-
weaving :
Method


In diaper-weaving, the harness is divided into sets of equal numbers of headles. There may be any workable number of sets, and these may contain any equal number of headles. The treadles also are divided into sets, but each set of treadles acts on more than one set of headles, so that, whichever set of treadles is used the whole of the warp is acted upon, and no gaps remain in the weaving.

Harness and
Entering

Fig. 87 is a simple design which will serve well to explain the method. Here the harness is divided into two sets having four headles in each (nos. 1 and 2). There are also two sets of treadles, each set consisting of four. The entering shown to the right of the plan corresponds with the proportions of the square and oblong forms of which the design is composed. For instance, if the design be compared with the plan of entering, it will be found that the warp is entered in the spaces where dark predominates. The second division of the harness and the bottom line of the design agree, while the first division of the harness and the fifth line of the design agree also. Before proceeding it may be remarked that the size and proportion of the squares and oblongs laterally is determined by the entering. In the present case four courses are entered in no. 2 harness and two in no. 1, which makes the oblong

twice as wide as the square.

The plan of tie-up for the headles, shows the second harness connected with the four treadles of the first set. The connection is made in the order necessary to form the twill tie on the portion of warp entered in the second harness. To the same treadles the first harness is tied up to make the reverse twill. The second set of treadles is tied up with the reverse twill in front and the figure tie at the back. The effect of this arrangement is that if weaving be done, using



Plan of
Tie-up for
Diaper-
weaving

①
②




FIG. 87.—Example of Diaper-weaving.

Plan of
Tie-up for
Diaper-
weaving

Extended
Diaper-
weaving

Pattern-
weaving
with Two
Harnesses

the first set of treadles only, a broad and narrow stripe of light and dark reversed twills will be made ; on the contrary, if the second set of treadles only are used the broad stripe will be dark and the narrow one light (see top and bottom of fig. 87A). By the alternate use, then, of the set of treadles 1 and 2 the changes from light to dark spaces, required for the pattern, can readily be made.




FIG. 87A
Variations of
Fig. 87

By adding to the number of sets of headles and extending the entering through them, with or without adding to the number of the treadles, a great variety of intricate designs can be arranged for ; and, indeed, this used to be done, but since the same effects have been found to be attainable by less intricate means, the more elaborate forms of diaper-weaving have been discontinued, and the ingenious contrivances for working large numbers of sets of headles, are only interesting from an antiquarian point of view.

A great advance was made in the weaving of pattern when the idea occurred of passing the warp threads through two or more sets of headles, each set having its own separate function to perform, such as making the ground, forming the pattern, or binding a portion of the design separately, as is sometimes necessary.

A good example of the action of two separate harnesses working together, is afforded by the Indian

double-cloth pattern, fig. 88. The making of plain double cloth and the advantages such cloth possesses have been fully described at the end of Chapter XII., p. 188. That description should be referred to at this point. It may be noted in addition, that, while cloth is being woven from one half of the warp for one or two shoots, as the case may be, the other half-warp is either lifted out of the way or left below, but that THEY NEVER REVERSE THEIR RELATIVE POSITIONS. Now in double-cloth pattern-weaving while the tabby cloth of one colour is being made the warp of the other colour is lifted in some places and remains below in others, according to the design, but whether above or below it does not interfere with the tabby



Pattern-
weaving
with Two
Harnesses

FIG. 88.—Indian Double Cloth.

Pattern-
weaving
with Two
Harnesses

weaving of the opposite colour. When the web is finished the separate cloths will be found to be quite distinct from one another, except at the edges, or




FIG. 89.—Plan of Indian Design.

outline or the shapes of the design, where the threads will be found to cross or intersect one another.

Fig. 89 is a portion of the working plan of the Indian design fig. 88. The warp, which has alternate threads of black and white, is shown at A, at the top of the diagram.

In front of the loom, as near to the reed as it can conveniently hang, the tabby or ground harness must be placed. This consists of four headles having long eyes on the leashes as described at p. 156, fig. 66. The warp must be entered in the harness in regular order from back to front, beginning with a black thread (fig. 89*d*). When the entering is finished all the black threads should be found on headles 1 and 3, and all the white ones on headles 2 and 4. Although thus mentioned first, as appeared necessary, the ground harness would not be fitted up or entered until the figure harness, which will presently be described, was in its appointed place with the warp ready entered in it.

In order to find the requirements for the figure harness the design fig. 88 must be dissected. The result of this dissection is shown at C, fig. 89. The design consists of only four different groupings of a few squares of eight black and eight white threads, arranged in lines and repeated in different sequence. These lines are numbered 1, 2, 3, and 4 in the design, fig. 88. It will also be seen that laterally there are five squares and two half-squares. The first figures indicate that four treadles will be required for the black portion of the design, and four more for the white portion. The second figures show that twelve headles will be wanted, six for lifting the white threads and six for the black. These twelve headles are shown at letter B in the diagram, and their construction and entering is as follows :

Unlike any of the enterings shown up to the present, this harness is entered in groups instead of single threads, the groups consisting of eight threads,

Mounting
the Loom
for Double
cloth
Indian
Design

The
Ground
Harness

Dissection
of the
Design

Construc-
tion of the
Figure
Harness

Construc-
tion of the
Figure
Harness

except in the cases of the first black and first white headle, which are entered in groups of four. It will be at once seen that if any one of the headles be lifted, all the black, or, all the white threads in two squares of the design, will be raised; also that by raising two, three, four, or five, or even six headles together various groups of squares can be formed; in the last case—that is, with six headles—solid black or solid white will be lifted.

Spaced
Harnesses

If this harness were made specially for this pattern the leashes would only be hung on the shafts of the headles in the places required for the groups of threads. This is called spacing the harness. By thus spacing the leashes, not only is time and thread saved in making the harness, but the inconvenience of having unnecessary empty leashes hanging about is avoided. This spacing of harnesses will often be referred to as we proceed in the subject of pattern-weaving.

The Work
of the
Tabby
Harness in
Double-
cloth
Pattern-
weaving

It will be remembered that in making plain double cloth with a tabby harness of four headles one half of the warp was raised by two of the headles, while the plain weaving was being done by the other two. In the case of double-cloth pattern-weaving this lifting out of the way is effected by means of the figure harness, and the tabby harness is only used for making the black and white plain cloth in regular alternation.

The Work
of the
Figure
Harness

The province of the figure harness is to form the design *in large* without regard to the binding or weaving it together. If only the figure harness were used, the design would be formed, but the threads of both warp and weft would only interlace

where the black takes the place of the white or the white that of the black.

By using two harnesses, one for the formation of the design and the other for the details of the weaving, the scope of pattern-weaving is immensely extended, and IT WAS BY THE DEVELOPMENT OF THIS TWO-HARNESS METHOD THAT THE MOST SPLENDID RESULTS OF THE WEAVER'S ART WERE ACHIEVED.

The plan, tie-up and treadling of the Indian design are given in fig. 90. An examination of these will show that only some portions of the black warp are raised above the surface at the one time, and the same thing occurs in regard to the white warp. Those portions remaining below, however, do not get woven into the tabby, because they are of the opposite colour to that which is at the moment being made. For example, when the black threads are some, right up, and some, down, the white cloth, is being woven by two headles of the tabby harness and in like manner when some white threads are held up by the figure harness, and some left down, the black plain cloth is being woven and cannot interfere with them.

It will be sufficient, in order to make the working quite clear, to analyse one line of the design as a key to the whole. In the first line, beginning at the left hand, three squares together are shown black, one white, one black, half a white, one black, one white, three black together, and half a white. In order to form this series of squares headles 1, 2, 3, and 5, entered with black thread, must be lifted. While these are held up the second headle of the front harness is raised, and one shoot

The Work
of the
Figure
Harness

Importance
of the Two-
harness
Method of
Weaving

The Plan
and Tie-up
of Indian
Design

Analysis of
the Working
of the
Design

Analysis of
the Working
of the
Design




FIG. 90.—Plan of Tie-up.

of white weft thrown in. This shoot being pressed close, the white figure headles 4 and 6 must be raised, and together with them the first tabby headle. This being black must be shot with black weft. The same black headles must again rise, but this time the fourth headle of the front harness must be raised with them, for the second shoot of white tabby. The same white figure headles again rise, and the third tabby headle makes an opening for the black weft. After this order of proceeding has been repeated six or eight times, according to the size of the wefting, one line of squares will be woven. The upper and under surfaces of the cloth will be found to be exactly the same in design, but the colours will be reversed.

Analysis of
the Working
of the
Design

The first line of the pattern being complete, the second line will proceed as indicated in the plan, which need not be further described.

As will be gathered from the above, two shuttles must be used if the effect of clear black and white is desired. If only one shuttle were used, the form of the design would be quite correct, but the colour of the weft would tinge the black and the white and modify them.

Two
Shuttles
necessary
for Solid
Effect of
Black and
White

The treadles are shown in the plan and tie-up, arranged in three groups for the sake of clearness, but the weaver would no doubt rearrange them to suit his own convenience. He would probably mix the white and black treadles up so as to bring the first white next to the first black, in order to work them with his toe and heel. This rearrangement, however, will not affect the order of rising in the least if the tie-up be made correctly in accordance with it.

Weaving of
Small
Damask
Patterns

Another method of small-pattern weaving with two harnesses, by which what are known as damask effects are produced, is perhaps more generally useful than that for the weaving of double-cloth patterns. The material woven is also lighter and more perfect in texture. It owes its effect to the fact, already pointed out, that on one surface of a satin or twill web, the warp threads are for the most part exposed, and on the other surface the weft threads predominate (see *Satin*, p. 184). The result of this peculiarity is, that, if the weaving be arranged in such a manner as to bring both warp satin and weft satin, as the two surfaces may be called, together, side by side, in certain shapes, on the front of the material, the design so worked out will be quite distinct. This will be so, even if the warp and weft are of precisely the same size, colour, and material. This most subtle and charming of all effects of woven design results from the threads of warp and weft running, as they needs must, in contrary directions; so that the light strikes and reflects differently on the different parts of the pattern, according as the vertical warp or lateral weft threads, most preponderate.

Details of
Weaving
Pattern
Damask

Fig. 91 is an example of a simple design which may be woven in the damask manner—that is, by means of two harnesses, one for raising the figure, or design, and the other for making the ground. The ground harness must be fitted up with leashes having long eyes, the same as in double-cloth pattern-weaving. The entering of the figure harness is shown above the design. The harness must have eight headles and four threads must be entered in each leash. This is indicated, in the sketch of the entering, by the filling in of four small squares to each

entry (A, fig. 91). The entering of both harnesses would probably be done at once, the hook being passed through the eye of the leash of the ground

Details of
Weaving
Pattern
Damask




FIG. 91.—Simple Damask Pattern.

harness first, and then through the eye of the figure harness. If entered singly, the cross must be preserved by drawing the threads over and under a rod, alternately. Only six treadles are required for

Details of
weaving
Pattern
Damask

working the figure harness to form the whole design, although it consists of sixteen lines in the one repeat. This is possible because one line is used six times over, one four times, and three lines twice in the one repeat. The sequence in which the treadles are to be depressed for weaving the pattern is indicated by the black oblongs, placed on the treadle lines at B, and level with the spaces with which they agree. If it were woven with this harness alone, the white warp and black weft would only intersect at the places where the black shapes join the white ones, as shown in the upper half of the drawing. The white spaces would simply consist of long loops of warp threads, and the black spaces of loops of weft. In the lower half of the drawing a broken twill tie is represented binding the loose loops of warp and weft together. In the case of damasks the threads of the weft satin (see black spaces in drawing) are tied down by the warp threads crossing them at regular intervals (see white spots on black figure), and the threads of the warp satin (white spaces in design) are bound by the occasional crossing of the black weft (see black binders on white ground). This effect is the same both on the back and the front of the material, except that the white spaces of one side will be the black spaces of the reverse. It must now be carefully explained how this ingenious result is obtained. After passing through the figure harness, in groups of four, the warp threads have to be entered singly in the long-eyed ground harness. As the tie, in this case is a broken, four-headle twill (p. 168), this harness must consist of four headles. The ordinary entering of the warp in the ground harness, is shown below the design at C. This

harness will require four treadles, and these would be placed in a group between the six treadles of the figure harness. They are so shown in the plan, D, D. The twill tie-up and order of treading are also there given. In this case the usual order of working the treadles for the twill ground may be departed from, because the weaver will only have one foot to spare for the ground, as the other foot will be occupied in treading and holding down the figure treadles. We have already noted the effect of weaving with the figure harness only. If in like manner we now use the ground harness by itself, the web will be a plain satin. The front, or under surface, will be like the white spaces in the design, warp satin with black weft ties. The back or upper surface will be just the reverse, being black weft satin with white warp ties.

Details of
weaving
Pattern
Damask

Having now a clear idea of the effect of the two harnesses when used separately, and all being ready, let us suppose that the weaver places his left foot on the first treadle of the ground harness. This will raise the first of every four threads of the whole warp. If now, still holding the ground harness treadle down, the first figure harness treadle be depressed with the right foot, groups of threads will be seen to rise, similar to the black spaces E, E, E of the first line of the design, but more correctly shown at the line F, which represents the back or upper side of the web, whilst G gives the reverse or under side. The line G should correspond with the drawing, but it will be seen that it does not quite do so. The white ties are missing from the black spaces, although the black ties are to be seen on the white ground. At F, on the

The Effect
of the Two
Harnesses
when used
together


The Effect
of the Two
Harnesses
when used
together

Rising and
Sinking
Shed with
Stationary
Bottom
necessary
for Ground
Harness

Contrary
Action of
the Two
Harnesses
further
explained

contrary, the white ties are in their places on the black portions, but there are no ties on the white spaces. In order to rectify this omission and complete the damask fit-up of the loom, the ground harness must be furnished with the shedding motion similar to 85A, so as to cause the missing binder threads to sink, and be held down at the same time as the others rise. The counter-marches, or short levers, to which the lower shafts of the treadles are tied must be exactly the same as at fig. 85A. The connection with the treadles, however, must in this case be somewhat different, as what we now require is to sink and hold down, only one thread out of the three stationary ones left, when one is raised as we have seen it. The shed now wanted is represented at H, fig. 91, where the dotted lines show the rising and sinking threads and the thick line the stationary bottom. We must therefore tie up treadle 1, to the short lever connected with the lower shaft of the first headle. The second treadle must be connected with the fourth headle, the third treadle with the second headle, and the fourth treadle with the third headle. This second tie-up for the sinking headles may be shown on the tie-up plan by circles, to distinguish it from the first or rising tie-up, indicated by crosses. The new arrangement being complete, if another trial be made it will be found that the sinking threads will make the required ties both for the warp and weft satins.

In order to make this contrary action of the two harnesses quite clear fig. 92 is perhaps necessary. It is a most important point, and must be perfectly understood, for, simple as it may appear to be, on it the whole system of damask-weaving depends.



Contrary
Action of
the Two
Harnesses
further
explained





FIG. 92.—Various Two-harness Sheds.

Further
Description
of Shed-
making for
Damask
Patterns

In no. 1 of this figure the warp, represented by the thick horizontal line AA, is seen to pass through a figure harness (B) of five headles having short-eyed leashes. The entering in this harness may be of any reasonable number of threads; for this instance let it be four; and if it be deemed desirable to keep the threads separate, although this is not essential, the figure harness leash eyes may consist of mails having four holes, as shown in the enlargement at D. Beneath letter C the ground harness is shown, also consisting of five headles, but these have long-eyed leashes. Between this harness and letter A on the left, a shed, E, is shown opened by the rising of the fifth headle of the figure harness. The rising of this headle has lifted four threads together; these are represented by the line drawn from the eye of the raised headle to the letters A, A. Although each of these five threads may pass through the eye of one of the five ground harness headles C, the latter will not be affected by them because of their long eyes. This allows for the formation of the design without ties, as described at p. 212. At no. 2 the same line of warp, AA, and the same harnesses, B and C, are depicted. In this case, however, the shed is much more complicated. The fifth headle of the figure harness is still up, but its line of our threads is divided. The thread passing from it through the fifth headle of the ground harness is not allowed to rise, as it is held down by the sinking of the headle. The effect on the front of the web of this contrary action is similar to that shown at G, fig. 91. At F, in the same figure is the back of the web as it would appear to the weaver, providing the warp were white and the

weft black. Although one of the lifted threads passes through the first headle of the ground harness, it is not affected by its rising, as it is already up, so that it does not have any influence on the portion of the design raised by the figure harness headle. No. 3 will explain the action of the first headle (shown raised) of the ground harness on the parts of the warp not raised for the figure. Here the holding down of headle 5 will have no effect, as all the threads of the figure harness are down as well, but the first headle being up, will tie the figure at the back and at the front as at E, E, fig. 91. The dotted lines between the two harnesses are not really essential in no. 3, but are merely put in to make easier the comparison between nos. 2 and 3.

Further
Description
of Shed-
making for
Damask
Patterns

The great scope given to pattern-weaving by means of the above ingenious invention will now be realised. It will also be understood, from the foregoing examples, that all the most astonishing developments, to be seen in the more or less modern ornamental textile fabrics, are based on this principle whether they be woven by hand or by power, on the draw-loom of the seventeenth and eighteenth centuries, or by means of the Jacquard machine and appliances of the nineteenth century.

All Modern
Pattern-
weaving
based on
Two-
harness
Principles

It has already been shown that the tabby selvage of a satin web will use up a greater length of warp than the body of the material, and that this is due to the fact that in tabby weaving there are more intersections of the warp and weft than there are in satin-weaving. The same thing occurs sometimes in a pattern web. A large space or stripe of satin, running longitudinally in the web, would, on account of this difficulty, require special consideration.

Weaving
from Two
Separate
Warps

Weaving
from Two
Separate
Warps

For example, let us examine fig. 93. Here we have a stripe of satin in a tabby ground. This pattern would be woven on eight headles, entered




FIG. 93.—Stripe of Satin and Tabby Ground.

and tied up to eight treadles. If only one warp were used for this web, it would soon be found, that the tabby woven portion of the warp would begin to get tighter than the satin stripe, and ere long the difference would be so great that the weaving could not proceed. This inconvenience can be obviated by the use of a separate roller for the warp of the satin

stripe. This second roller would be fixed either above or below the one for the tabby ground. It would also be weighted separately from it. By this means the take-up of the two warps would be rendered quite independent one of the other. In making the two warps, the whole number of threads in the collection of satin stripes would be counted and warped together, and the same would be done for the tabby ground. In turning on to the rollers, the satin stripes would have to be set out and wound on in their proper places on the one ; and on the other, corresponding spaces left vacant for them. This being done, the two warps could be entered in the harness and reed as one. Very often in fancy weaving, especially when there is brocading, a separate binder is required, and it is generally necessary to have the warp for it wound on to a separate roller. This will be explained later on in the book, when the subject of *brocatelle* and other *tissue* webs, as they are called, is dealt with.

Weaving
from Two
Separate
Warps

Plain velvet-weaving requires the use of two warps on separate rollers, while figured velvet needs for its production the use of many warps for the pile, sometimes to the extent of needing a separate warp roller or bobbin for each group of threads in the repeat of a design, and there are sometimes as many as four, or even eight hundred, of these tiny warps arranged in a figured-velvet loom.

For plain velvet-weaving, the two warps required are, one for the groundwork, which may be an ordinary tabby, twill, or satin, and one for the pile. The difference in the take-up of these two warps is astonishing, the pile warp having to be made at least six times the length of that for the ground. In order to

Velvet-
weaving

Velvet-weaving

make one yard of velvet, the ground will take up about one and one-sixteenth of a yard of warp, but for the pile, not less than seven yards will be required. The reason of this enormous take-up of the pile warp, in velvet, is owing to the method of weaving peculiar to this sumptuous material. Velvet-weaving also requires the use of two harnesses, and the two warps are each entered in the harnesses




FIG. 94.—Section of Velvet Loom.

independently. Fig. 94 will assist in the explanation of the arrangement.

The Velvet Breast Roller

In fig. 94 A is the breast roller, a section of which, so enlarged as to show its details of construction, is given on the next page (fig. 94A). This construction of the roller is necessary because the cut pile surface of the velvet cannot be wound and pressed on the roller without injury, as other materials may be. The roller is hollow, and generally much larger in circumference than ordinary breast rollers. It has a wide, hinged lid, running its entire length, so shaped on the outside as not to interfere with its cylindrical

form when the lid is closed (fig. 94A, D). The edge of the lid is cut away and carefully rounded in the centre, so as to leave, when it is shut, a narrow opening wide enough for the velvet to pass in and out again, without crushing the pile together. Inside the roller, which must be perfectly smooth, a second roller, B, is fitted in such a manner,

The Velvet
Breast Roller




FIG. 94A.—Breast Roller of Velvet Loom.

that the velvet, after entering at the narrow opening C, fig. 94A, may pass round it and out again in the same opening. The inner roller has a wide and deep groove in it, and is covered with some material to which the velvet clings, so that very little pressure by a lath in the groove, is sufficient to prevent its slipping. This, together with the slightly rounded edge of the narrow opening, holds the velvet tight enough to allow for the strain of weaving.*

• When the inner roll is covered with the velvet it is prevented from turning by pins or buttons at the ends.

The Velvet Breast Roller As soon as enough velvet has been made to allow of passing it round the inner roller, the lid is opened, and after the end of the velvet is in the right position it is closed, fastened down, and the weaving proceeds. When the narrow opening in the roller, C, nearly reaches the under surface of the velvet, the work is loosed, the roller moved round, the lid




FIG. 94B.—Velvet Roller with Lid Open.

opened, and the velvet, being separated from the small roller, is drawn round it and carried under the loom, to be hung on a rack, or gently laid in loose folds on a low shelf placed conveniently to receive it (see fig. 94). The greatest care has to be taken to keep the material straight and true while it is being thus moved along. As the roller is about ten or twelve inches in circumference, it will be seen that about one yard can be made between every shift. One yard of fine velvet is about a day's work for a good weaver, so that this operation of moving the

web does not hinder the weaving to any great extent.

Referring again to fig. 94, D is the roller for the ground warp. This warp is indicated by the strong line passing from D to A. E are the headles of the ground harness; four are shown here, but the harness may consist of any number of headles required to make the ground tabby, twill, or satin, as the case may be. F is the roller for pile or *pole* warp, as it is often called. This is usually placed above the ground roller, and is very lightly weighted. Sometimes the roller itself is fixed very high in the loom, but more generally a second small roller, G, is fitted high up, at about the centre of the loom, and over this the warp passes as in the diagram. This arrangement is made in order to keep the two warps as separate as possible, and is placed by the weaver himself so as to suit his own peculiar method of work. The line drawn from the roller F over G through the headle I and the reed H to join the ground warp, near the roller A, is the pile warp. Only one headle, I, is shown, and it may be that only one is necessary, as for plain velvet, with one pile warp, the pile threads all rise or sink together. If, however, the pile is too rich to be all entered in one headle, two or more may be required. The pile harness is hung as near to the reed as the working of the batten will allow.

As regards the warps themselves, the ground warp is by far the richer, the number of threads in it being usually three or four times as great as that of the pile. All the other fittings of the loom for weaving velvet are the same as those for the ordinary hand-woven materials.

The Velvet
Breast Roller

The Warps
for Velvet-
weaving

The Ground
Warp

The Pile
Warp

Proportion
of the
Warps

**Velvet-
Weaving :
the Actual
Process**

The special fittings of the loom for velvet-weaving being now all described, the actual process claims our consideration. Everything being, so far, in order, the weaver would begin by making a few inches of the ground, raising and depressing the pile harness, in regular order, as may be indicated in the plan. The pile thus woven in, has little visible effect on the ground, especially if the latter be a rich satin. It will only give a slight, lateral, ribbed appearance to the material, and thicken the ground to a certain extent. When all is working properly the pile is raised by itself, and its raising forms a shed in front of the reed. Into this the weaver, instead of weft, inserts a finely made, smooth, flat brass wire, called a *velvet rod*. This rod has a fine groove cut in one edge, which, when the rod is placed in the shed, should be on top. It is held by the weaver until the next shoot of ground is made with the pile down ; this will fix it in position. Two or three ground shoots are then made, the pile rising and falling between them as may be arranged by the designer ; this binds the pile to the ground more or less securely. After these few shoots of ground, the pile is again raised by itself and another rod inserted, being followed up in the same manner. When five or six rods are thus woven in, the most delicate operation of velvet-weaving begins, viz., the cutting of the pile. This is effected by the weaver, with a tool called a *trevette*, in which a fine, sharp, peculiar-shaped blade is most accurately fitted. The necessary perfection and accuracy of this tool, according to some authorities, gave rise to the proverb "As right as a trevette," and the suggestion seems quite reasonable. A drawing of this implement is given at fig. 95.

It is taken from a trevette of the simplest construction, and is therefore of the kind which in skilful hands is capable of the nicest adjustment. The trevette is made in two parts, the upper part, which carries the knife, shown open at no. 1, being hinged to one end of the lower part, and grooved at its bottom edge so as to fit quite firmly on to one side of it

Description
of the
Trevette




FIG. 95.—Trevette.

when the instrument is closed for use, as at letter B and at letter D, where the end view is given. The knife, C, is shown at A fixed in the strong staple, by small hardwood or metal wedges, and it is in the adjusting of the knife with these, and keeping it sharp, that a great deal of the art of velvet-weaving consists. It is for the purpose of adjusting and sharpening the knife that the two parts of the trevette are hinged together. When closed, ready for work, the knife is so placed that its sharp end is very near to the

Description of the Trevette inner edge of the straight steel side or the lower part of the tool. This may be seen in the end view, D. The brass front of the lower part, letter B, is for the purpose of steadying the instrument when in use.

Velvet-weaving (continued) We must now return to the loom, where we left the first rod ready to be cut out of the pile. The weaver, taking in his right hand the trevette, rests it on the left-hand side of the web in such a position, that, the sharp edge of the knife fits into the groove of the *first* rod woven into it. Making sure that it is rightly placed, by a firm, steady, rapid movement, he draws the trevette right across the web to the other side, and, if the knife be sharp and has been kept in place, the rod will spring out and the line of pile will stand up, like a row of delicate little, silk brushes in its place. Having cut out the first rod successfully, the pile shed is again opened and the cut-out rod inserted, ground is woven as before and the second rod cut out, and so on in regular succession. As may be imagined, great care has to be exercised in cutting out the rods, as an unfortunate slip may result in cutting out more or less of the ground warp, which is most disastrous. If properly cut, the velvet made by hand should require but very little finishing when out of the loom, beyond what the weaver himself can do.

Terry Velvet Terry velvet is simply velvet woven in the above manner, but uncut in the pile. Smooth, grooveless wires are used in this case, and when half a dozen have been woven in, instead of being cut out the rod is drawn out from the same end at which it was inserted.

Velvets, woven and cut by hand in this ancient
226

manner and made of good silk throughout are unequalled, both for texture and durability, by any imitations that can be produced by modern means. A comparison of the many specimens of ancient velvets, with the most perfect and ingenious productions of the power-loom, will verify this statement. Power-loom imitations smoothly shaved and highly finished present a hard, inartistic, shining surface when thus compared with the rich, glowing and slightly varied texture of hand-loom woven velvets, either of mediæval or modern times.

The
Superiority
of Hand-
loom Velvet

With regard to small-pattern weaving in velvet, a great deal might be done by quite simple means, such as varying the colour of the pile warp, or spacing it out so as only to come up in spots or lines, vertical or lateral. The use of terry and cut pile in the same pattern is also quite easy to produce. Many of the ordinary small designs, too, could be made in velvet quite readily if the pile were entered in a harness which would lift it in the separate portions required, and the warp were distributed over the requisite number of warp rolls. The necessary arrangements for small velvet patterns will, however, be better understood when the description of figured-velvet weaving, which will be found in Part III. of this book, has been read.

Small
Designs in
Velvet

The edges of stripes in striped materials such as that shown at fig. 93, p. 218, and taborettes, as well as the grounds of rich brocades, are often decorated with little squares, oblongs, or lines, composed of warp threads floating over two or more shoots of ground weft and dipping below it at regular intervals. These form bright edges and embellishments, and often have a very pleasing effect. This simple kind of

“Tobine”
Embellish-
ments

“Tobine”
Embellish-
ments

ornamentation is called *tobine*, and requires a separate warp spaced out and entered in one headle, in the same manner as a velvet pile warp. Fig. 96 is a ruled-paper drawing of a taborette stripe, and will




FIG. 96.—Tobine Stripes.

sufficiently explain the method of introducing the tobine edges. Plate 1x is a good example of the use of tobine stripes, which, being graduated in colours, form the sole but very effective ornamentation of a seventeenth-century silk.

CHAPTER XV

AUTOMATIC MACHINES FOR SHEDDING MOTIONS

Automatic Shedding Motions and their Use—
Disadvantages of the Jacquard Machine for Home
Weaving—Comparison of it with Simpler Machines
—The Jack-in-the-box—Its Inventor—Character
of Old Hand-loom Weavers—Tie-up and Working
of the Jack-in-the-box—The Drawboy Machine,
its Details and Use—Examples of Pattern-weaving
with Drawboy.

IT now becomes necessary to describe two ingenious automatic contrivances, by means of which the inconvenience of managing a large number of treadles, required for lifting the headles in the formation of some patterns, may be obviated to a great extent. At the present time the ingenious invention, the Jacquard, and the various machines made on the same principle, have taken the place of all other automatic machines for pattern-weaving. But the Jacquard machine, although admirable in its capacity and adaptability, has certain disadvantages for hand-loom, especially if these be in a private house, a small workshop or a studio. Not the least of these disadvantages is that the Jacquard machine requires the constant attention of a skilled

Automatic
Contriv-
ances for
Shedding
Motions

The
Jacquard
Machine

Advantages
of Simpler
Machines

machinist to keep it in working order. It also requires to be continually in use. For the weaving of simple designs, therefore, on an isolated hand-loom, the less delicate and complicated machines, invented by weavers themselves for the purpose of simplifying the shedding of the loom, are preferable. They have the advantage, too, that the weaver himself can repair and keep them in order, as, like the loom, they are chiefly made of wood and string. They are also less heavy and noisy in working than the Jacquard machine, and, being placed by the side of the loom instead of at the top, no extraordinary height is required in the place where they are set up. For rapid commercial work in a factory, where a great number of looms are set up and in constant use, the Jacquard machines are, of course, superior and offer many advantages, but it can be readily understood that different qualities are desirable in a machine for home weaving.

Jacquard
Machine
most suitable
for Factories

The two machines we have to examine are the *Jack-in-the-box*, or Jennings shedding motion, and the *Drawboy* machine, which latter was intended for drawing the cords of the draw-loom, but was found to be equally useful for drawing up any number or combination of headles required for small-pattern weaving.

Jack-in-the-
box, when
invented,
and by
whom

The Jack-in-the-box was chiefly used for making rich satins and very small figures. For this purpose many hand-loom weavers prefer it to a small Jacquard machine, it being so perfectly reliable in its action.

Ingenious
old Weavers

It was invented about 1840 by a working silk-weaver of Bethnal Green named Theodore Jennings; and it is interesting to notice, by the way, how many of the valuable inventions of weaving appliances in

the old days were made by the actual workers, who not only understood the working of the loom when all was prepared for weaving, but could build harnesses, contrive alterations of design and methods of working, tie up new patterns, and do all the necessary preparation of the loom, themselves. This required for its accomplishment much judgment and skill, and we find that many of the old hand-loom weavers possessed these qualities to a very great extent. Some of them, indeed, were quite famous in their day, not only for weaving, but in various branches of science. Mathematical, entomological, botanical, and other clubs were common amongst them, and several were corresponding members of the learned scientific societies of the eighteenth and early nineteenth centuries.

Ingenious
Old Weavers

In Chapter XIII., where the typical shedding motions are described, it was pointed out, that as many treadles were required as there were headles or groups of headles to be raised in succession to form any particular pattern. In an eight-headle satin, for instance, the eight headles required eight treadles to raise them in the following order : 1, 4, 7, 2, 5, 8, 3, 6. The Jack-in-the-box provides the means for raising any number of headles in any sequence by the use alternately of two treadles only.

Jack-in-
the-box :
its Utility

Fig. 97 is a general view of the shedding motion of the loom, with this simple machine in its relative position to the treadles and headles. Fig. 98 gives the details and construction of the various parts. Fig. 98, no. 1, AA, is a strong oblong wooden box, without back or front, set on end and perforated at the top end with two rows of holes,

Description
of the Jack-
in-the-box




FIG. 97.—The Jack-in-the-box.




FIG. 98.—Details of the Jack-in-the-box.

Description of the Jack-in-the-box four holes in each row. Inside it has a shelf, B, placed across it, at about one-third of the distance from the top to the bottom ends. This shelf has transverse slots cut in it, to correspond with the eight holes with which the top is pierced. These transverse slots are cut in such a position, that one of the top holes is over the centre of each slot. The box has also two long slots cut in each of its sides, and above these pulleys are fixed. One of these is shown in the drawing and marked C. Just below the shelf, in front, a bar, D, is fixed from side to side, and this bar is made to stand an inch or two in front of the box, by means of two short arms which project from its sides.

No. 2 shows an elevation of one side of the box. Both sides being exactly alike, the description of one will suffice. Here we have again the two long slots and the pulley C. In addition to these, the elevation shows the sections of two, long bars, numbered 1 and 2, which are fitted to the slots and are long enough to reach from side to side of the box, and, after passing through the slots, to project not less than three inches beyond them. To the top of one bar a strong cord is tied, carried over the pulley C, and then fixed to the other bar. The cord is of such a length, that when one bar is near the top of its slot, the other bar will be at the bottom of the other slot. Two other cords are fastened to the bottom edges of the two bars, and connect them with the two treadles of the loom in a manner which will presently be explained. It will now be perceived that when one bar is pulled down, the other must rise and reverse the position shown in the drawing. Also, that, by working the two treadles, with which

they are connected, this action of the bars can be repeated in alternation.

Description
of the Jack-
in-the-box

Nos. 3, 4, and 5 represent a section of the box no. 1, taken at the place indicated by the dotted line EE. The parts which will be recognised severally are : (1) the bottom board of the box ; (2) the top board pierced with holes, one of which appears in the section ; (3) the shelf, with one of the transverse slots shown ; (4) the front bar attached to the sides of the box ; and (5) the two sliding bars. In this figure three new and important features are shown : (1) The large hook FF, made of hard wood and suspended from a cord passing through the hole in the top board. The hook itself hangs through the corresponding transverse slot in the shelf, and when held in the position shown, is caught by the bottom edge of the sliding bar 1, which is represented up. A metal ring, placed just below the slot, is connected with the front bar D by a strong piece of elastic, or wire spring, G. The ring encircles the hook F, and would pull the hook towards the bar D were it not held, in its present position, by the tight cord tied to it, which passes through the perforated narrow board H. This board is fixed to the back edge of the shelf B. The position of the hook set free by the slackening of the cord is shown in No. 4.

In order to complete the machine it must be fitted up with eight hooks, springs, rings, and cords. A greater number of hooks can be used, and the capacity of the machine much enlarged, but the details of the construction would remain the same in any case.

Turning back to fig. 97, where the Jack-in-the-

Description of the Jack-in-the-box box is shown fitted in the loom, the eight headles suspended from the eight levers, will be recognised as similar to those seen in the illustration of the shedding motions in Chapter XIII. The cords, however, which in those passed down from the ends of the levers and were fastened to the ends of the long marches, are now seen to pass into the box and terminate in the hooks hanging there. In this case only two long marches and two treadles are needed, instead of as many of each as there are headles in the harness. The long marches are connected with the two rising and falling bars, whose ends project from the side slots in the box.

The machine itself is now complete, and, if the treadles of the loom are worked alternately the result will be, that, the two sliding bars will rise and fall regularly, but nothing else will happen, as the hooks at present are all held back by the rings and springs as at No. 4, fig. 98.

Tie-up of the Jack-in-the-box The tie-up to the headles, in accordance with the design, must next be effected. From the ends of the levers, just above the headless, even loose cords and one tight one are seen to pass into the back of the box, and it is by means of these cords that the tie-up is made. As the tie-up has to be made with very great nicety, all the strings must have adjustable loops, as well as the cords by which the hooks are suspended.

Although any tie-up can be arranged for, it will be best, for the purpose of illustration, to take the simplest one possible, which is that for an eight-headle twill. For the formation of this, the headles will have to rise in regular succession from back to

front. The cord from the first or back lever, therefore, must be tied to the ring of the second hook, which is the *first* in the back row of hooks. The second lever cord must be tied to the third ring, the third lever to the fourth ring, and so on till the last lever is reached. This cord must cross over and be tied to the first ring in the box. Now if the cords are all of the proper length—which can only be ascertained by experiment—the result of drawing down any one of the hooks will be that the lever to which it is suspended will be drawn down with it, and its other end, to which the headle is suspended, will be raised, raising the headle with it. The lever rising will also tighten the cord which is connected with the ring of the next hook to be drawn down and pull it forward, so that it catches on the sliding bar, which is at present up. When this bar is drawn down by the treadle, it carries the hook down with it; this raises the headle and draws forward the next hook, and so they all follow, in succession, till the last is reached, which, being connected with the first ring, draws it forward, and the same course is repeated again and again. All that is now required to start the motion, is, for any one of the hooks to be placed under the sliding bar and drawn down by one of the treadles; all the others will then follow in proper order if the tie-up be correct. The tie-up always has to be arranged so that each succeeding hook is in the opposite row, in order that it may be drawn down by the alternating bar. This can always be provided for by altering the tie-up of the hooks to the levers above the box, if it cannot be done without.

Tie-up of
the Jack-in
the-box

Working
the Jack-
in-the-box

The action of this little machine, especially when

Working
the Jack-
in-the-box


The
Drawboy
Machine

used for the weaving of light webs, such as twills and satins, is most neat, cheerful, quiet, and altogether admirable.

The *Draw-boy machine* is of much greater capacity than the Jack-in-the-box, and more adapted for heavy and complicated work. Any number of headles or cords, singly or in groups, up to as many as four hundred or more, can be managed by its means, and only two treadles are required to keep it in motion. It was originally intended for use with the draw-loom, in place of the boy employed by the weaver to draw the cords necessary for the successive lines of the design, as will be explained later on. It was, however, soon adopted for the purpose of drawing the complicated systems and sets of headles for pattern-weaving, which had till then been drawn by a large number of treadles, brought in and out of action by various levers and cords. It is said that "when introduced in Spitalfields the weavers hoped to reap great advantage from them; for instance, they would save the draw-boy's wages. But they began to find that they had adopted a mistaken notion. They found that if they had not to pay the draw-boy they had to pay the manufacturers for the use of the machine, and, moreover, the work itself was heavier." The complaint that the work was harder would refer only to the draw-loom, as the simple management of two treadles must be much easier and lighter than that of twenty.

Fig. 99 is a representation of a drawboy machine. It is shown attached to a set of cords, A. These cords may, in their turn, be connected with any system or sets of headles. Twenty cords are shown,

detail. No. 1 is the framework, which consists of four strong wooden uprights, about two feet six inches long, D, D, D, D. These are set firmly in



pairs on two cross-pieces, E, E, which are screwed to the ground at the side of the loom near the front and about two feet apart. Each pair of uprights is joined together at the top by a strong cross-piece, and there are also cross-pieces, F, F, just above the centre. In these centre cross-pieces, on the insides,

there are sockets, made to hold the end pins of a rocking shaft, which when placed in them reaches from one end of the frame to the other. On the centre of the outside of the cross-piece F, at the end shown in the drawing, a pulley may be seen raised a little above its top edge. The two pairs of uprights are joined together by four side cross-pieces; G, G, G, G. Two of these are fixed at the top and two at the sides a little lower than the end centre cross-pieces F, F. The cross-pieces G are made of hard wood, and have a number of holes (in this case ten in each) accurately and smoothly drilled in them, not more than an inch apart, The row of holes must begin and end about six inches from the four uprights.

Details
of the
Drawboy
Machine

At H, no. 2, a rocking shaft is shown, which fits into the sockets on the inside of the cross-pieces F, F. The shaft is made of hard wood, and must be exactly the same size, and perfectly square from one end to the other, so that the pecker, I, when fitted on it, may be made to slide easily backward and forward along its whole length. At one end of the rocking shaft a large, strong, deep-grooved pulley, K, is firmly fixed. Through the pulley a segmental hole is cut, just above the centre, where the shaft joins it.

The
Rocking
Shaft

The pecker, I, no. 2, shown in position on the shaft and in side elevation on the right, is also generally made of hard wood, although sometimes partly of metal. The points a, a, and the top edge, have a deep but narrow groove cut in them, just large enough to allow a fair-sized cord to slip in them. The pecker has also a hole pierced through it, just above the shaft, as well as the square hole through

The Pecker

The Pecker which the shaft itself passes. When the rocking shaft is in its place (see fig. 99) the pulley K is near the end of the shaft towards the back of the loom. In the groove of this pulley a strong cord is placed, its ends being tied separately to each of the two long marches of the loom, B, which are made long enough to enter the frame beneath the end of the shaft where the pulley K is fixed.

The Cords No. 3, fig. 100, shows a section of the machine, with the pecker, also in section, in position. G, G, G, G are the perforated side cross-pieces; the pecker is seen mounted on the rocking shaft; L, L are two, of twenty cords, having weights at their ends which are seen, in fig. 99, to hang in the holes of the side cross-pieces, a row of ten being on each side of the machine. Near the points of the pecker, a, a, a hard knot, or bead, is so placed, that, when the rocking shaft is set in motion by the long marches being pulled down alternately, the pecker will rock from side to side, and, catching the cords in the groove at its points just above the beads, will pull the cords downwards, first on one side, and then on the other. It will now be seen that if the pecker be caused to slide along the bar, rocking as it goes, its movement being properly regulated, as it comes opposite to each pair of cords, they will be pulled down as described, and that by the time the pecker has passed the twenty cords, they will all have been pulled down in regular succession. If then the side cords of the drawboy machine are tied up to a set of twenty headles, the latter may be caused to rise in any grouping and sequence desired.

In order to complete the description of the draw-

boy machine, it only remains to explain the means by which the pecker is caused to travel along the rocking shaft. No. 2, fig. 99, represents the back end of the machine where the pecker motion is placed.

The Pecker
Motion

M is a strong board firmly screwed to the uprights. Above the board, between the uprights, a part of the pulley of the rocking shaft, with its segmental hole, may be seen. Opposite the centre of the hole, and projecting a little from the board, to the top edge of which it is fixed, a small metal pulley matches the pulley at the other end of the machine above letter F, fig. 100. Over the pulley F in fig. 99 a cord with a weight, N, attached to it is seen to pass, through the pecker, and along the shaft to the segmental hole in the large pulley, where it disappears. Turning to no. 2, the same cord, coming through the hole in the rocking shaft pulley and passing over the small pulley on the edge of the board, is seen to be attached to another large pulley, which is riveted to a ratchet wheel. The combined ratchet wheel and pulley turn loose on their axle, which is a stud strongly bolted to the board M. Now, if the ratchet wheel be turned in the direction of the arrow, the cord will be wound on to the large pulley and drawn through the hole, drawing with it the pecker along the rocking shaft, past each pair of cords, until it reaches a stop, fixed on the shaft near the rocking shaft pulley. Also, if the distance between the beaded cords, be made equal to the teeth of the ratchet wheel, the pecker as it travels along the shaft will stop between each pair of drawing cords, and, as it rocks, pull them down first on one side, and then on the other. When the

The Pecker
Motion

pecker has drawn all the cords, if the ratchet-pulley be released, the weight N, fig. 99, will bring the pecker back to its original position in the machine.

The ratchet wheel itself is governed by means of two catches, P and Q. The catch P, is to prevent the ratchet wheel turning back before the pecker has finished its course. The other catch, Q, is to move it gradually, one tooth at a time. The catch P has a thin cord attached to it, which may easily be guided by pulleys to the front of the loom and enable the weaver to release the ratchet at the completion of one repeat of the pattern. This, of course, coincides with the pecker's arrival at the stop on the rocking shaft. The catch Q, which moves the ratchet, is connected with one of the marches by the cord which passes over the pulley R, and its length is so regulated as to raise the catch just enough to move the ratchet one tooth at a time, or as may be desired. The mechanism of the catch Q, is shown above no. 2. It is simply a piece of hard wood having a long slot, into which the ratchet wheel partially enters. It is so hung that the pin S, will be, when the catch is at rest, just underneath one of the teeth, and as the catch is raised by the cord attached to the march, it will move the wheel, which, when moved, is prevented from returning, as the catch Q falls, by the second catch, P.

Utility
of the
Drawboy
Machine

Any of the designs previously given could be woven with two treadles if the drawboy machine were used. Fig. 101 is, however, an example of the kind of design for which it is specially adapted, and the way of tying it up to the cords is shown

above the machine (fig. 99).* This design might be woven in various ways, but it will only be necessary to give two of the most useful workings as specimens.

(1) The warp might be fine cotton or linen, entered in the back or figure harness in the order shown above the design, two threads being entered together in each headle eye for each square of the drawing. If in the reed there were forty threads to an inch, the woven design would be about twice the size of the drawing. The kind of weaving suggested in this case would have the same effect as that described at p. 176, fig. 80, being a tabby ground with a floating figure woven by alternate shoots with two shuttles. In addition to the figure harness, a ground harness having long eyes must be used. It would be advisable to make it of eight headles, as such a harness would be most generally useful, and it could just as well be used with only two treadles as a harness of smaller capacity.

The warp would be entered in the front harness singly, in regular order, and the eight headles would be tied up to the two treadles in the usual way (see fig. 71, no. 1, p. 166).

The length of the design would be regulated by the number of times the depression of each treadle was repeated. Probably two treads for each line of the design would be sufficient, but this depends

* The tie-up of two lines of the design to two draw-cords of the drawboy only are shown (fig. 99, p. 239). There would, of course, be a much greater space between the top of the draw-cords and the headle cords than it is possible to show in the limited space at disposal.

Utility
of the
Drawboy
Machine

Examples
of the Use
of the
Drawboy
Machine

Examples
of the Use
of the
Drawboy
Machine

entirely on the size of the warp and weft used in the weaving. Either a fine coloured, tussah silk or




FIG 101.—Design for Floating Figure on Tabby Ground.

fine wool, would be a very suitable weft for the pattern shoot of this material.

(2) This would be a very suitable design for a fine silk damask, the arrangements for which would be as follows. The headles would have to have eyes or mails of glass, with separate holes for eight or ten threads to be entered in. (See fig. 92, letter D). These eight or ten threads are represented in the drawing by one small square of the ruled paper. The headles, too, would of course be spaced, so that leashes were only placed on the shafts where required (see top of fig. 101). In addition to the twenty pattern headles, a front or ground harness of eight headles with long eyes will be required, in which the fine silk threads must all be separately entered. The number of leashes to the inch must agree exactly with the spacing of the figure harness. It is not necessary that the number of threads lifted by each mail of the figure harness should agree with the number of headles in the ground harness, but only that the whole number of threads must be entered evenly and come out to the same total width in both. The satin made on eight headles may either be eight-headle satin or four-headle broken twill. In the latter case it would only require four treadles for the ground harness, but in order to make a fine, rich-looking damask, eight-headle satin, requiring eight treadles, must be used. The method of tying the treadles up for the satin has already been explained in the chapter devoted to their consideration, and that of damask-weaving in connection with fig. 91, p. 211.

In damask-weaving it is not necessary to drop the pattern headles between each shoot of the ground weft. The two treadles of the drawboy machine can therefore have a hook near them screwed in the

**Examples
of the Use
of the
Drawboy
Machine**

floor, which will allow of their being conveniently held down, while the necessary number of ground treadles are worked over. In this pattern each line of the design would require about six shoots of weft between the change of figure treadles. In damask-weaving the length of a design can be perfectly regulated by the number of times each line of the ruled paper is worked over. It is necessary to add that in the case of damask-weaving the drawboy machine only acts on the figure harness, the ground harness having to be governed by treadles in the usual manner.




Plate IX.—Piece of Eighteenth-century Silk-weaving,
illustrating *Tobine* Stripes.

See page 228.

Victoria and Albert Museum, South Kensington.



Plate X.—Fragment of Seventeenth century French Brocade,
a most perfect specimen of the Weaver's art.

See page 316.

Author's Collection.

PART III

COMPLEX PATTERN-WEAVING

PART III

COMPLEX PATTERN-WEAVING

CHAPTER XVI

THE DRAW-LOOM AND THREAD MONTURE

Ancient Origin of the Draw-loom—Its Importance in Weaving—Description of Draw-loom—Building the Monture—The Two Kinds of Repeating Patterns—The Comber-board—The Pulley-box—The Tail Cords—The Simple and Guide Cords—The Term *Cords* in reference to Design—Rigidity of Lateral Repeats on a Loom—Freedom of Vertical Repeats—The Drawboy—The Drawboy's Fork—The Most Perfect Loom—The Thread Monture—Various Uses of the Thread Monture—Examples of Silk-weaving on Thread Monture.

THE number of headles it is possible to hang effectively in a loom must necessarily be limited, because of the space they occupy, no matter how closely they may be crowded together and how thin their shafts may be made. This limitation renders it impossible to weave any large design with a figure harness composed of headles. The small

Ancient
Origin of
the Draw-
loom

Ancient
Origin of
the Draw-
loom

capacity of the headle harness led, no doubt, to the invention of the *draw-loom*, in which, in place of the headles, a narrow perforated board is fixed across the loom, in the holes of which, separate leashes are hung. They are so arranged, that a design which occupies the whole width of the loom for one lateral repeat, takes up no more space than a harness of eight or ten headles, on which number only the very smallest patterns can be woven, as we have already seen.

Importance
of the
Draw-loom
in Weaving

It is impossible to fix the date of this ancient invention. The earliest specimens of, what are without doubt, draw-loom webs, are of about the sixth century, and are of Asiatic origin. But when, or wherever it may have first been made, THERE CAN BE NO DOUBT THAT THIS INVENTION IS THE MOST IMPORTANT IN THE WHOLE HISTORY OF TEXTILE DEVELOPMENT. All the finest pattern-weaving of the Eastern, as well as the Western world, ancient and modern, has been done on the draw-loom principle, and even the invention of the Jacquard machine, which is often supposed to have superseded it, did not alter the essential principle of draw-loom weaving in the least. Jacquard's invention only rendered the tedious process of tying up the design on the cords of the loom itself unnecessary. Jacquard substituted for the tie-up, an endless band of cards, on which the pattern to be woven was punched line by line. The design for the tie-up of the cords of the draw-loom was worked out, or draughted, on paper, ruled out in squares, in exactly the same way as is requisite for the punching of the cards used in the Jacquard machine. In some of the early accounts of its introduction into this country, Jacquard's invention is called the "new draw-loom engine."

The essential part of the draw-loom is the perforated *comber-board*, in and about which the *monture*, as the draw-loom harness is called, is built.

Description
of the
Draw-loom

Fig. 103, is a representation of a draw-loom monture very much simplified for the sake of clearness. A headle harness is drawn below it for comparison. A is a harness of six headles, entered, in the way before described, as necessary for a design having equal sides pointing different ways, and which requires eleven threads of warp for one lateral repeat. B is the comber-board of a draw-loom, perforated with eleven holes in a single row. C is the bottom board of a box pierced with six holes, through which the cords D are seen to pass. These answer to the cords from which we have hitherto seen the headles suspended. We need not trouble at present about the means of




FIG. 103.—Diagram of Monture and Harness, Point Repeat.

Description of the Draw-loom governing them, whether by treadles, drawboy, or Jacquard machine. All that concerns us now are the details of the monture below the board C.

Hanging in each of the eleven holes of the comber-board a separately weighted leash may be seen. The weight itself consists of a thin strip of lead wire, having a hole at one end, by which a loop of harness thread about six inches long is attached to it. These strips of lead are called lingoos, and vary in weight from an ounce upwards, according to the kind of material to be woven in the loom when completed. As in some cases there are as many as three or four thousand of these lingoos in a monture, the accumulated weight is considerable when a large proportion are drawn up, especially as the weight is nearly doubled by the friction at various points of the monture. At the other end of the thread loop, to which the lingo is attached, a glass eye or mail is tied, having at least three holes in it, through the centre one of which the future warp will be entered. The holes at the ends of the mail are used, one for attaching it to the loop of the lingo, as we have just seen, and the other for tying it to another loop about nine inches long. When this has been done the leash is complete as shown at E.

Building a Monture When preparations are being made to build a monture all the loops of one size are, of course, made together of exactly the same length. They are then tied up in bundles ready for slipping on to the mails and lingoos, as required.

In building a monture the top loops of the leashes are hooked up through the holes in the comber-board, and a cord temporarily threaded

through them in order to keep them suspended while the upper cords are being attached. This is shown, still in place, in the separate diagram F.

Referring now to the plan of entering the harness shown at A, the first, and the eleventh leashes, are found on the first headle. Accordingly the corresponding leashes in the comber-board, must be joined by threads passing from them to the end of the first cord at D, in the bottom board of the box C. The second and tenth leashes are on the second headle; the corresponding ones to these in the comber-board must be joined in the same manner to the second cord D. The third and ninth, fourth and eighth, and the fifth and seventh leashes, must be connected in like manner to the cords D, while the sixth, the only remaining leash, is to be connected singly with cord 6, which corresponds with the sixth headle, on which only one leash is found to two on each of the other headles.

It is now obvious that if any of the cords D are pulled upwards, singly or in combination, it will have the same effect on the warp, entered in the mails, as the similar raising of any one or more of the harness headles. Thus we have in a single row in the comber-board, equal facility for selecting and raising particular threads of warp with that afforded by the six rows of headle-mounted leashes. But this example, owing to the necessary simplicity of the drawing, is very inadequate to show the enormous advantage obtained, for suppose the row of holes in the comber-board extended to eleven hundred (quite a moderate number) instead of only eleven, the effect would be the same as if the harness consisted of six hundred headles, which is, of course, an impossible

Building a
Monture

The Point
Repeat

Monture
Capacity

The
Comber
Repeat

number. A linen table-cloth was woven at Dunfermline, about sixty years ago, which required a comber-board with four thousand two hundred leashes, each




FIG. 104.

under separate control, so that one, or any combination of them, could be raised as indicated on the draught.

Fig. 103 shows the comber-board arranged for the *point* repeat, the valuable qualities of which, to the designer, will have to be dealt with later on. Fig. 104 is the same in all respects as the previous one, except that it

is what is now called a comber* repeat. It has the same effect as the ordinary straightforward entering of the harness, indicated at the bottom of the diagram. Two exact repeats, or combers, on six threads, are shown in the harness, and these require twelve holes in the board, instead of the

* Originally *camber*.

eleven required for the turnover point repeat. Any design for this arrangement would have to be made so as to repeat on every six threads of the warp. For comber repeats, the necking of the monture is tied up differently. The first and seventh leashes are connected to the first cord D. The second and eighth, the third and ninth, the fourth and tenth, the fifth and eleventh, and the sixth and twelfth are all likewise joined to the top cords in regular order. This difference between the point and comber repeats of woven designs must always be borne in mind, as they will now very frequently be referred to.

The
Comber
Repeat

Fig. 105 represents a draw-loom complete enough for the purpose of explanation. In this drawing the comber-board is pierced with three rows of holes. It will also be observed that it is not simply a single board, but is composed of several slips of thin, hard wood. This is a great convenience when a very large number of holes is required, as the perforated slips can be spaced out slightly, and thus enable the builder to regulate the number of holes to every inch of the entire width, which must be done with great accuracy.

Building
the Comber-
board

The comber-board in the illustration is made up of eight slips, each containing nine holes. The board is therefore pierced with seventy-two holes in all.

These seventy-two holes are divided into four repeats of eighteen holes each. It is usual in England to hang the first leash in the first row, at the back left-hand side, as indicated in the drawing. To prevent confusion, only the first six leashes which begin the repeats and the last one in each repeat are shown, these being all connected in the diagram by dotted lines. The first leash of each

[illegible]

FIG. 105 —Mechanism of the Draw-loom.

repeat is attached by the necking cords to the first pulley cord D, which is seen to enter the pulley-box, C. Six pulley cords only are shown, but it is evident that there must be eighteen of them, as eighteen sets of four necking cords each have to be tied to them. The attachment of the six sets of necking cords is shown, and from these the principle of the whole arrangement will be readily understood. It must be noted that the height of the pulley-box, above the comber-board, must be much greater than could be shown in the drawing without making all the parts inconveniently small. It may vary from four to six feet. As much height as possible is necessary here in order to avoid friction in the working.

Building
the Comber-
board

The *pulley-box* itself (C) now claims attention. The bottom board of the box, looking upwards, shows the eighteen holes through which the pulley cords pass. Inside the box an arrangement of the eighteen pulleys is fitted up. They are so placed as to be immediately over the holes in the bottom board. The box has to be very strongly framed together, and to be very firmly fixed in its place on the top of the loom. The comber-board also has to be very firmly fixed close to the ground harness in the exact position required for the proper opening of the shed. In gating the loom all these details of position require a great deal of consideration and experiment.

The Pulley-
box

The pulley cords D, after passing over their several pulleys, are carried to the nearest wall or beam, and tied there in regular order, being accurately adjusted as to length, in a horizontal line, as shown at E, fig. 105. These cords, between the pulleys

The Tail
Cords

- The Tail Cords and the wall, are called the *tail cords* of the loom. When a drawboy machine is used the design is tied up on them, and they are simply pulled down in the requisite order to form the pattern. The pulling down of a tail cord pulls up the corresponding necking cords, and raises the several leashes depending from their ends. By this means the necessary shed is opened.
- The Simple and Guiding Cords When a real drawboy, not a machine, is employed, another set of cords, equal in number to those of the tail, is required. These are called the *simple*, and on it the design is tied up. In the illustration the simple is shown joining the tail cords at F, F, and from that point its cords are carried vertically to the ground. In front of the simple two very strong cords called *guides* are stretched vertically, between the ground and the roof of the workshop. The groups of ties to the simple cords, making each separate line of the design, are gathered together and passed round these strong guiding cords in succession as they are formed. By this means they are kept in regular order and free from entanglement. In the drawing the small design no. 2 is shown tied up on the simple, and its formation will be readily traced out.
- Capacity of an Ordinary Silk Monture The above description of the draw-loom, although complete as to its mechanism, must not be taken as a sample of its capacity. It is only intended to show the construction and purpose of the various parts of the machine, as well as their relation to each other. In a very ordinary silk-loom the space occupied by the design no. 2 would not be more than three-quarters of an inch, so that there would be in the narrowest loom, say twenty-one inches

wide, twenty-eight repeats to be allowed for in the comber-board. The latter would have to be pierced with five hundred and four holes, and require to be furnished with the same number of leashes. Twenty-eight leashes would have to be attached to each of the pulley cords, and by their means the pattern would be exactly repeated across the whole width of the web. WITH THE SAME COMBER-BOARD AND THE SAME NUMBER OF LEASHES ANY KIND OF REPEAT THAT CAN BE DESIGNED ON FIVE HUNDRED AND FOUR LINES OF RULED PAPER COULD BE ARRANGED FOR. The most ordinary repeat is, perhaps, two combers or one repeat point. Either of these would require two hundred and fifty-two cords in the simple for working out the design on, and, of course, the same number of tail and pulley cords. In this case each pulley cord would only have two leashes attached by the necking to it. The technical method of describing the number of lines in the width of a design is, to say that it is draughted on, two hundred and fifty-two cords, or four hundred cords, as the case may be; the cords referred to being those of the simple. The same term is used now in connection with the Jacquard machine, but it would be more correct to say, draughted for so many needles or hooks, as these have taken the place of the *simple*, in modern weaving.

It may be well here to call attention to the fact, that, in all weaving, but particularly in drawloom, and Jacquard weaving, the *width* and number of repeats in a loom is most rigid, and cannot be altered without rebuilding the whole monture. The designer and draughtsman must know exactly the number of cords and the kind of

Capacity of
an Ordinary
Silk
Monture

The Term
Cords
used in
describing
Width of
Design

Rigidity of
Lateral
Repeats in
a Loom

Elasticity of Vertical Repeats in a Design repeat the loom has, which he is designing for. This is not the case with regard to the *length* of the design ; here the artist is at perfect liberty. The only objection to a very long, vertical repeat is, that the tie-up for the draw-loom, or the endless band of cords for the Jacquard machine, has to be more extensive. No alteration is required in the loom, whatever length the design may be, nor is the weaver's work affected by it to any appreciable extent.

The Draw-boy The work of the *drawboy*, as the weaver's assistant was called, must now be described. He had to pull forward, by means of the loops on the guide cords in front of the simple, each set of cords, in regular order, as they were required to form the successive lines of the design. He not only had to pull them forward, but downward, in order to raise the leashes ; and not only this, but to hold them down while the weaver worked over three, four, or more shoots of the ground, as explained in the chapter on damask-weaving. We have seen that the lingoes often weigh an ounce each, and also that in a not over-rich silk-loom, such as that described at p. 261, twenty-eight leashes had to be raised by each cord of the simple.

The Draw-boy's Fork When several of these cords were drawn together, and the frictional resistance added to the actual weight of the lead, it is obvious that the boy must need some mechanical assistance in drawing the cords down, and holding them as long as required. The heaviest line in no. 2, fig 105, is the sixth, in which twelve cords have to be drawn together. The lingoes for these would weigh three hundred and thirty-two ounces, or twenty-four pounds, so that, taking into consideration the frictional as well as the dead weight

on this line, the cords have to raise thirty-six pounds at least, and the boy has not only to lift that weight, but, as just explained, hold it for about one-third of a minute while the ground is woven. For

The Draw-boy's Fork




FIG. 106.—Draw-loom Fork.

his assistance in this arduous work the boy is furnished with a fork and lever (fig. 106).

This drawing shows a solid stand, no. 1, having two broad uprights. This is fixed by the side of the simple, but a little in advance of it. At the top the uprights are joined together by two parallel bars. A, is a block of hard wood which fits between the two bars, and is kept in position by four small wheels, or runners, being fixed on both sides of the block, two above and two below, as shown in the drawing.

The Draw-boy's Fork These runners allow the block to move freely along from end to end of the bars. The fork and lever, shown separately at A, E, are hinged to the top of the sliding block in such a manner that they can be easily moved from a vertical to a horizontal position, and will remain in either.

When about to be used, the block is moved back until the points of the fork are by the back edge of the simple, and in the upright position as shown in section at B, no. 2. The boy, by means of the loops, next draws forward the simple cords necessary for the formation of one line of the design. He carefully inserts the upper prong of the fork in the opening made, gradually drawing it forward as he does so. When this has been done the position is represented by C, no. 2. Grasping the end of the lever, the boy now draws it down and holds it in a horizontal position, the result being that the required cords are drawn down as shown at D.

The Most
Perfect
Loom

The most perfect pattern loom possible, is one in which the leashes are entered with one thread of warp only, and every leash is under separate control by means of the tie-up. On such a loom every imaginable form of design and variety of tie can be woven without the use of any other mechanism whatever. The extensive tie-up in the case of the drawloom, and the unmanageable quantity of machinery required if Jacquard machines were used, would, in the case of silk at any rate, render this unpractical. Silks warps, of twenty-one inches wide, sometimes contain, as we have seen, as many as eight thousand threads, which would involve the building of a simple with eight thousand cords, or the use of twenty Jacquard machines, with four hundred needles

Large
Designs
Unpractical
in Silk with
Thread
Monture

and hooks in each.* As regards the comber-board and the loom itself, there would be no difficulty ; in fact, the weaving on such a monture would be as simple as any pattern-weaving could possibly be.

If linen, cotton, or wool warps are used, such an arrangement for a fine bold design is quite practical. A design draughted on eight hundred and forty lines in the width of the ruled paper gives forty threads to an inch in the reed. This is sufficient for a massive pattern, where great refinement of detail is not required. Weaving with a thread monture gives the designer liberty to use any variety of texture, form, and detail that he can get in on the eight hundred and forty threads at his disposal. He may make the ground of tabby, twill, or satin, and he may ornament parts of the figure with tabbies of double, treble, or any number of threads, and fill the different spaces of it with any of the various twills or satins he may wish. IN FACT, HIS ONLY LIMITATION IS THE NUMBER OF THE SQUARES INTO WHICH HIS SPACE IS DIVIDED.

It will be seen that the preparation of the draught, particularly for this kind of weaving, is a most important work, as on it the whole of the success of the finished web depends—that is, with regard to its ornamental shapes and texture. It also requires a thorough knowledge of the effect that weaving has in modifying or exaggerating edges, angles, and outlines generally.

Fig. 107 is a portion of one of the finest of the traditional Italian damask designs. Various versions of it are to be found amongst sixteenth- and

* This might be possible if electricity were applied to the draw-loom.

Large
Designs
Unpractical
in Silk with
Thread
Monture

Practical for
Cotton,
Linen, or
Wool

A Large
Design on
Thread
Monture

Preparation
of the
Draught
needs
Technical
Knowledge

Example
of Italian
Design

Example
of Italian
Design



FIG. 107.—Italian Damask. Point Design.

seventeenth - century weavings. Some of the earliest wall-papers in imitation of silk damask were copied from it. There is some such paper remaining in the mansion of Christchurch Park, Ipswich, copied from one of the finest versions of it, the length of its longitudinal repeat being about nine feet.

This design will also illustrate the great advantage gained by using the point repeat. All the effect in scale of a design drawn on eight hundred and forty cords, is by its use obtained on a simple of four hundred and twenty cords. This was no doubt the reason for the frequent adoption of this plan of design in the early work. It will be observed that nearly all the old designs of greater width than ten or twelve inches are constructed in this way. We must notice in passing that in the Sicilian and early Italian designs (fig. 108), which are so admirable, narrowness of repeat is a chief characteristic of their construction, and there can be no doubt that the reason for this peculiarity is the desire for economy in tying up the design on the loom.



Example
of Italian
Design

FIG. 108.—Sicilian Damask.
Point Design.

Modern
Treat-
ment of
Traditional
Italian
Design

In this case, then (fig. 107), the simple would need four hundred and twenty cords, and the monture would have to be built in *point* as in fig. 103. The first, and the eight hundred and thirty-ninth leashes, would be drawn by the first cord, answering to the first, and the eleventh, in that diagram.* All the other cords would also draw the leashes from opposite sides until the centre cord 420 was arrived at. This, like the centre cord of the diagram (fig. 103), would only support one leash.

Effect of
Point
Repeat
on Tabbies,
Satins, and
Twills in a
Thread
Monture

If the centre cord only has one leash attached to it, a tabby ground will not be affected by it. This is one reason for building the monture on eight hundred and thirty-nine cords instead of the even number. All the other ties, satins, twills, &c., will be thrown in opposite directions by the point repeat. This will make little difference in the general effect, and will only require a little extra care at the centre line of the design, where the change of direction in the ties is most obvious.

Damask
Effect on
Thread
Monture

The damask effect depending on reversed satins can quite easily be woven on a thread monture. Fig. 109 shows a small portion of the design draughted for this effect. For the coarse texture at present under consideration a five-headle satin, shown in the sketch, is the most suitable one. A linen or cotton warp, not too fine in size, shot with wool of a contrasting colour, would bring the design out well. This kind of web used to be largely used for furniture and curtains, and was called *union damask*. It was very useful and artistic, as

Union
Damask

* One hole in the comber-board would remain empty, as the centre cord only requires one leash instead of two.




FIG. 109.—Union Damask.




FIG. 110.—Draught showing
various Ties.




FIG. 111.
Figure Draught.

Union
Damask

well as durable, if the colours were well chosen and the yarns good and well dyed.

Perhaps a still better effect would be gained by making the ground tabby and the figure a looser satin or a four-headle twill and shooting a coarse-spun or tussah silk into the warp instead of wool. Of course, endless suggestions might be made in this connection, but it is in such details as this that the designer and craftsman must exercise his taste and invention.

Another
Treatment
by Various
Ties

Fig. 110 is a draught of a portion of the same design in which a different treatment is adopted. The field or background of the design is a twill, while the figure is shaped and brought out by means of a tabby outline and the use of different ties for its various parts.

The Effect
of a Tabby
Ground

If a tabby shoot of weft, similar to the warp, were made between each opening of the figure shed, and an extra shuttle carrying a different weft used for the figure, the strength and solidity of the cloth woven would be much enhanced. This separate treatment of the design would also make it stand out from the ground in a bolder and much clearer manner both as to form and colour. The easiest way to do this would be to fit up a harness with long-eyed leashes in front of the monture and enter the warp in it as well as in the leashes of the monture. This would enable the weaver to work the tabby ground independently of the drawboy, by means of two treadles. The draught of this effect would not need the tie on the ground to be indicated, but would be drawn as in fig. 111.*

Front
Harness
preferable
for Tabby
Ground

* If a Jacquard machine to govern the thread monture is being used, the tabby can be made by inserting an extra card between each of the figure cards, and the extra harness would not be necessary. The

If the thread monture be used for silk-weaving without any additional harness or other appliance for making the groundwork, very perfect webs, full of variety and detail, can be made. The designs certainly must be very limited as to size, but that is practically their only limitation. They may be as fine as the finest engraving, for any lines and spots down to the three-hundredth part of an inch may be woven with the greatest ease and certainty. Such delicate little designs as fig. 112—which is reproduced the exact size of the original—are examples of thread-monture weaving. The example illustrated was made in Spitalfields about the end of the eighteenth century, most probably on a draw-loom with a draw-boy machine. A few weavers are left in Bethnal Green who still make this kind of silk, which is mostly used for ties and scarves. The Jacquard machine is, of course, now used for lifting the threads, but the monture itself is exactly the same as in the old times. This Spitalfields sample is woven about two hundred and eighty threads to an inch. The design repeats fourteen times in twenty-one inches, and is drawn for four hundred cords. The comber-board would have to be pierced with five thousand eight hundred and eighty holes, and the same number of leashes and lingoes would, of course, be required to fill it up. The repeat of this design is comber. Although the figures are turned over to extend them, they do not turn over on the same lines; they are work, however, would be much heavier, and the number of cards necessary would be doubled. The front harness would probably be used even in this case, especially as it would allow of the ground being changed at will.

Silk-weaving
on Thread
Monture




FIG. 112.—Spitalfields Silk. Size of Original.




Plate XI.—Example of French Silk-weaving, time of
Louis XIII. Size of design, 30" × 21".

See page 274.

Victoria and Albert Museum, South Kensington.

therefore what designers now call *drop turnover* repeats. This is of no advantage in regard to the Silk-weaving on Thread Monture




FIG. 113.—Part of Draught for Fig. 111.

weaving, but is an easy way of getting balance in a design, and is often resorted to.

Weaving
Large
Damask
Patterns

Fig. 114.—Leash fitted up for Damask.




Fig. 114 is taken from a portion of a ruled-paper draught for fig. 112. It represents the twenty-fifth part of a square inch of the finished silk, and shows the amount of detail required in such designs, as well as the freedom with which the textures may be varied in designing for this most perfect loom.

The manner of weaving damask webs with two harnesses has already been fully explained in Chapter XIV., but it is necessary just to describe the making of damask on the monture of a draw-loom, which takes the place of the figure harness. Such large designs as the traditional Italian pattern given in fig. 107 or the beautiful Louis XIII. damask of plate XI cannot be made on a thread monture, and, indeed, would lose a great deal of their beauty if they were. The fine sharp edges which result from the lifting of every thread would make such large designs hard and uninteresting. A great deal of the charm of woven ornament results from the mystery given to the edges of the forms by the more or less evident steps of their outline.

Both the large designs referred to are made on from four hundred to four hundred and fifty cords of the simple, acting on ten and a half inches of the warp, and as they are point designs, one repeat fills the whole twenty-one inches of the width of warp, and requires eight hundred or eight hundred and fifty holes in the comber-board. If

the count of silk in the warp were four thousand eight hundred threads, each mail in the monture would have to lift six threads at least. In order to do this the mails of the leashes must be perforated with six holes in addition to the two required for the construction of the leash. Fig. 114 shows a leash fitted up with its lingo, and a mail having the required number of holes. It will therefore be seen that THE RICHNESS OF THE SILK IN DAMASK-WEAVING DOES NOT DEPEND ON THE SCALE OF THE DESIGN, BUT ON THE NUMBER OF THREADS LIFTED BY THE LEASHES. After passing through the mails the threads of warp are entered separately in the long eyes of the front or ground harness, which is worked by treadles, and the process of weaving is the same in all respects as that described in Chapter XIV.

Weaving
Large
Damask
Patterns

CHAPTER XVII

THE SHAFT MONTURE

Invention of the Split or Shaft Harness—The Comber-board for Shaft Harness—Building a Shaft Harness—Description of Various Parts of the Harness—The Shaft Harness in Use—Note on regulating the Length of Designs—Draughting Designs—Examples of Shaft-harness Weaving.

Important
Addition to
the Thread
Monture

A VERY important improvement was made in the monture about the middle of the last century by Mr. James Gough, a weaver of Bethnal Green. By means of this invention separate grounds, satins, twills, and tabbies can be made without a separate front harness, the use of which was explained in the last chapter. At the same time the design can be worked out in a larger repeat on groups of two, four, or more threads, while the ties are made with single threads. This facilitates the weaving of fine silk in large designs, and gives freer opportunity, when a separate binder is provided, for making the large and important class of webs known as *tissues*, of which the *brocatelle* is a member.

Invention
of the Split
or Shaft
Harness

The invention was not made until after the Jacquard machine had come into general use, and was therefore never used on the original draw-loom. It would, however, have been a very useful addition

to it, and have made the wonderful tissues of the seventeenth and eighteenth centuries much less laborious to weave.

Invention
of the Split
or Shaft
Harness

This invention is called the *split* or *shaft* harness. One name is as good as the other, but each by itself only describes the invention in part, for the leashes are split, and they are also suspended on shafts.

The comber-board for this description of harness requires the same number of holes as the thread monture, but each cord of the simple raises several leashes together for the formation of the design, just as the glass mails lift several threads together in the damask monture.

The Comber
board for
the Shaft
Harness

Let us take such a warp of silk as the sample of Spitalfields weaving examined in the last chapter, and see what can be done with it on a shaft monture. The count was five thousand five hundred and eighty threads, one thread being entered in every leash. We will at once decide that each square of the ruled paper, on which the design is to be draughted, shall represent four threads. This gives us one thousand three hundred and ninety-five groups of four, in the whole width, which shall be twenty-one inches. Three comber repeats, of seven inches each, would be a convenient size for a design ; we decide, then, on this, and divide one thousand three hundred and ninety-five by three. This gives us four hundred and sixty-five cords on which to form the design. The ruled paper must also have four hundred and sixty-five squares, counted laterally, for the draught.

$$\begin{array}{r} 5580 \div 4 = \\ 1395 \div 3 = \\ 465 \end{array}$$

The number of rows of holes in the comber-board must next be decided, and if the most usual satin, viz., eight-headle satin, is intended to be used there must

**Building
a Shaft
Harness**

be eight, sixteen, or twenty-four rows. Twenty-four rows would no doubt be decided on, two hundred and thirty-three being in twelve rows, and two hundred

and thirty-two in the remaining twelve.*

Before the leashes are gathered up in groups and joined to the pulley cords by the necking they must be carefully examined, for it is in the leashes below the comber-board that the peculiarity of the shaft harness is to be seen.

Fig. 115 shows the formation and arrangement of the leashes. A, A, no. 1, is the section of a comber-




FIG. 115.—Section of Split Harness.

board having twelve rows of leashes suspended through its holes. The lower parts of the leashes have lingoes and mails, and are made in the usual manner. But between the mails and the comber-board the leash is much longer than usual in the ordinary monture, and part of this length is occupied by a long loop, which begins at, or a little above, the mail and reaches

* For description of comber-board and illustration see p. 308.

about half-way between it and the comber-board. The upper part of the leash to which the loop is attached is made of stouter cord. This passes through the comber-board and is gathered together with another, or it may be, several other leashes, and knotted to a necking cord, which in its turn is attached to the cord coming from the pulley-box above the loom. The twelve leashes of the illustration are shown joined in fours to three of the necking cords of the monture. No. 2, B, B, shows the end of one of a set of twelve shafts of stout hoop-iron, made perfectly smooth, and enamelled. The shafts are a little longer than the comber-board, and are passed through the loops as shown at B, no. 1, in section, one shaft passing through all the loops of the leashes in each row. The shafts are hung from strong cords, which pass through an extra row of holes drilled in the frame of the comber-board, which is made wide at the ends for that purpose. The shafts are hung at such a height that the leashes just hang on them when the loom is at rest. This is the state of the four leashes on the left. If one of the cords of the simple, on which the tie-up of the design is made, be drawn, it will draw up with it the four leashes with which it is connected, but the shafts will remain stationary. If then the shafts were raised they would have no effect, as their particular loops are already drawn up. This position will be made clear by the centre group of leashes in the illustration, which has been raised by the figure cord. The third shaft in the group is seen to be raised, but has no effect on the leash. In the third group of leashes on the right the result of raising two of the shafts, while the figure cord is left down,

Description of the Shaft Harness is shown. The shafts have raised the two leashes, with which they are connected, but the other two members of the group are unaffected. It will now be seen that any ground or figure can be made with single threads by means of the twelve shafts independently of the figure harness. Also that any pattern made by the figure harness raising the four threads in groups may be made without affecting the shafts, so that in spaces where the figure is not raised the shafts can be filling in a background of satin or twill, as may be arranged.

The Shaft Harness in Use Fig. 116 will make the whole arrangement perfectly clear. The large sketch is a portion of a ruled-paper draught, and represents the face of a figured silk made on a shaft harness. The warp is fine white silk, of which the drawing shows one hundred and sixty threads. The weft is black silk, for the sake of contrast. The twelve shafts shown in section at fig. 115, each carrying a twelfth part of the warp, have to make a ground of twelve-shaft satin. This is indicated by the fine black dots powdered over the background of the draught. One shaft has to be lifted for each shoot, and each shaft must rise in the necessary order to form the satin. The mechanical method of raising the shafts will be described presently.

The effect of the figure harness is seen in the bold black squares of the design. These consist of weft, which crosses in front of the lifted white threads. The shaft satin has no binding effect on the figure, for the reason already explained; accordingly it follows that the smallest intersection of warp and weft in the pattern must be four threads wide. Such intersections are shown working a tabby

edge to the square in the centre of the flower. If all the odd- and even-numbered cords of the simple The Shaft
Harness
in Use




FIG. 116.—Draught for Shaft Harness.

were drawn alternately, this tabby effect, with a single-thread tie occasionally appearing in the

**The Shaft
Harness in
Use**

white portion only, would cover the face of the cloth. It will now be apparent that any ties on the figure, must be drawn on the design ; and that these when woven will be four threads wide. These quadruple ties are seen on the petals of the flower, arranged in diagonal lines. Much care is necessary in designing these ties, in order to prevent undue length in the floating loops of weft. The draught being made on ruled paper with squares divided equally 8×8 , the ties in this case are square and need more than one shoot of weft to build them up. If the designer had wished, he might have made them only one shoot high instead of four, as shown in no. 1 below the flower. This would, however, involve the drawing of the figure cords every shoot, and make the tie-up four times as long as at present. If a Jacquard machine were used, the number of cards required would also be increased fourfold.

**Note on
regulating
the Length
of Designs**

It is perhaps necessary to pause and specially note here that in order to bring any design to the required length, the cords of the simple have to be held down over two or more shoots, according to the size of the weft and the nature of the pattern. The draughtsman makes his design on the number of lines he deems necessary for the effect he wishes to obtain, but the number of shoots to each line required to bring the woven pattern to the same proportion as the draught, has to be settled by experiment, when the web is ready for starting. Some designs, especially for damasks, need each separate line to be repeated as many as eight times. In the draw-loom the figure harness is left up while the requisite number of shoots of ground are made, but with a Jacquard machine

the shed is closed every shoot, and opened again by keeping the same card on the cylinder of the machine, until the requisite repetition has been completed.

Draughting
Designs

Returning to fig. 116, no. 2 shows the manner in which the design would be worked out on the ruled paper. The ground would be left plain, being woven independently by the shafts. The pattern for the tie-up would have to be drawn with all its ties and subordinate effects, such as little diaper patterns and different-sized tabby fillings. Any shapes and details that can be got in on the available four hundred and sixty-five squares are weavable. In making the draught, care must be taken to avoid long loose floats of weft. The design may be of any length desired, but it must be remembered, that, great length of design needs a long tie-up on the draw-loom, or an expensive and unwieldy set of cards for the Jacquard machine.

No. 3 of the illustration shows the proportional size of the flower in comparison with the draught, and its general effect when woven in fine silk.

Plate XII is a copy of an eighteenth-century French silk. It was photographed from the woven silk reproduction, and is the same size as the original. The illustration only shows a part of the design, which is seven inches wide and repeats four times in a web of twenty-eight inches. The count of the warp is about the same as that of the Spitalfields example, fig. 112, p. 272. The groundwork is eight-shaft satin, woven on a split harness, and the lace-like pattern is formed by raising the threads two together instead of four as in fig. 115. The

Draughting Designs draughting is on eight hundred cords instead of the four hundred and fifty. This increase of size in the draught is rendered necessary by the fewer number of leashes raised by each cord of the simple. In all other respects the draughting and weaving of this silk are the same as described in connection with fig. 115.

CHAPTER XVIII

BROCATELLE AND TISSUE WEAVING

The Technique of Brocatelle Webs—Weaving Brocatelles—Draughting for Tissue weaving—Two Methods of mounting Binders—Old Spitalfields Tissue—Broché Tissues—General Utility of Shaft Harness—Shaft Harness for Coarse Materials—Tissues of Wool, Linen, and Cotton on Shaft Harness—Examples of Modern Wool Tissues—Old Method of Tissue weaving without Split Shaft Harness.

BROCATELLES and other webs, which weavers call by the general name of *tissues*, cannot be made on the shaft monture, described in the last chapter, without some arrangement being added in order to work a separately warped binder. The reason for separate warping generally, was given in Chapter XIV. But it will be necessary to examine a sample of these webs and ascertain the reason why a separate binder is specially required for brocatelle and tissue weaving ; and afterwards the fitting which has to be added to the loom, for this kind of weaving, can be explained.

The chief characteristic of a brocatelle web is the raised satin figure, which gives such a rich appearance to the fabric (see plate XIII). In a

The
Technique
of Brocatelle-
weaving

The
Technique
of Brocatelle
Webs

Damask
and
Brocatelle
Effects
compared

damask web the background of the figure is a satin, made by the long floating threads of the silk warp, while the figure itself is the reverse satin, in which the weft chiefly shows. In the brocatelle, on the contrary, the warp floats rather loosely in the figure, and a special weft entirely covers it up in other places. The second weft is tightly bound down by a separate binder, and forms the background to the design.

Fig. 117, no. 1, shows a portion of a brocatelle as it would be draughted by the designer. The weaver, in tying up the design on the simple cords, in this case, would not tie up the figure, shown in white, as he would for a damask web, but would tie up the ground, represented by the black portion of the draught. In like manner, on cards for a Jacquard machine the instruction to the card-puncher would be, "Cut the ground, not the figure." No. 2 shows the effect as far as it could be woven on the shaft harness as described in the last chapter. Plain satin has been woven all over by the shafts, the warp being white and the weft, as is usual in brocatelles, an undyed linen.* The satin ties, shown on the figure are of linen, but the ground having been raised by means of the simple cords, a black silk weft has been shot across the spaces so lifted. These ground spaces are thus only covered by unbound loops of the second weft, and the separate binder is required to tie them down securely in their places. In brocatelle weaving the characteristic raised effect of the satin figure is obtained by

* The first or satin shoot of a brocatelle only binds the satin, and does not show on the face of the cloth. Linen gives solidity of texture, and on that account is usually employed.

lightly weighting the roller of the main satin warp and heavily weighting the binder roller, and the effect is further enhanced by the harshness of the linen back.

No. 3 shows the ground weft bound down by a four-headle twill, and it is in order to enable this to be done that an addition of some kind has to be made to the monture. This may be arranged for in two ways, as follows: (1) The number of shafts may be increased by four, the extra ones being fitted up in front of those used for the satin ties of the main warp. This will make twenty shafts in all. On these shafts, four extra rows of leashes are hung by their long loops. These leashes have no top member

Damask
and
Brocatelle
Effects
compared

Plan of
making a
Separate
Binder




FIG. 117.—Illustration of Draughting.

Plan of
making a
Separate
Binder

Weaving the
Brocatelle

Care
required in
draughting
for Tissue-
weaving

passing through the comber-board, as the others have, but are complete when hung upon the shafts. The warp for the binder is brought through the main body of leashes, one between every four, and entered in regular order in the binder. This completes the arrangement, and the brocatelle effect of no. 3, fig. 117, is obtained by the following procedure. The first shoot of flax thread is made with the binder all lifted, and one shaft of the main warp lifted as well. The second shoot of weft (black silk in this case) is made with one shaft of the binder down and the ground of the design raised by the drawing of the cords of the simple. When this has been done the effect of one line of no. 3, fig. 117, will have been woven. The next and following shoots proceed in their proper order, first the flax and then the silk, in regular succession. A set of four additional treadles and levers will be required to lift the binder shafts, or if an automatic machine such as a drawboy or a Jack-in-the-box are used to lift the grounds, the necessary additions will have to be made for them.

In draughting for brocatelles, and other tissues, it is necessary to be more careful in selecting the ruled paper, in regard to its proportion ; as the length of the design of a brocatelle cannot so easily be regulated in the loom as can that of a damask. It is true the same *simple* cords can be drawn twice or thrice over, but as there are two wefts to be shot in, the space occupied by one line of the design is much greater than is the case in fine damask. The draught has to be made on paper ruled 8×12 , or 8×10 , and the final regulation of the length of the woven pattern must be made by the



Plate XII.—Copy, by the Author, of Eighteenth-century Fine French Silk.
A portion of the design only is shown. The part photographed
is the full size of the original.

See page 283.




Plate XIII.—Copy, by the Author, of Sixteenth-century Italian Brocatelle. A portion of the design only is shown, about half the actual size of the original.

See page 285.

alteration of the size of the wefting used, as well as by the closeness with which the weft itself is beaten together. In the case of some tissues in many colours, where several shoots of weft go to make up each line, the ruled paper has to have fewer lines in the height than the width. It may be necessary, therefore, to use paper ruled 8×6 or 8×4 . Anyway, all these points must be carefully calculated before the draught is commenced.

Care
required in
draughting
for Tissue
weaving

2. Another arrangement of the binder, required for weaving brocatelles, is to mount an ordinary harness, of the proper count, in front of the shaft monture in the same position as for damask-weaving, and to enter the second or binding warp in it. The warp, however, unlike that of the damask harness, is not entered in the mails of the monture leashes, but passes between them. It is also not necessary that the binder leashes should have long eyes. This kind of binder harness is sometimes preferred to the shaft harness, but the latter takes up less space and is in the position to receive another improvement, which will be noticed presently. As far as the brocatelle and some other tissues, which now claim our attention are concerned, one of the above plans of fitting up the binder harness is as good as the other. For a temporary work perhaps the binder could be more easily added in the second method.

Alternative
Plan of
arranging
Binder
Harness

The weaving of a great variety of fabrics is possible, with the draw-loom at the stage of development to which we have traced it. A volume, or perhaps many volumes, might be filled with descriptions and dissections of such webs, but a very few

An Old
Spitalfields
Tissue
analysed

An Old
Spitalfields
Tissue
analysed

typical specimens must suffice for the present handbook.

First we must examine two very different examples of tissue weaving, which might, however, have been woven on the same loom, with the same count of warps and precisely the same fitting up.

Plate XIV is taken from a fine piece of tissue-weaving made in Spitalfields probably at the beginning of the nineteenth century. The colours are green and gold. The ground is green satin, both rich in colour and in texture. The design is in green, lighter than the ground, and gold, and repeats *point* once in the width. Both the green and gold portions of the figure are tied by the same twill binder. The warp of the satin ground was not lightly weighted, as in brocatelle weaving, but is peculiarly flat, which would suggest that it was more heavily weighted than is usual even for a damask. The binder warp of the figure, on the contrary, is rather lightly weighted. This tissue has no linen shoot, but is all pure silk throughout, the weft of the ground satin being fine and rather harder than usual. The green and the gold weft used in the figure are both, rich, lightly twisted silk, known by the name of *tram*, as distinguished from *organzine*, which is the harder-twisted silk always used for warps. Three shuttles are required for weaving this web, one for the ground satin, which is the first shoot. The ground satin, as we saw was the case in the brocatelle, is made on the main warp, with the figure cords at rest and the binder all lifted out of the way. At the second shoot, the green part of the figure is lifted, and one shaft of the binder left down while the other shafts




Plate XIV.—Spitalfields Tissue in Green and Gold Silk.
Date about 1900.

See page 290.

Author's Collection.

This is shown as an example of skilful weaving, not of fine design.

are all raised. The shed for the second shoot being thus made, the shuttle carrying green weft is sent across, and passes behind the satin ground until it comes to the lifted figure. Here it goes in front of the satin and all the binder warp threads, except those entered in the one left down. These remain in front of the weft to tie it. When the shed has closed on the second shoot the gold figure cords are




FIG. 118 —Spitalfields Tissue.

drawn, the same binder shaft left down, and the shed being open the third shoot is made, the weft now being gold-coloured silk. This shoot also passes behind the satin ground, and behind the green figure as well, until it reaches the opening made by the raised ground warp and all the binder threads except the first. Here it shows on the face of the cloth, and when the shuttle is drawn out and the shed closed one line of the ground and figure will be completed, and is represented on ruled paper in fig. 118, letter A. In this draught the white squares stand for the main warp threads of green silk, the dots for the green binder warp threads, the crosses for the first shoot of green ground

An Old
Spitalfields
Tissue
analysed

weft, the black squares for the green figure shoot, and the lined squares for the third shoot, the gold weft.

The draughting of the separate colours on the ruled paper must always be done very carefully, as a separate tie-up has to be made for each. If, for instance, two shuttles have to be used in forming one line of the figure, as in the above case, there have to be two rows of loops in the tie-up on the simple, in order that the cords may be drawn in proper succession. If as many as seven shuttles had to be used for one line of the figure, the same number of rows of loops would have to be tied up for it.

A Broché
Tissue

The next example, fig. 119, is of quite a different character. In this design, a part of which only is shown, a great variety of colours are used, which have on the face of the material almost the effect of brocading in many coloured silks. Four shoots have to be made in each line of the weaving, one for the plain ground, and three for the figure, and they are all thrown right across the web in the ordinary manner. A glance at the back of the material would show that the colours are all arranged in lateral stripes of different widths, and also that the colour effect is obtained by changing the weft used for the figure, at certain intervals, as arranged for on the draught by the designer. In many designs of this class great ingenuity is displayed by the artist in distributing the coloured ornament in such a way, that, the lateral stripes of the weft are altogether lost sight of. This at first was no doubt the aim of the designer, who wished to obtain the effect of brocaded ornaments in a quicker way. But although this deception is quite possible, after all, some of the most successful of such designs show the method of working quite



A Broché
Tissue




FIG. 119.—Rococo Tissue. Broché Weaving.

A Broché
Tissue

frankly. It will be seen that the chief difference between this example and that of the tissue previously given is a matter of design. The working out is very similar, except that the ground is a tabby with a thick weft, such as used to be called a *lute-string*, or *lustring*, as it is often spelt on old designs. The three figure wefts are all thrown into the same shed of the binder, which opens, in different parts of the web, according to the drawing of the simple cords at three successive shoots. In order to show clearly the method of changing the colours of the weft, the sketch is ruled laterally from letter A to G. At A the architectural feature is coloured yellow and shaded with dark brown; in the yellow there are small touches of dark green, represented by the solid black. The foliage above the vase is mostly dark green, and the yellow shuttle is changed for one having light green weft in it, so that in the space marked B, only light and dark green show. In the space C the light and dark green are continued and the dark brown weft is changed to red (represented by dots). The light green at D is changed to purple (cross-hatching), and at E the dark green changes to yellow, so that in this space red, purple, and yellow occupy the three shuttles. At F the red changes to orange, in the pines, where it is heightened by touches of yellow, and in the space G with dark green, which takes the place of the purple shuttle.

Small
Broché
Tissue

Fig. 120 is an example of a small design, quite ordinary in form, which, when woven in the above manner, in lateral stripes of rose-colour, green, and dull gold on a dark blue satin ground, has a most excellent effect. This is woven with only two



Small
Broché
Tissue

FIG. 120.—Modern Broché Tissue. Designed and arranged for weaving by the Author.

Small
Broché
Tissue
General
Utility of
the Shaft
Harness

shuttles, one for the ground satin, and the other with changing wefts for the figure.

It is not only for the weaving of fine silk that the shaft monture is useful, but it is equally so for linen, cotton or woollen pattern webs, of either large or small design, such as are used for hangings, furniture, and other purposes. If properly planned, an astonishing variety of weft effect patterns can be designed, which do not require alterations to the loom itself. This is, indeed, the chief advantage of designs in which the weft is most conspicuous. It is obvious that where the warp is only used as a ground or binder to the ornament, alterations are easier to make. Different designs can be woven on the same length of warp, and altogether more freedom is given to the artist in arranging his design. Take, for instance, the simple matter of stripes. If a stripe or stripes of colour are made in the warp, they have to remain in the same position from beginning to end of the web. But, weft stripes, of any size, colour, or distance apart, can be thrown in at will. It is therefore a great advantage to have a loom built particularly with a view to weft effect designs, especially in a studio or small workshop.

Description
of a Most
Useful Shaft
Harness for
Coarser
Materials

As an example of a most useful build of shaft monture for the weaving of these coarser materials, the following may be interesting. The comber-board is the first thing to consider. We will suppose that the width of the web to be woven is twenty-four inches. It might be forty-eight inches,* in

* In the case of the warp being forty-eight inches wide a fly-shuttle would have to be used, and when two

which case the figures of the specification would simply have to be doubled. The space of the pierced part of the comber-board must be at least twenty-four inches, and in view of the material to be used, fine linen or cotton, it must be pierced with sixteen hundred holes, arranged in eight rows. The eight rows of leashes suspended in these holes will require eight shafts, and the leashes themselves must have much heavier lingoos than we saw to be necessary for fine silk. The number of cords in the pulley-box, or hooks in the Jacquard machine, should be four hundred, and four leashes should be raised together by the drawing of each cord for the figure. One comber repeat will fill the whole width of twenty-four inches, so THAT ANY DESIGN DRAUGHTED ON FOUR HUNDRED SQUARES, IN THE WIDTH OF RULED PAPER, CAN BE WOVEN ON THE LOOM.

The binder, in which there must be eight hundred threads of the same size as those of the main warp, may either be mounted on eight extra shafts in front of the figure shafts, or be distributed in an eight-headle harness. It should be on eight headles in order that tabby, twill, or satin binders may be made at will. The entering of the binder threads, is only in the binder leashes; they must pass between each two of the main warp, but not be entered in its mails. The raising of the binder harness may be either by means of the treadles and levers, or by the Jack-in-the-box, unless a Jacquard or more shuttles were required drop-boxes must be added. Most of the old draw-loom weaving was done with hand-shuttles, the fly not being invented till the middle of the eighteenth century, and the drop-box much later.

Shaft
Harness for
Coarse
Materials

Varieties of
Weaving
possible on
Shaft
Harness




FIG 121
Tie-ups for Tabby.

machine is used, in which case all the lifting, both of figure and binder, is done by it.

The reed, for the loom thus fitted up, would require eight hundred dents, and each dent to have two threads from the main warp, and one from the binder entered in it.

Some examples of the kind of weaving to be done with the above loom may now be given. In the first place, tabby cloth, quite plain and even, made by lifting single threads alternately, can be woven, all the threads of both warps being used. This would require all the shafts to be tied up to the treadles as shown at fig. 121, no. 1. No. 2 gives the sketch plan of the entering and tie-up of a tabby of two threads. No. 3 shows the plan and tie-up for three-thread tabby. Tabby of four threads could not be made unless there were sixteen shafts in the figure harness, and above that number of threads would make too coarse a tabby to be of any service.

Double or treble cloth could be made either with single, double, or treble threads, and with or without pattern. Also double cloth,




FIG. 122.—Curtain Border.

one portion having double threads and the other portion having single threads, could be woven, and double cloth of two different textures, one tabby and the other satin, could be devised.

Figs. 122 and 122A will show the great utility of being able to weave a perfect plain cloth, with a border introduced at regular intervals. The illustrations are from such a web. It was made for a heavy curtain to fill an archway, and both surfaces were alike. The border being double cloth, it was possible to make the front and back exactly alike, even as to the position of the colours, which in single weaving must always be reversed. The letters of a motto or a monogram might in this way be woven so as to be read rightly on both sides.

We must now examine three samples of woollen hangings recently made on a loom constructed according to the plan just specified.



FIG. 122A.—Curtain Edging.

Varieties of
Weaving
possible on
Shaft
Harness

Woollen
Hangings
woven on
Shaft
Harness

Woollen
Hangings
woven on
Shaft
Harness

Plate xv was woven for a church hanging in scarlet, blue, and green wool on a ground of fine cream-coloured, mercerised cotton. The ground is a treble-thread tabby, but shows very little on the face of the web—only, in fact, in the bold outlines of the conventional lily and the large leaf forms which compose the trellis of the design. The lily is in scarlet wool, and is only tied down by a satin, which is made on the simple cords of the figure harness. This loose tie allows it to stand well above the general surface of the cloth. The green vase and foliage, and the dark blue background, are tied by a four-headle, single-thread twill, made by the binder harness.

It is often found more convenient to weave this kind of material face upwards as the present example was made.

Examples
of Wool
Tissues

The order of the weaving was: (1) A tabby shoot of coarse mercerised cotton in a shed made by the tie-up of no. 3, fig. 121. (2) For this shoot all the cords of the figure harness are raised except the background of the design. For the binder the first and fifth binder shafts are raised. Into the shed thus formed the dark blue weft is shot. (3) All cords raised in the figure, except, the foliage and a portion of the trellis leafage. The third shuttle carries a light green weft, and the same binders are raised as for the blue shoot. The spaces between the scarlet lilies (about two-thirds of the design) are woven with three shuttles, but when the lily is reached a fourth shuttle must be added. In this part of the design all the figure cords are raised except those forming the lily itself. Here all the binder headles are left down, as the binding of this part of the

design is by four threads of the figure harness, in the same manner as shown in fig. 116.

The next example, plate xvi, is a portion of a very heavy wool and spun-silk hanging. In this web the binder does not show on the surface, except in the treble-thread tabby ground, as the few ties required on the figure are made by lifting one of the group of four threads raised by the cords of the simple, and are arranged for by the designer on the draught. The binder harness is, however, useful, as it ties in the wool at the back and keeps it flat; it also helps to force out the figure and make it stand well up from the ground. It will be observed that the two colours of the figure are so interwoven that there are very few long floats of weft which require being tied down. Whenever a float of more than seven squares of the ruled paper is made a binder is raised for the tie. Three wefts, carried by three shuttles, are used in this tissue, and four shoots are necessary to complete one line of the draught.

The warp consists of three thousand two hundred threads of spun silk, warped double. Their being warped double, makes the necessary number of threads (1600) for entering in the figure harness, and the binder must also have double threads like the cane warp. The spun silk for both warps is white.

The weft for the tabby ground is coarse, strong-spun silk, four or five ends being twisted together. This is also white. The weft for the figure is soft wool spun rather finely, several ends (six or eight) being also lightly twisted together. One shoot of the figure is green and the other a very dark indigo blue. One repeat of the bold design

Examples
of Wool
Tissues

fills out the whole width of the twenty-four-inch web.

The order in which the wefts are shot is : (1) The white silk in a tabby shed made by the shafts only, of both harnesses ; (2) the same weft in the alternate tabby shed ; (3) the figure harness alone being used, the green wool is shot into the shed first raised by the simple cords, and is followed (4) by the dark blue in the next figure shed. This completes one line of the design as draughted. This web is also woven face upwards, and the tie-up has to be so made, that, the cords lift first the ground and the blue part of the figure, and secondly the ground and the part of the figure coloured green.

Fig. 123 is particularly interesting, as it shows the great extent to which the changing of the weft in lateral stripes may be carried, with advantage. It is difficult in black and white to indicate the variety of colours used in this pattern, which is arranged to weave with one ground and two figure shuttles only ; but the changing colours are indicated to some extent by dots, lines, and cross-hatchings. Fifteen changes of colour are made in one vertical repeat, and the effect of lateral striping is entirely hidden. The weft changes are shown in the two vertical stripes at the side of the illustration.

The ground in this case is a tabby of double threads only, and is of fine linen. The tabby is made by both harnesses working together, as draughted at no. 2, fig. 121. As in the last example, there is no binder on the figure except in the few places where the length of the floating loops renders it necessary. Where thus required



Plate XV.—Wool Hanging, designed, draughted, and arranged for weaving by the Author for St. Christopher's Church, Haslemere. The colours are scarlet, blue, green, and white.

See page 300.



Examples
of Wool
Tissues

FIG. 123.

Examples
of Wool
Tissues

they are made by drawing one cord of the simple.

This pattern is woven face downwards, which makes it very light, both as to the tie-up and the drawing of the simple cords, but it needs the binder harness all raised while the figure is being woven.

The first shoot is one of tabby with white linen weft. The second is fine black or very dark green wool, two or three ends being wound together. This colour runs nearly all through the design, there being only three small spaces where it is changed, once to yellow, at A, and twice to green, at B, B. The third shoot begins with blue at C, and changes at D to green, at E to purple, at F to a different blue, at G to another green, at H to rose-pink, at I to green, at K to brown, at L to blue-purple, at M to green, and finishes the repeat at N with scarlet.

The Split
Harness not
Indispens-
able for
Tissue
weaving

It must be understood that all these examples of tissue weaving could be made on the loom as fitted up for damask weaving—that is, with a long-eyed harness in front of the figure harness, if to the latter were added another set of headles to work the separate warp of the binder. In fact, this was the kind of mounting on which the old brocatelles and tissues were made. The split harness is, however, a great improvement, and has many advantages, not the least of which is its occupying so little space in the loom.

The
Compound
Harness

There is another kind of harness for silk damask weaving which was also invented by a working weaver of Bethnal Green; this is called the compound harness. It is most ingenious, and has been extremely useful in connection with the Jacquard



Plate XVI.—Portion of Hanging of woven wool and coarse silk.
Designed, draughted, and arranged for weaving by the Author.
See page 301.

machine, for use with which it was invented, but as it is not suitable for use with the draw-loom it is not necessary to describe it here.

The
Compound
Harness

The next group of samples for examination require for their weaving a still further development of the monture, which must be explained in the next chapter.

CHAPTER XIX

THE COMPOUND MONTURE

Advantages of dividing the Monture—Description of the Compound Monture—Examples of Compound Monture Weaving—Old English Brocade—Eighteenth-century Striped Brocade—French Late Seventeenth Century Brocade.

Advantages
of the
Divided
Monture

THE scope of tissue-weaving may be immensely increased by building the monture in two or more divisions, to be governed by separate sets of simple cords, and acting on separate warps, all combining to make one web. This compound build of monture was often used by the tissue weavers of the sixteenth, seventeenth, and eighteenth centuries, and enabled them to produce an almost unlimited variety of webs. It is also even more largely used in modern pattern-weaving by power, which to a very great extent consists of warp effects. Warp effects, in power-loom where very long lengths of the same patterned material must be woven at the highest possible speed, are the most economical, as when once the loom is set up, no matter how complicated the pattern may be, the actual loom-tending is very simple. In the draw-loom sometimes, montures with as many as four divisions seem to have been used, but generally two divisions

were deemed sufficient. The weavers of the best periods for the most part used weft rather than warp effects in their webs.* The advantages of weft effects have already been dwelt upon in the previous chapter.


Advantages
of the
Divided
Monture

For the demonstration of the utility of the compound monture let us make an addition to the split shaft harness for silk-weaving described in Chapter XVII., p. 278. The comber-board is there described as pierced with twenty-four rows of holes, two hundred and thirty-three being in each row. These are lifted in fours by the simple cords, which number four hundred and six, in order to make three comber repeats in twenty-one inches. The leashes, in the twenty-four rows, are also separately suspended on twenty-four shafts. This is the figure harness complete. In Chapter XVIII., p. 287, four extra shafts were added for a separate binder, on which four rows more, of similar leashes were hung, but were not connected as those of the figure harness were with the comber-board. This completed the monture for making brocatelles and broché tissues. On the loom so arranged, brocading in detached spaces could not be done, as the binder warp would be in the way whether it were lifted or not. If left down it would hide or mar the brocaded ornament, while if it were raised it would

Description
of the
Compound
Monture

* There is a design for silk brocade in the print room of the Victoria and Albert Museum, South Kensington, which has a note at the back to the effect that four simples were required for its production. As it is only a sketch design, not a draught on ruled paper, it is impossible to say how the divisions were made or why they were required.

Description
of the
Compound
Monture



make the manipulation of the brocading shuttle very tiresome. In fact, a weaver of to-day would despairingly say it was impossible. For making true brocaded tissues, then, some addition to the shaft harness and binder is needed, and this need is met by arranging the figure harness as a compound monture.

Fig. 124 represents a pierced hardwood comber-board slip one inch wide and ten inches long. Twenty-one of such slips would be required to fill the frame of our comber-board. The twenty-four rows of holes in division A are already occupied by the leashes of the figure harness as described. For the compound monture the comber-board would have to be extended above the binder shafts as shown in division B, where six more rows of holes are seen to be pierced; and below these new holes the six shafts of the binder harness are already suspended by their long loops. These leashes must now all be connected with the comber-board in the same manner as directed for those of the figure

FIG. 124
A Comber-board Slip
308

harness (see p. 278, fig. 115). At the top of the loom the pulley-box must be doubled in capacity, or a second box having the same number of pulleys placed in front of it. Tail and simple cords must also be added to complete this addition. Sometimes the second simple was arranged on the opposite side of the loom, but more often the simples were placed side by side, so as to be worked together when required. All such details of the construction were, of course, subject to individual requirement and convenience.* All these additions being made, it only remains to join the leashes of the front harness, in regular order, to the cords of the front pulley-box, care being taken to connect them in the same repeats as the main figure harness. As the binder warp equals only one-fourth of the figure harness, it follows that the leashes of the former must be joined up singly instead of in fours.†

The additions being complete, the compound shaft harness will enable the weaver (1) to raise the binder threads all together or in separate rows by the shafts as freely as before, and also to use the main figure harness simple by itself, also as before ; so that any web that has already been made can be

* It is only possible in such a book as the present to show the general principles on which these complicated machines were made. In practice they were subject to innumerable modifications.

† This is not an arbitrary arrangement. The harnesses in both divisions may be exactly alike. In fact, any combination may be planned on the same principle and have special advantages.

Description of the Compound Monture repeated. (2) To raise any single thread of the binder or a combination of them, at any place, to make ties for a brocaded figure. - (3) To utilise the binder warp in order to make small designs, diapers, checkers, spots, or what not, as a background to the main design.* (4) To lift any portion of the binder out of the way of any other weaving that may be going on. (5) To weave damask-like figures in the background of the brocade, as was so often done with fine effect in the French and Italian webs.

Examples of Compound Monture Weaving It is difficult to select a few examples of tissues woven on compound montures out of the great number available, any one of which might be chosen on account of some special point of interest in its technique. The space, however, now at our disposal precludes the extended examination which this part of the subject deserves. Three examples must suffice; these have been chosen as diverse as possible, and will give some idea of the capacity of the drawloom in its highest state of development. Ample opportunity for further study of tissue-weaving is afforded by the fine collection of drawloom woven fabrics in the Victoria and Albert Museum, which is particularly rich in seventeenth- and eighteenth-century examples, French, Italian, and English. There is also in the print room of the same museum a wonderful and most instructive collection of designs for this class of weaving, dating from the beginning of the eighteenth century. The value of these drawings is much enhanced by

* This kind of background effect is particularly characteristic of English eighteenth-century weaving.



Plate XVII.—Brocade, probably Old English. The lower portion of the photograph shows the method of brocading with small shuttles at the back.

See page 311.

Author's Collection.

the designers' and weavers' notes which are written on their margins.

The first example for present examination is a pure brocade, probably old English (plate xvii). The cream-coloured ground is a rich plain tabby, very finely and closely woven, there being eighty shoots of weft to an inch. Two shoots of weft are laid between each line of the brocading, and there are two shoots of brocading to each line of the draught on ruled paper. The quaint floral and landscape design occupies the whole twenty-one inches of the width of the web, and is draughted for six hundred cords. The most convenient ruled paper for this size of design, would be divided into twelve lateral spaces in each of the fifty large squares on to which the design had been first sketched, and as each line is repeated, as we have seen, in the weaving, the proportional number of vertical spaces would be eight. This would therefore be said to be drawn on 12 x 8 ruled paper. The colours are so arranged, that, although there are a great variety of them, as they are brocaded in, there is no necessity for more than four tie-ups for each line of the design on the simple, or for four cards if the lifting were done by a Jacquard machine. For the latter, however, each card would have to be duplicated, as when more than one card is used for each line the second and third, or whatever number are required, must follow in unbroken sequence. The Jacquard machine cannot be turned back to the first card of the line without great trouble; accordingly a second sequence identical with the first has to be laced in the endless band of cards. This repetition, however, could be done quite easily on

Examples of
Compound
Monture
Weaving
Old English
Brocade

Old English the draw-loom providing the cords were drawn
Brocade by a human drawboy.*

The tie-up for this design would be very simple, as only a few cords here and there would have to be drawn at each line.

All the colours would have to be painted in on the draught quite distinctly, in order that the tie-up might be *read in* correctly by the weaver, and also that it should be a clear guide to him in the brocading. Two draughts would have to be made, one painted in, exactly as the design is to appear when woven, only without the binders; the other having all the shapes exactly copied, but without colour, and the binder ties indicated. In the colour draught, the colours to rise in each tie-up would have to be indicated by letters or numerals, 1, 2, 3, or 4. The colour draught would be for the back or main division of the monture, and the binder draught, for the front division. The effect on the loom of this arrangement, when the tie-up was made, would be that the back division of the simple would draw up the figure in large on the main warp without any ties (see effect of shaft harness, p. 287, fig. 117, no. 1). Now if the cords of the front harness be drawn simultaneously with those of the back, all the threads of the second warp will be lifted from the figure, except those required for binders. As there

* With regard to two or more colours being tied up in one line for brocading, it should be pointed out, that, as each colour is put in with a small shuttle separately, it follows, that if sufficient space is left between the parts lifted, any reasonable number of colours can be brocaded in one line. With a skilful weaver a very little space between the colours is sufficient.




Fig. 125.—French Brocade Silk Tissue, Eighteenth Century.

Old English are six shafts for the binder warp, the twill tie
Brocade may be either a three- or six-shaft twill. The
one used in the example (plate xvii) is on six
shafts.

The weaving would proceed as follows: Shoots 1 and 2 will be a tabby of the ground and binder together. The brocading shed will next be made by drawing the first tie-up of both the simples together. The brocading wefts in the first shed being laid in the places indicated in the draught, the second tie-ups will open the second brocading shed; this also being laid, the third tie-ups will open the final shed, for the first line of the design. The third and fourth tabby shoots follow next in order, and the same sheds are to be repeated for the brocading. When the two lines of brocading are thus woven, with two tabby shoots between them, one line of the design, as draughted, will have been woven. The weaving of brocades requires great care and skill, especially when, as in this example, several colours are put in at one drawing of the simple. The weaver has to follow the coloured draught very attentively until he has learned the position and entry of the different colours. Needless to say, brocading must be done face downwards, and the small brocading shuttles are left standing on the back of the web in exact order, like a fleet of little boats, and pass through the shed in regular succession. The lower portion of plate xvii shows the back of the old English brocaded silk, and will greatly assist in the explanation.

The dainty and characteristic eighteenth-century brocaded and striped silk of French weaving (fig. 125) could be woven on two differently




Plate XVIII.—Figured Velvet. The ornament is composed of cut and terry pile. This specimen is beautifully designed and perfectly woven.

See page 321. Victoria and Albert Museum, South Kensington.

mounted looms: (1) On a loom arranged for damask-weaving, with two separate harnesses in front, one to work tabby and the other to weave a satin, with two spaced warps on separate rollers, and with the harnesses also spaced, and *both* entered in the monture. (2) On a divided shaft harness, with one simple and with the warps spaced and arranged on two rollers. If made in the latter way the weaving would be much simpler, and there would be a great deal less strain on the silk, which is always an advantage. The design must first be briefly described, and then the method of preparing the monture for it. The design is shown squared out in preparation for the draughting. The broad stripes on which the large bouquets are placed are of rich satin of a pale blue colour. The narrower stripes, one of which, in the centre, has a wavy ribbon with a garland of small flowers adorning it, and the other, the half of which is seen at each edge of the drawing, are both white tabby-woven silk. The two narrow stripes near each edge are of the same satin as the wide one, and only differ from it in their colour, which is pink, with white edges. These are arranged in the warping. The fine stripes on which the large bouquets are placed are floating white silk weft, as are also the edges of the wavy ribbon and the fine stripes of various lengths which are placed at its side. The bouquets, sprays, and garland are all brocaded in exquisitely delicate tints of pink, creamy yellow, and green. It is not necessary to give a specification of the monture for reproducing this example, but only to indicate broadly the method of its building. The comber-board would be in two divisions, and as there

Eighteenth-
century
French
Striped
Brocade

Eighteenth-
century
French
Striped
Brocade

would be an equal number of shafts for both divisions the same number of rows of holes would require piercing in the board. In the back division holes would only be pierced in the spaces required for the satin stripes, and in the front division holes would be made for the tabby stripe spaces. In this web there would be no binders for the brocading, as the smallness of the spaces brocaded renders them unnecessary. The cords from both divisions of the shaft harness could be brought into one simple, as the figures are all raised simultaneously. The first tie-up of the simple would be of the fine stripes in the centre of the broad satin one, and the fine vertical lines and edges of the wavy ribbon. The second, third, and fourth tie-ups would be for the three sheds of the brocading.

The order of the sheds, for the shoots of white silk, in weaving would be as follows : (1) The tabby and satin groundwork on shafts alone of both warps together ; (2) the first tie-up on the simple cords would be drawn and the second shoot of tabby and satin groundworks lifted. When these shoots had been made, the first tie-up of the brocading figure would be lifted by the simple cords and the brocading done ; then the second and third tie-ups and their brocading, in succession. This would finish one line of the design. At the fourth pair of ground shoots with the white weft, the one round of ties of the eight-shaft satin would be complete, and the fifth pair would begin with the first tabby and first satin shafts again together.

The third and last example to be examined is the fine late seventeenth century French brocade which is reproduced in colours as the frontispiece

of this Part of the book. It is a superb piece of weaving, and a fine specimen of appropriate and economical design. The fragment from which the photograph is taken is only fifteen inches high and ten and a half inches wide, yet this gives nearly two repeats of a fairly bold design. The figure is turned over in repeating vertically, so that the real design is barely eight inches, and yet on looking at a whole piece of the brocade we should have "no wearisome sense of repetition," which is a quality in design that William Morris commended so highly when describing the early Sicilian webs.* Then again the design is so perfectly adapted to the method of its production that no artist who was unacquainted with the technique of weaving could invent a pattern so suitable for working out in the loom.

French Late
Seventeenth
Century
Brocaded
Tissue

The ground of the web is a lilac silk tabby, very rich and warped with double threads. The graceful ornament, consisting of a twisted ribbon and conventional flowers and foliage, is all brocaded in, by means of a multitude of small shuttles. The silks used for the wefts are of exquisitely delicate-coloured dyes, and are varied in a most artistic way in the repeats. The dark green and red wefts are fine chenille threads, which give a velvet-like texture to the portion of the work where they are used. A part of the floral ornament is brocaded with a curiously twisted silk thread, which gives a metallic

* A fine description of the early Sicilian damasks may be found in a lecture on textile fabrics by the late William Morris. The report of the lecture is in the Art Library, South Kensington.

French Late appearance wherever it is used.* The intricate
Seventeenth brocading is not tied down with a binder, but is left
Century loose or floating, the designer having so arranged the
Brocaded draught that none of the loops are inconveniently
Tissue long.

It was not only on account of its exceeding beauty that this example was chosen for this particular illustration, but on account of the peculiarity of the embellishment of the background of the figure. This background pattern, is put in by means of the second or front division of the monture working on the second warp, which is used for this purpose instead of as a binder. This ornament is woven in the tobine manner described at the end of Chapter XIV. As will be gathered from that description, tobine effects are generally confined to narrow stripes, vertical or lateral, as small squares and oblongs, but here we have a kind of key pattern and spaces between it of plain tabby, and it does not interfere with the brocading, although it is in a line with it. All this shows that some means has been devised for raising and depressing the tobine warp at any place required by the design and between any one of the tabby shoots. In order to effect this, the front division of the monture is fitted up with ordinary leashes without shafts. The extra warp, of the same colour as the main one, is about one-fourth of its richness, and the simple cords draw from four to six leashes with every cord. The shapes of the brocading figure have to be tied up on

* The French weavers were very ingenious in twisting threads of silk and metal, and many beautiful effects in their webs are due to this special weaving.

the front simple and drawn simultaneously with those of the back. The tobine pattern on the ground is worked in by the tie-up of the front simple while the ground itself is being woven. This tie-up of the front division of the harness would all have to be worked out on a separate draught from that of the brocading.*

French Late
Seventeenth
Century
Brocaded
Tissue

* These tobine effects for groundwork patterns became very common and characteristic of English Spitalfields weaving in the eighteenth century. In French work they occur chiefly in stripes.

CHAPTER XX

FIGURED-VELVET WEAVING

Pile and Terry Figured Velvet—The Draught—
The Monture—The Preparation of the Loom—
The Bobbin Frame—Italian and Spanish Velvets.

Figured-
velvet
Weaving

THE weaving of plain velvet has been fully described in Chapter XIV. It will therefore require but few words to explain the method of making figured velvet, which, as far as the actual weaving goes, is done in precisely the same manner. In one respect the weaving of figured velvet is not so difficult as when the pile is plain, as small defects in the cutting out of the rods are not so apparent.

The design for figured velvet is draughted in exactly the same way as designs for damask weaving. Each square of the ruled paper represents a group of from four to eight threads of the pile. When both cut, and terry, velvet are in one design they are treated as two colours, and require two successive tie-ups on the simple.

The leashes of the monture for velvet weaving are more heavily weighted than for damask or tissue weaving. They are also mounted on shafts as in the tissue shaft harness. When both terry and cut pile are being woven the grooved rod is first placed in its shed, and the terry one next to it, before the

intervening shoots of ground are made. This is the only difference in the weaving process. The shafts raise and depress the pile altogether between the shoots, and the cords of the simple raise the pile as required for the design. Plate XVIII is taken from a very fine example of cut and terry figured velvet in the collection at the Victoria and Albert Museum.

Figured-
velvet
Weaving

Although the actual weaving is so similar there is a great difference in the preparation of the loom for figured velvet. Each separate group of threads, lifted for the design by the cords of the simple, has to have a small warp of its own, individually weighted with a tiny piece of lead wire. Eight hundred or a thousand of these, mounted in a frame at the back of the loom, is no uncommon number. It will be remembered that the take-up of the pile warp is so great that the warp has to be at least six times the length of the ground warp. It will therefore be readily seen, that parts of the design, where more or less pile is raised would take up different lengths of warp. Some of the bobbins are found to run out sooner than others, and when they do so they are immediately replaced and the new threads of silk joined to the original ones. In this way the pile warp is kept even, whatever the nature of the design may be.

The Pile-
bobbin
Frame

Figured-velvet weaving seems to have reached its highest perfection in Italy and Spain during the sixteenth century. The webs then produced have never been surpassed, or even equalled, although if good silk, of fine colour were used, in a properly set up hand-loom, there is no reason why velvet, the most sumptuous of all textiles, should not be made as well as ever.

Sixteenth-
century
Velvet

CONCLUDING NOTE

Concluding Note

It may be surprising, and perhaps somewhat disappointing, to some readers to find that this description of the methods of weaving and weaving appliances, comes to an end at this point. We have traced the history and development of the craft, from its earliest beginning, up to the time when the Jacquard machine was introduced and began to supersede the traditional draw-loom for pattern-weaving. This ending, although perhaps somewhat abrupt, is not unintentional, for it was just at that time that weaving, to a great extent, ceased to be an artistic craft. It was then that the loom ceased to be a tool, more or less complicated, which the weaver himself could keep in order and cunningly adjust, alter, and adapt to any particular work he might have in hand.

With the exception of the fly-shuttle, chiefly useful for weaving wide webs, the Jack-in-the-box, and the split or shaft harness, descriptions of which have been given, no real improvement has been made in weaving or weaving appliances since the middle of the eighteenth century.

As regards the Jacquard machine, the chief advantage (?) it offers is the facility with which designs can be changed in the loom, the endless

band of cards taking the place of the weaver's tie-up. This facility for change only resulted in the multiplication of patterns ; patterns, for the most part inferior to the traditional ones already in use. The Jacquard machine is also responsible, to a great extent, for the separation of the art of designing from the craft of weaving.

Concluding
Note

The speed of weaving has been by means of the power-loom, of course, vastly increased, but although this is in some respects a commercial advantage, the quality of the weaving is far below that of the earlier times, and the ruthless, rigidly perfect mechanism of the machine loom has had a disastrous effect on the weaver as a craftsman.

There can be no question that the best weaving was done before these innovations of the engineer and mechanic were made. It would therefore seem, that the right road to improvement in weaving, as in all the crafts, can only be found by those who are willing to return to the traditional methods and simpler ideals of the earlier masters of craftsmanship.

GLOSSARY*

Glossary

Batten, the frame of a reed.

Beam, a roller.

Beaming, winding on a warp.

Beaming drum, the essential part of beaming machine.

Beaming posts, supports for a beam.

Binder, the tie for floating weft.

Binder harness, headles for lifting binders.

Bobbin, a reel.

Bobbin-carrier, a reel-holder for warping.

Bobbin frame, part of a warping mill.

Box batten, batten with fly-shuttle boxes.

Breast roll, front beam of a loom.

Brocade, a brocaded web ; originally, silk wefted with gold or silver thread.

Brocading, weaving detached ornaments in a web.

Brocatelle, tissue with satin ties in figure.

Broché, web to imitate brocading.

Cane, a new warp.

Cane roll or roller, the back roller of a loom.

Cane sticks, sticks for fastening the warp in beam.

* This glossary does not pretend to comprise all the technical terms used in weaving. These are of infinite variety, and often have totally different meanings in districts separated but a very short distance one from another.

Glossary

Carding, preparing fibre for spinning.

Cards or *cardings*, fibre prepared for spinning.

Cloth beam, the breast roller.

Comber-board, a board perforated to hold the leashes of a monture.

Comber repeat, repetition of a design which does not turn over.

Comber slip, a portion of the comber-board.

Compound harness, two or more harnesses working together.

Compound monture, monture with two or more sets of leashes.

Cords, the simple on which the pattern is tied up in a draw-loom.

Counter-march, a short lower lever in a loom.

Couper, the top levers of a loom.

Cross, the crossing threads of a warp.

Cross, porrey, the cross retained while weaving.

Cross, portee, the cross at the finishing end of a warp.

Cross sticks, smooth rods for preserving the cross.

Damask, a system of weaving introduced from Damascus.

Dent, one space in a reed.

Design, a pattern ; one square of ruled paper.

Diaper, a system of weaving small patterns.

Distaff, appliance used in spinning.

Doubling, winding two or more threads together.

Draught, drawing on ruled paper.

Drawboy, a boy employed to draw the cords of a simple.

Drawboy's fork, implement for drawing the cords in a draw-loom.

Drawboy machine, machine for drawboy's work.

Entering, threading warp in leashes or reed.

Entering hook, thin hook for drawing thread through mails.

Eye, centre loop of a leash.

Fancy web, see *Tissue*.

Figured velvet, velvet with pattern.

Figure harness, the monture or pattern headles.

Float, a loop of weft passing over two or more threads.

Fly-shuttle, a shuttle driven by a picking stick.

Friction brake, appliance for regulating weight.

Gatherer, a part of the heck-block.

Gating, adjusting a loom.

Ground, the plain part of a web.

Ground harness, headles which form the ground of a web.

Guiding cords, supports for the pattern loops on the simple.

Hand-shuttle, a shuttle for throwing by hand.

Hand-stick, a short stick on which warps are wound.

Harness, a collection of headles.

Headle or *heddle*, a collection of leashes.

Headle frame, a frame for knitting headles upon.

Headle gauge, a tool for making leashes.

Inlaying, see *Brocading*.

Jack-in-the-box, invention which reduces the number of treadles required in a loom.

Jacquard machine, a machine perfected by M. Jacquard to supersede the drawboy in pattern-weaving.

Lam, see *Headle*.

Leaf, see *Headle*.

Lease, see *Cross*.

Leashes, loops of a headle.

Lingo, the weight of a leash.

Long march, the long levers below a loom.

Glossary *Loom*, any arrangement for supporting a warp and keeping it in order for weaving.

Mail, the glass or metal eye of a leash.

Monture, the mounting of a loom for pattern-weaving.

Necking cords, cords joining pulley cords and leashes in a monture.

Pecker, part of the drawboy machine.

Pickers, tweezers.

Picking-stick, the handle of the fly-shuttle motion.

Pile, the cut portion of a velvet.

Plan and tie-up, a sketch showing entry of harness and tie-up of treadles.

Plug, a tube on which weft is wound for the fly-shuttle.

Point repeat, a design repeating in opposite directions.

Pile, the pile warp of velvet.

Porrey, the warp between heddles and cross-rods.

Portee, a collection of threads warped together.

Pulley, a grooved wheel.

Pulley-box, the upper part of a draw-loom.

Pulley cords, cords in a pulley-box.

Quill, a tube on which weft is wound for a hand-shuttle.

Race, the beading on the race-block of hand-batten.

Race-block, the lower part of a batten.

Race-board, that on which the shuttle runs.

Raddle, implement for evenly spreading warp.

Ratchet and wheel, a toothed wheel and catch.

Reed, a comb-like implement for keeping warps even and beating weft together.

Reed hook, hook for entering reed.

Retting, steeping flax in water.

Reverse satin, a satin with weft predominating.

Rising shed, a shed in which part of the warp rises, the rest being stationary.

Rocking shaft, part of the drawboy machine.

Ruled paper, paper for draughting.

Satin, a web with infrequent intersections.

Satinette, a short tied satin.

Selvage, the edge of a web.

Selvage bobbin, reel for mounting separate selvages in a loom.

Shaft, a flat lath.

Shed, the opening in the warp for the shuttle.

Shed-stick, a flat stick for opening the warp.

Shedding motion, a contrivance for opening the warp.

Shoot or shute, weft ; also throwing the shuttle.

Short march, see *Counter-march*.

Shuttle, a tool for carrying weft.

Shuttle-box, part of a fly-shuttle batten.

Simple, the pattern cords of a draw-loom.

Sinking shed, shed made by drawing threads down.

Skein, a loosely wound length of thread.

Skutching, cleaning retted flax.

Slot, an elongated perforation.

Spacing, arranging threads or leashes in groups.

Spinning, twisting fibre to make thread.

Spinster, a female spinner.

Tabby or taffeta, plain weaving.

Tail cords, the upper cords of a draw-loom.

Take-up, the gradual winding of cloth on to breast roller.

Tapestry, tabby weaving, in mosaic, with loose weft.

Tartan, a web striped in warp and weft.

Temple, implement for keeping out the edges of a web.

Terry velvet, see *Velvet*.

- Glossary *Thread monture*, a monture with single threads in the mails.
- Tie*, a binder on loose weft.
- Tie up*, connecting parts of a loom together for forming patterns automatically.
- Tissue*, a web having one or more binder warps.
- Tobine*, ornaments formed by one or more headles rising and sinking together.
- Trevette*, a knife for cutting velvet pile.
- Tumbler*, a top lever of a loom.
- Turning on*, beaming.
- Twill*, a web with a diagonal tie.
-
- Union damask*, damask woven of linen and wool.
-
- Vateau*, implement for spreading the warp on cane roller.
- Velvet, cut*, a woven fabric with cut pile.
- Velvet, figured*, see *Figured velvet*.
- Velvet knife*, see *Trevette*.
- Velvet rod*, a grooved rod for the pile.
- Velvet, terry*, velvet with uncut pile.
-
- Warp*, longitudinal threads of a web.
- Warping*, preparing a warp.
- Warping board*, for making small warps.
- Warping mill*, for warping large warps.
- Web*, a piece of finished weaving.
- Weft*, the crossing thread of a warp.
- Whorl*, a spindle weight.
- Woof*, weft.
-
- Yarn*, thread of any kind.

INDEX

AMENHEF II., 133
 Automatic pattern-weaving, 138,
 139, 140
 Automatic shedding motion, 86

 BATTEN and reed, origin of, 95
 Batten, fixing in loom, 99
 Batten, fly-shuttle or box, 117-
 119
 Batten, hand-, 97
 Batten in position, 114
 Beam, or roller 60
 Beaming, 60, 61, &c.
 Beaming posts, how fitted up, 77
 Beni Hasan, wall paintings of
 looms at, 19
 Bethnal Green, James Gough of,
 276
 Bethnal Green weavers, 271
 Binders for brocading, 150, 310
 Board for weaving, the simplest
 loom, 23, 24, 25, 26
 Bobbin-carrier, description, 34, 35,
 36
 Bobbin frame, 47, 48, 54
 Borders of needlework, 132
 Box or fly-shuttle batten, 117,
 118, 119
 Boxwood shuttles, 112
 Breast roll or roller, 63, 90
 British Museum, collection of
 textiles, 133
 Brocade, French, seventeenth
 century, 315

Brocading, 148-152
 Brocading in open and close warps,
 149
 Brocading on compound monture,
 310
 Brocading on old English loom,
 152
 Brocading similar to embroidery,
 159
 Brocading with cut threads, 148
 Brocading with extra headle, 153
 Brocatelle, draughting for, 286,
 287, 288
 Brocatelle, methods of weaving,
 285, 289
 Brocatelle, satin of, 286
 Brocatelles, ground tied up or
 cut in, 286
 Broché effects in large and small
 patterns, 293, 294, 295, 302
 Broken twill, or satinette, 168

 CAIRO Museum, Egyptian tapestry,
 133
 Calculating number of threads of
 warp, 54
 Camber, or comber, repeats, 256
 Cane reeds, 97
 Cane roll or roller, 63, 67, 88, 90
 Cane sticks, 63, 66
 Cap of batten, 99, 104
 Carders and carding, 10
 Cards for turning on, 71
 Cards of Jacquard machine, 270

Index

Index

Carrier for bobbin, 34, 35, 36, 37
 Cashmere shawl weaving, 157
 Catching the shuttle, its importance, 126, 127
 Characteristics of ancient weaving, 133
 Chenille, weft, 316
 Chinese and pattern-weaving, 131
 Chinese origin of satins, 168
 Chinese silk-weaving, 87
 Chinese weaving inventions, 86
 Circe's loom, 24
 Classic tapestry, 136
 Coarse warps for pattern webs, 265
 Colour effect of satins, 188
 Colours distinct in double-cloth weaving, 188
 Comb, or reed, 95
 Comber-board, the, 253
 Comber, or camber, design repeats, 256
 Comber slips, 257, 308
 Compound monture weaving, 310, 311,
 Coptic webs and borders, 137
 Cords, the term used in describing width of design, 261
 Cotton, its introduction, use, and adulteration, 6
 Cotton, preparation, 9
 Counting threads of a warp, 37
 Course of threads in the harness, 103
 Cross, or lease, 88
 Cross-pieces of loom frame, 90
 Cross-roads, 72, 88
 Cut threads, brocading with, 148

Dacca muslin, 12
 Damasks, 180
 Damasks, large designs, 274
 Damasks, linen, 182
 Damask of Louis XIII. period, 274

Damask-weaving, 156, 210, 211, 212, 274
 Damask-weaving, entering for, 211
 Damask-weaving, shed for, 214, 216
 Darning patterns in webs, 132
 Decoration of ancient webs, 132
 Dents of reed, 97, 103
 Designs, ancient, for weaving, 132
 Designs, regulation of length, 282
 Designing for brocading, 153
 Details of turning on, 68-71
 Diaper-weaving, 199
 Diaper-weaving, examples of, 201, 202
 Diaper-weaving, place of origin, 199
 Dissecting designs, 174
 Distaff, 12, 13, 14, 15
 Distribution of warp in raddle, 66
 Divided monture, advantages of, 307
 Domestic looms, warps suitable for, 67
 Double-cloth pattern-weaving, number of headles required, 205
 Double-cloth tabby weaving, 189
 Double-cloth weaving, 179, &c.
 Double-harness pattern-weaving, 199
 Double-knotted leash eyes, 110
 Double-woven tissues, 299
 Doubling stand, 123
 Draught for thread monture weaving, 273
 Draught of Spitalfields tissue, 291
 Draught, the, its preparation, 265
 Draughting, 283
 Draughting enterings of harness, 163
 Draughting for figured velvet, 320

- Draughting for thread monture, 268
 Draughting, how counted, 261
 Draughting on ruled paper, 161, 162, 163
 Drawboy's fork, 263
 Drawboy's work, 262
 Drawboy machine, 230-248
 Drawboy machine, advantages of, 238
 Drawboy machine, drawing cords of, 244
 Drawboy machine, Spitalfields weavers disappointed with, 238
 Drawboy machine, suitable design for its use, 245
 Drawboy machine, working of, 244
 Drawloom harness or monture, 253
 Drawloom, the, 42, 252
 Drawloom, the, its importance in textile work, 252, 306
 Drawloom methods used in power-loom weaving, 306
 Drawloom, part of, superseded by Jacquard machine, 254
 Drawloom, variety of webs woven on, 289
 Drawing threads for darning in, 133
 Drum for beaming or turning on, 73, &c.
 Dunfermline, table-cloth woven at, its fineness, 256
 EARLY Christian weaving, 133
 East African weaving, 142, 143
 Eastern spinners, 12
 Egyptian looms, 19, 20, 21
 Egyptian webs, 131
 Egypto-Roman webs, 137
 Embroidery, 132
 English loom, old, described, 88
 Enterer, the, 103
 Enterer's assistant, 102
 Entering hooks, 102
 Entering of harness, usual method, 102, 103, 163, 164
 Entering the reed, 97, 103
 Entering the warp in the heck, 55
 Entering warps in various orders, 160
 Essential part of a loom, 24
 Euripedes, reference to brocading, 159
 Extended twills, 169
 Eyes of brocading leashes, 155
 Eyes of harness, 103
 FIGURE harness, the, 206
 Figured-velvet grounds, 321
 Figured-velvet weaving, 320
 Finding broken threads on the warping mill, 58
 Fine linen of Egypt, 85
 Fineness of spun thread, 12
 Finishing off a warp on the mill, 57
 First attempts at ornament in Egypt, 132
 First thread of warp, 103
 Fitting the friction brake, 105
 Fittings of heck-block, 45, 46, 47, 50, 52
 Fixing cross-roads for entering, 100
 Fixing the headles for entering, 100
 Flax, its use and preparation, 6
 Flax, retting, 7
 Fly-shuttle and fittings, 114, 115, 116
 Fly-shuttle plugs, 117
 Fork of drawboy, 263
 Frame for bobbins, 47, 48
 Frame for making headles, 109
 French eighteenth-century weaving, 313, 314

Index

French eighteenth-century web,
description of, 315, 316
Friction brakes for beaming drum,
74
Friction brakes for cane roller, 90

GATHERER for heck-block, the, 52
Gating the loom, 104
Greek looms, 20, 21
Greek spinster, 12
Grooves in the batten, 104
Ground harness, entering of warp,
212
Ground harness, long eyes, 212
Ground patterns, 167, 168
Guiding cords, 260

HAND-SHUTTLE, the, 112
Hand-shuttle and fittings, 113
Hand-spinning, 12
Handstick for taking off warps,
38, 64

Harness, the, its proper place in
the loom, 105
Harness, compound, 304
Harness, ground, 214
Harness of loom, 99, 102
Harnesses, effect of two, 213
Harnesses for satin, 182
Headle frame, 109
Headle, or heddle, the, 92
Headle-rod, the, 85
Headle weaving, its limitations,
251

Headles, spaced, 247
Headles, their position in the
loom, 99

Heck, the, 50
Heck-block, the, 45, 46, 47, 50
Heck-block regulator, 52
Herodotus' mention of weaving,
22

Homer's reference to variegated
webs, 146

Homespun cloth designs, 141
Hooks for entering, 102
Horizontal looms, 86
Horizontal position of the warp,
its advantages, 92, 111

INDIAN and English looms alike in
two points, 92
Indian brocading, 148
Indian cotton weavers, 141
Indian design, plan and tie-up,
204
Indian double-cloth design, 203
Indian, English, and French looms
compared, 88
Indian looms, their antiquity,
87
Indian muslins, 149
Inlay, 148
Italian damask, traditional design,
266

JACK-IN-THE-BOX, the, 230-238
Jack-in-the-box, tie-up to, 236
Jacquard cards, 270
Jacquard machine, 229, 230, 276
Jacquard machine, effect of, 3
Jacquard machine for commercial
weaving, 230
Jacquard machine, introduction
of, 2
Jacquard machine, results of its
invention, 252
Jennings' shedding motion, 230
Jennings, Theodore, 230
Joining in a new warp, 102

KEEPING account of the warp on
mill, 58
Knife for velvet-weaving, 224,
225
Knitting spaced leashes, 109

LAKE-DWELLERS, spinning and weaving, 6
 Lam, 93
 Laying the weft, 126
 Leaf, 93
 Lease, or cross, 25, 26, 32, 88
 Leash, 92
 Leash eyes for silk-weaving, 110
 Leash making, 106
 Leashes, long-eyed, their use, 155, 270
 Leashes of monture, 254
 Length of designs for simple looms, how limited, 174
 Linen and fine wool broché, 302
 Linen, damasks, 182
 Linen thread, preparation of, 7, 8, 9
 Lingoes, 254
 Long eyes in leashes, 155
 Loom, entering warp of, 100
 Loom frame, strength a necessity, 88
 Loom posts, 67
 Loom, the essential part, 24
 Looms, ancient pictures of, 18, 19, 20, 21, 22
 Looms and appliances in art, 12, 13
 Looms, Indian, antiquity of, 87
 Looms, simplest, 23, 24, 25, 26
 Loop for turning cane roller, 67
 Loop, the weaver's most useful, 38-41
 Lute-string, or lustring, grounds, 294

 MACHINE-MADE reeds, 97
 Mails, or eyes, 51, 254
 Marches, counter-, 214
 Marches, long, 198
 Materials for brocading, 149
 Measuring lengths of warp on the mill, 49

Mechanical pattern-weaving unknown to ancients, 132
 Mediæval tapestry, 137
 Mending broken threads on the warping mill, 58, 59
 Metal reeds, 97
 Monture, the, 253
 Monture building, 254
 Monture, divided, or compound, advantages of, 306, 307, 310, 311, 312
 Monture for coarse threads, specification of, 296, 297, 298
 Monture, necking cords of, 259
 Monture, the leashes of, 254
 Monture, the shaft, 276
 Morris, William, 317
 Muslin, Dacca, 12

NECKING cords of monture, 259
 Needlework borders, 132
 Nippers and pickers, 125

OLD English brocade, draughting for, 311
 Old English loom described, 88
 Opening in warp, or shed, 81
 Order of working treadles, 165
 Origin of the loom, 18
 Ornament, brocaded, 149

PAPER quills, 113
 Pattern loom, the most perfect mechanical, 264
 Pattern weaving, 131
 Pattern weaving, complex, 249, 251
 Pattern weaving, delicate silk, 283
 Pegs of warping mill, their relative positions, 49
 Penelope's loom, 23
 Perforating the comber-board, 277

Index

Persian decorations, 141
 Picker and picking stick, 118, 119
 Pictures of ancient looms, 18, 19, 20, 21, 22, 23, 24
 Pile, or pole, of velvet, 223
 Plaids, Scotch, 146
 Plain cloth, its construction, 4
 Plain cloth weaving, 82
 Plan and tie-up, 165
 Plugs for fly shuttles, 117
 Point design repeats, 174, 198, 256
 Portee and portee cross, 37
 Portee cross on warping mill, 57
 Portee cross secured, 64
 Porree cross, 71
 Ptolemaic period, 133
 Puiley-box, the, 253, 309
 Pulley cords, 253

QUILL, the, on which the weft is wound, 112, 113
 Quill-holder, the, 112
 Quill- or plug-winder, 124

RACE-BLOCK, 97, 99
 Raddle, 61
 Raddle, length of, 66
 Raddle, selection of, 63
 Raddle stands, 64
 Ratchet and wheel of breast roller, 90
 Raw materials used in weaving, 5, 18
 Reed, or comb, 95
 Reed and batten, origin of, 95
 Reed cap, 104
 Reed dents, 97, 103
 Reed hook, 102
 Reed laths, 97
 Reed making, 96
 Reed making by machinery, 97
 Reeds, cane and metal, 97

Regulation of the heck-block, 52
 Repeating patterns automatically, 140
 Repeats in loom unalterable, 261
 Retting flax, 7
 Reverse satin, 181
 Rocker of batten, 99
 Rococo silk broché dissected, 292
 Rods, cross-, 72, 88
 Roller, roll, or beam, 60
 Roller, breast, 63, 90
 Roller, cane, 63, 88, 90
 Roller, second, its position in loom, 219
 Roman looms, 21
 Roman period, 133
 Rubber, the, 125
 Ruled paper described, 161, 167
 Ruled-paper drawings, 182

SATIN, Chinese origin of, 168
 Satin, five-headle, 182
 Satin, its peculiarity, 180
 Satin not necessarily silk, 180
 Satin, reverse, 181
 Satin ties and the development of weaving, 175
 Satin woven face downward, 184
 Satins, colour effects of, 188
 Satins, varieties of, 182, 183, 184
 Selvages, good, 126, 127
 Selvages, separate, 186
 Selvages, separate, not necessary in tabby weaving, 185
 Selvages, their arrangement, 186, 187, 188
 Selvages, their importance, 127, 185
 Separate leashes, how made, 108
 Separate warping of binders, 285
 Shaft harness, invention of, 276
 Shaft-monture weaving, example of, 280, 281
 Shafts used in monture for figured-velvet weaving, 320

Shawl-weaving in Cashmere, 157
 Shears, 125
 Shed or opening in warp, 82
 Shed, a rising, 192, 193, 194
 Shed, a rising and sinking, 195, 196
 Shed for brocading, 154
 Shed making for damask webs, 213, 216
 Shed, patterns suitable for rising and sinking, 197, 198
 Shed, rising and sinking, with stationary bottom, 214
 Shed-stick, the, 82
 Shedding motions, 94, 164, 191
 Shedding motions, automatic, 229
 Shoot, also shute, woof, or weft, 4
 Shushan, the palace of, 141
 Shute, also shoot, woof, or weft, 4
 Shuttle-boxes, 118
 Shuttle, boxwood, 112
 Shuttle race, 99, 104
 Shuttle race of box batten, 118
 Sicilian damasks and tissues, 267, 316
 Side cords for entering loom, 100
 Silk damask weaving with two harnesses, 247
 Silk, preparation for weaving, 6-9
 Silk weaving, seventeenth, eighteenth, and nineteenth centuries, 43
 Simple or pattern cords, 260
 Simplest patterns, the, 139
 Single-harness patterns, 160
 Skein-winder, 121, 122
 Skutching or stripping flax, 8
 Slip-loops, how made, 106
 Spacing warp on cane roller, 69
 Spindle, 12, 13, 14, 15
 Spinners, Eastern, 12
 Spinning, primitive, 11, 12
 Spitalfields tissue, 290
 Spitalfields weaving, sample of fine, 271

Split harness, 276
 Split harness, section of, 278
 Split harness, shafts for, 279
 Split or shaft harness, the working of, 279
 Spreading warps on warping mill, 48
 Stretching the warp in the loom, 60
 Striped Indian warps, 141
 Striped warp designs, 142, 143, 144, 145
 Stripes of ornament on tabby grounds, 176
 Swords of batten, 99

TABBY and other grounds for designs, 270
 Tabby ties on two harnesses of different counts, 298
 Taborettes, 227
 Tail cords of drawloom, 260
 Take-up of the cloth, 128
 Taking off warps, 38
 Taking the cross on warping mill, 56
 Tapestry akin to embroidery, 138
 Tapestry, classic, 136
 Tapestry looms fitted with two ratchets and wheels, 91
 Tapestry, mediæval, 137
 Tapestry-weaving, 131
 Tartan designs, 146
 Temple, the, when necessary, 120
 Tension of warp, how adjusted, 92
 Tension of weft, 113
 Terry velvet, 226
 Textile decoration, 133
 Textiles in Victoria and Albert Museum, 310
 Textiles mentioned in ancient history and poetry, 137
 Textiles of Greece and Rome, 85
 Thothmes IV., 133

Index

Index

Thread monture, 264
 Thread monture for silk-weaving, 271
 Threading or entering the harness and reed, 103
 Throwing the shuttle, 113, 114
 Tie-up of pattern, 139
 Tie-up of tabby ornamented webs, 177
 Tie-up of treadles to headles, 94
 Tissues, numerous wefts and shuttles used in, 292
 Tissues of linen, cotton, wool, and spun silk, 296
 Tissues of seventeenth and eighteenth centuries, 277
 Tobine effects, 228, 318, 319
 Treadles connected with headles of harness, 105
 Treadles of loom, 93
 Treadles, working of, for twill, ground, 213
 Trevette for velvet weaving, 224, 225
 Turning on, process of, 60, 68-71
 Twills, extended, 169
 Twills, right- and left-handed, 167
 Two-harness method, fine results of, 207
 Tying up headles and treadles, 165

 VARIEGATED webs of Sidon, 146
 Vase paintings of looms, 23
 Vateau, 61
 Velvet, ancient, its superiority, 227
 Velvet, pile bobbins for, 321
 Velvet, breast roller for, 220
 Velvet, figured warping for, 321
 Velvet ground, twills, &c., 219
 Velvet, ground warp for, 223
 Velvet pile or pole, its position in loom, 219, 220
 Velvet power-loom, 227
 Velvet rod, 224

Velvet, small-pattern, 227
 Velvet, take-up of pile warp, 219
 Velvet warps, their proportion, 223
 Velvet weaving, actual process, 224
 Velvet weaving, figured, cut, and terry, 320
 Velvet weaving, plain, 219
 Velvet weaving, speed of, 222
 Velvet weaving, weighting leashes for, 320
 Victoria and Albert Museum collection of textiles, 133
 Victoria and Albert Museum, examples of tissues, 310

WARP, 88
 Warp and weft, their proportions, 5
 Warp, counting threads of, 37
 Warp, its preparation, 26, 81
 Warp, joining in a new, 102
 Warp, opening in, 81
 Warp patterns, 140
 Warp, why so called, 4
 Warping, ancient and simple method, 27-32
 Warping board, 27-32
 Warping mill, Chapter IV., 42, 58
 Watson, Dr. J. F., on Indian brocading, 148
 Weaver's beam, 60
 Weaver's ingenuity, 230
 Weavers, old, their capacity, 231
 Weaving a most complicated art, 82
 Weaving, ancient designs for, 132, 133
 Weaving, ancient method of wide, 120
 Weaving, board for, 23-26, 150
 Weaving, damask-, 156, 210, 211, 212, 213, 274
 Weaving, development of, 2

Weaving face downwards, 304
Weaving from two warps, 217
Weaving, importance of, 1
Weaving mentioned by Herodotus,
22
Weaving, modern developments,
217
Weaving on hand-loom, 125, 126,
127
Weaving, primitive, 18, 85
Weaving with fly-shuttle, 127
Weaving wool hangings, 300, 301
Weaving, universal, 3
Webs of Egypt, 131
Webs of Sicily, 317
Weft, also woof, shute, or shoot, 4
Weft effect designs, 145

Weft effects, their advantage,
296
Weft stripes, 132
Wefting, 82
Wefting of ancient textiles, 134
Weight box of loom, 91
Weighting shuttles, 118
Winding quills and plugs, 128
Woof, also called weft and shoot,
or shute, 4
Wool for weaving, preparation of,
6, 9
Wool hanging for heavy church
curtain, 300
Wool hangings, grounds of, 301
Workshop for beaming, 76, 78,
79

Index

ADDENDA

NOTE TO P.99.—At end of 10th line it should be Addenda added that—The batten requires to be very exactly made, and the reed especially must be carefully fitted in such a manner that the swords of the batten and the front of the reed are quite flush.

NOTE TO P.105.—After the word “batten” in the 5th line, the method of fixing the warp to the front roller should have been described thus—The front roller must now be rested on its brackets at exactly the same height as the back roller, and a thin iron rod, having been passed through loops at the ends of two weighted cords and attached by cords or tapes to another rod placed in the groove of the roller, must be fixed in the manner shown in fig. 47A.




FIG. 47A.

Addenda

The bunches of threads must now be tied to the iron rod as evenly as possible, but in order to do this the back roller must be fixed temporarily so that it cannot turn as the threads are pulled and firmly tied. When the warp is quite evenly tied to the rod the back roller can be released, a little weight put in the weight-box to give some tension to the warp, and the front roller being turned the rod CC can take the place of rod BB, and the warp will be fixed to the cloth roller ready for weaving. An examination of fig. 47B will explain the method of fixing the rod C in the groove of the roller—A being the warp and C and B the respective rods.




FIG. 47B.

The
HAMPSHIRE · HOUSE
WORKSHOPS · LTD

Makers of
HANDICRAFT
FURNITURE

Sole Makers of
THE HOOPER LOOMS
AND ACCESSORIES

Prices on application

The Hampshire House Building
Guild undertakes BUILDING,
Repairs & Decorating Work

6 · UPPER · MALL · HAMMERSMITH
W · 6

Telephone : 474 Hammersmith

The
London School of Weaving

SUPPLIES LOOMS, SPINNING
WHEELS, *and all Weaving Appliances*

LESSONS given in Spinning, Weaving,
Tapestry, Carpet, Rug, and Lace making,
and orders for all kinds of hand-
woven materials promptly and carefully
executed.

13 Old Cavendish Street, Cavendish Square, W. 1
(Off Oxford Street, near Oxford Circus)

ESTABLISHED 1898

Tel.: MAYFAIR 6595

**WEAVING WITH SMALL
APPLIANCES**

By LUTHER HOOPER. In three books. Each in
foolscap 4to, illustrated with colour plates and black-
and-white drawings. 7s. 6d. net.

1. THE WEAVING BOARD. The appliances for
weaving and instructions for using them are described.

2. TABLET WEAVING. Shows how many kinds of
beautiful laces and braids can be woven by this simple
method.

3. TABLE LOOM WEAVING. Fully describes and
illustrates this little known art.

SIR ISAAC PITMAN & SONS, LIMITED

DATE OF ISSUE

This book must be returned
within 3, 7, 14 days of its issue. A
fine of ONE ANNA per day will
be charged if the book is overdue.

--	--

